Rodriguez Residence — Oak Valley Estates Lot 5
Wall Finish Square-Footage Takeoff

Group	Room	No	Ht	Perim	Gross SF	Openings SF	Net SF	Finish	Paint	Plaster	Micro	Tile	Conc tile	Cabinets	Exposed	Slat wall	Rammed
LOWER	Lower	105	10	170.4	1704	36	1668	Plaster		1668							
LOWER	Lower Bath	106	10	26.1	261	24	237	Micro cement			237						
LOWER	Lower AV	107	10	23.7	237	24	213	Paint	213								
LOWER	Lower Hall	110	10	31.2	312	0	312	Concrete tile					312				
LOWER	Lower Gun	113	9	76.7	690	24	666	Slat wall								666	
LOWER	Lower Range	115	9	128.7	1158	0	1158	Exposed							1158		
MAIN - Living	Office	77	10	64.6	646	36	610	Plaster		610							
MAIN - Living	Office Closet	78	10	34.1	341	24	317	Paint	317								
MAIN - Living	Office Bath	79	10	31.4	314	24	290	Micro cement			290						
MAIN - Living	Office Shower	79a	10	11.8	118	0	118	Tile				118					
MAIN - Living	Dining	80	10	76.0	760	60	700	Plaster		700							
MAIN - Living	Living	81	10	474.8	4748	108	0	Glass (no wall)									
MAIN - Living	Entry	82	18	102.7	1849	48	1801	Plaster		1801							
MAIN - Living	Coat	83	10	20.7	207	24	183	Paint	183								
MAIN - Living	Powder	85	10	27.2	272	24	248	Micro cement			248						
MAIN - Kitchen	Kitchen	86	10	130.8	1308	96	1212	Cabinets						1212			
MAIN - Kitchen	Pantry	87	10	90.1	901	24	877	Paint	877								
MAIN - Kitchen	Stair	88	10	51.7	517	24	493	Concrete tile					493				
MAIN - Kitchen	Pantry Stg	90	10	23.0	230	24	206	Paint	206								
MAIN - ADU	ADU Bed	91	10	61.5	615	60	555	Plaster		555							
MAIN - ADU	ADU Closet	92	10	36.2	362	24	338	Plaster		338							
MAIN - ADU	ADU Bath	94	10	44.0	440	24	416	Micro cement			416						
MAIN - ADU	ADU Shower	94a	10	14.1	141	0	141	Tile				141					
MAIN - ADU	ADU Living	95	10	69.7	697	60	637	Plaster		637							
MAIN - ADU	ADU Kitchen	96	10	56.2	562	24	538	Plaster		538							
GARAGE	Garage	97	10	190.2	1902	744	1158	Paint	1158								
UPPER - Primary	Primary	109	12	115.4	1385	96	789	Plaster		789							
UPPER - Primary	Primary Bath	104	10	58.7	587	24	563	Micro cement			563						
UPPER - Primary	Primary Shower	116	10	65.0	650	0	650	Tile				650					
UPPER - Primary	Primary Closet	117	10	67.6	676	72	604	Cabinets						604			
UPPER - Primary	Primary WC-1	120	10	18.5	185	24	161	Micro cement			161						
UPPER - Primary	Primary WC-2	121	10	18.4	184	24	160	Micro cement			160						
UPPER - Utility	Laundry	118	10	48.3	483	48	435	Micro cement			435						
MECHANICAL	Mech	84	10	40.7	407	0	407	Paint	407								
MECHANICAL	Mech 2	89	10	23.8	238	0	238	Paint	238								
MECHANICAL	ADU Mech	93	10	18.9	189	0	189	Paint	189								
MECHANICAL	Upper Mechanical	119	10	28.1	281	0	281	Paint	281								
RAMMED EARTH	Rammed Earth Exterior	RE-EXT			800	0	800	Rammed Earth									800
RAMMED EARTH	Rammed Earth Interior	RE-INT			1000	0	1000	Rammed Earth									1000
	TOTALS BY FINISH (SF)								**4069**	**7636**	**2510**	**909**	**805**	**1816**	**1158**	**666**	**1800**
	GRAND TOTAL ALL FINISHES							**21369**									