ARTISTIC WALL TEXTURES

ESTIMATE

08/05/2026

PROJECT: RODRIGUEZ ~ KANARAVILLE
CONTRACTOR: CRAIG ENGEL

DESCRIPTION	SF	Labor/ materials	TOTAL
LOWER BATH: Concretta microcement plaster. Labor $16/SF & materials $3.60/SF.	237 SF	$19.60/SF	$4,645.20
OFFICE BATH: Concretta microcement plaster. Labor $16/SF & materials $3.60/SF.	290 SF	$19.60/SF	$5,684.00
MAIN AREA POWDER: Concretta microcement plaster. Labor $16/SF & materials $3.60/SF.	248 SF	$19.60/SF	$4,860.80
MAIN ADU BATH: Concretta microcement plaster. Labor $16/SF & materials $3.60/SF.	416 SF	$19.60/SF	$8,153.60
PRIMARY BATH: Concretta microcement plaster. Labor $16/SF & materials $3.60/SF.	563 SF	$19.60/SF	$11,034.80
PRIMARY WC - 1: Concretta microcement plaster. Labor $16/SF & materials $3.60/SF.	161 SF	$19.60/SF	$3,155.60
PRIMARY WC - 2: Concretta microcement plaster. Labor $16/SF & materials $3.60/SF.	162 SF	$19.60/SF	$3,175.20
LAUNDRY: Concretta microcement plaster. Labor $16/SF & materials $3.60/SF.	435 SF	$19.60/SF	$8,526.00
RAMMED EARTH - EXT $30/sf labor. $4.50 materials Base primer / base plaster / horizontal pattern 2nd coat plaster / velature glaze gray / Stain Shield sealer.	800 SF	$34.50/sf	$27,600.00
RAMMED EARTH - INT $30/sf labor. $4.50 materials Base primer / base plaster / horizontal pattern 2nd coat plaster / velature glaze gray / Stain Shield sealer.	1,000 SF	$34.50/sf	$34,500.00

(435) 467-0700
ArtisticWallTextures@gmail.com
1743 W. Green Valley Drive
St. George, UT 84770

*** Travel time & fuel:** 1 day of travel both ways = 1.50 hours @ $50/hour = $75. Plus fuel @ $50/round trip.	$125/trip	30 trips	$3,750.00
Initial consultation / samples	3	$150	$450.00
Total:			**$115,535.20**
DEPOSIT:			

TERMS: A 50% deposit is required to calendar the job and purchase materials. Balance due upon completion.

*Subject to change +/-.

Contractor to provide boom or scissor lift for 26’ height ext/int. Walls.
Contractor to have exterior wall smooth browncoated. Interior wall level 4 smooth and primed.

Pricing is good for 120 days / subject to change upon hard measure.

(435) 467-0700
ArtisticWallTextures@gmail.com
1743 W. Green Valley Drive
St. George, UT 84770