Quote: 2597 / Date: 4/13/2026

D4 Electric and Solar
P.O. Box 957
Colorado City, AZ
86021, US
(435) 879-3007

Prepared By:
Darcey Dockstader
(435) 817-6796
ddock@d4electrical.com

Project: **Rac Development - Rodriguez Residence - Kanarraville, UT - Solar Fence/Vault**

Scope of Work

General Scope

- All labor, supervision, tools, and standard installation equipment
- Coordination with GC, owner, and utility (Rocky Mountain Power)
- NEC-compliant installation and labeling
- Startup, testing, and commissioning of system

Solar DC Wiring

- Pull and install DC conductors from solar fence array to vault (using existing conduit)
- Termination of DC conductors at inverter inputs
- Installation of required DC disconnects, fusing, and overcurrent protection
- String testing, verification, and documentation of voltage/current

Vault Equipment Installation (EG4 System)

- Installation of:
    - (1) EG4 FlexBOSS21 inverter
    - (3) EG4 16kWh batteries
- Battery mounting, interconnection, and communication wiring
- DC bus, breakers, and required protection components
- Equipment labeling per code
- System programming and commissioning

Service Entrance & Interconnection

- Metering coordination with utility
- Integration of EG4 system into service (ESS interconnection)
- Installation of required disconnects and interconnection equipment

Panic Room Dedicated Feed

- Installation of dedicated feed from vault to panic room panel (electrican is responsible of panic room panel and circuits)

- Underground feeder installation and terminations
- Independent system configuration per RFP intent

Permits & Inspections

- Solar permit procurement
- Coordination of inspections
- Utility interconnection coordination

Exclusions

By Others (Per RFP or Assumed)

- Main service equipment and panel distribution are **excluded from this proposal**. In the event that D4 is awarded the solar scope only, it is assumed that all service equipment, panel distribution, and associated house wiring will be provided and installed by the project's contracted electrician. D4 Solar's scope is limited to the solar and energy storage system installation and required interconnection only.
- Solar panel installation and mounting system
- Precast vault installation, excavation, and structural work
- Utility transformer installation and utility-side upgrades
- Underground trenching and conduit installation

Solar DC Wiring

	Quantity	Total Cost
Eging 705w bifacial module	30 ea	--
Solar Underground Wiring	150 ft	--
		$2,557.83

Vault Equipment

	Quantity	Total Cost
EG4 FlexBoss21 (built-in transfer switch)	1 ea	--
EG4 All Weather 16kWh Battery	3 ea	--
		$26,252.16

Service Equipment

	Quantity	Total Cost
Solar AC Disconnect	1 ea	--
		$2,090.88

AC Wiring

	Quantity	Total Cost
Vault to Service	50 ft	--
Vault to Panic Room	200 ft	--

Quote: 2597 / Date: 4/13/2026

	Quantity	Total Cost
		$4,496.80

Misc

	Quantity	Total Cost
Residential Solar Design/Engineering/Permitting	1 ea	--
		$1,154.34

Notes

Optional Adders and things to consider

- Home backup redesign (for the ability to backup additional panels/circuits)
- Future proof design (things we can do to make it easier to expand laterd if desired)
- Remote monitoring setup (we will need wifi to the vault or purchase a cellular data program.

Summary

Subtotal	$38,249.44

$38,249

Accepted By .....

Date .....