RANDY FREI CONSTRUCTION, INC.
1028 North West Ridge Drive #A
St. George, UT 84770

Phone: 435.986.3993
Fax: 435.986.0440
Email: rafconstruction@infowest.com

Estimate

Name / Address
RAC CON CRAIG ENGEL

Date	Estimate #	Job #
12/15/2025	19643	OAK VALLEY 5

Includes All Materials and Labor:

Description	Qty	Cost	Total
MOBILIZATION / ADMINISTRATION / LAYOUT	1.00	4,000.00	4,000.00
FOOTINGS 18X12	402.00	26.00	10,452.00
FOOTINGS 30X12	293.00	34.37	10,070.41
INTERIOR FOOTINGS 18X12	57.00	22.00	1,254.00
INTERIOR FOOTINGS 30X12	94.00	29.00	2,726.00
SPREAD FOOTING 24X24X12	3.00	123.00	369.00
SPREAD FOOTING 30X30X12	2.00	167.00	334.00
SPREAD FOOTING 36X36X12	4.00	210.00	840.00
SPREAD FOOTING 42X42X12	6.00	270.00	1,620.00
SPREAD FOOTING 48X48X12	2.00	330.00	660.00
SPREAD FOOTING 60X60X12	9.00	490.00	4,410.00
SPOT FOOTING 36X36X12	2.00	330.00	660.00
SPOT FOOTING 42X42X12	1.00	415.00	415.00
SPOT FOOTING 48X48X12	1.00	500.00	500.00
SPOT FOOTING 60X60X12	2.00	700.00	1,400.00
FOOTING STEPS	0.00	75.00	0.00
ROUND WALLS	0.00	150.00	0.00
30" STEM WALL	406.00	12.50	5,075.00
13' X 8" FOUNDATION WALL	107.00	195.00	20,865.00
10' X 8" FOUNDATION WALL	236.00	135.00	31,860.00
CORNER CHARGE	31.00	35.00	1,085.00
WALL CORNER CHARGE	12.00	45.00	540.00
POPOUTS	1.00	125.00	125.00
BASEMENT FLOOR SLAB W # 3 REBAR MAT @ 24" O/C	2,181.00	6.70	14,612.70
FLOOR SLAB W # 3 REBAR MAT @ 24" O/C	2,600.00	6.70	17,420.00
SUSPENDED 8" FLOOR SLAB OVER 20 ga B DECKING W # 4 REBAR MAT	1,180.00	26.25	30,975.00
WATER CURE	3,937.00	0.50	1,968.50
GARAGE STEMWALLS	72.00	24.00	1,728.00
GARAGE W # 3 REBAR MAT @ 24" OC	1,766.00	6.65	11,743.90

Total

A finance charge of 2% per month (minimum of one dollar); an annual percentage rate of 24%; will be charged on all past due accounts before and after judgement. Accounts are due and payable 30 days from the invoice date following service. Customer agrees to pay attorney's fees and other costs incurred in collections. Estimate pricing are good for 45 days. Once services begin, both parties are agreeable to the terms above.

Signature

Signature

RANDY FREI CONSTRUCTION, INC.
1028 North West Ridge Drive #A
St. George, UT 84770

Phone: 435.986.3993
Fax: 435.986.0440
Email: rafconstruction@infowest.com

Estimate

Name / Address
RAC CON CRAIG ENGEL

Date	Estimate #	Job #
12/15/2025	19643	OAK VALLEY 5

Includes All Materials and Labor:

Description	Qty	Cost	Total
SOFT CUT CUTTING OF GARAGE SLAB	1.00	600.00	600.00
SUNKEN SHOWER	0.00	350.00	0.00
HOLD DOWNS STHD 10	6.00	30.00	180.00
HOLD DOWNS STHD 14	0.00	45.00	0.00
BOLTS FOR STRONG WALLS	4.00	250.00	1,000.00
CONCRETE PUMPING BASEMENT FOOTINGS	1.00	1,400.00	1,400.00
CONCRETE PUMPING BASEMENT WALLS	1.00	1,800.00	1,800.00
CONCRETE PUMPING BASEMENT SLAB	1.00	1,500.00	1,500.00
CONCRETE PUMPING MAIN SLAB	1.00	1,500.00	1,500.00
CONCRETE PUMPING SUSPENDED SLAB	1.00	1,100.00	1,100.00
WASH OUT PIT	5.00	350.00	1,750.00
GRADABLE FILL	1.00	650.00	650.00
SKID LOADER ROUGH GRADING	6.00	110.00	660.00
CONTRACTOR TO PROVIDE; COMPACTED PAD FOR FOOTINGS AND SLAB TO (+,-) 2" SUB GRADING TO(+,-) 1" AFTER PLUMBING, ANY TESTS, PRETREAT OF SLAB, ANY CURB CUTTING. CONTRACTOR TO PROVIDE HOUSE CORNERS HDA-2 HOLD DOWNS SUPPLIED AND INSTALLED BY FRAMER Htt5 PROVIDED AND INSTALLED BY OTHER OVER EXCAVATION OF FOOTINGS (IF NEEDED) AT ADDITIONAL COST			

Total

A finance charge of 2% per month (minimum of one dollar); an annual percentage rate of 24%; will be charged on all past due accounts before and after judgement. Accounts are due and payable 30 days from the invoice date following service. Customer agrees to pay attorney's fees and other costs incurred in collections. Estimate pricing are good for 45 days. Once services begin, both parties are agreeable to the terms above.

Signature

Signature

RANDY FREI CONSTRUCTION, INC.
1028 North West Ridge Drive #A
St. George, UT 84770

Phone: 435.986.3993
Fax: 435.986.0440
Email: rafconstruction@infowest.com

Estimate

Name / Address
RAC CON CRAIG ENGEL

Date	Estimate #	Job #
12/15/2025	19643	OAK VALLEY 5

Includes All Materials and Labor:

Description	Qty	Cost	Total
IF ROCK OR UNDIGABLE CONDITIONS ARE ENCOUNTERED ADDITIONAL COSTS WILL BE INCURRED			
SKID STEER			
IF HV/AC IN SLAB ADD $1500	0.00	1,500.00	0.00
BACK FILL PLUMBING	0.00	300.00	0.00
ESTIMATE GOOD FOR 45 DAYS			

A finance charge of 2% per month (minimum of one dollar); an annual percentage rate of 24%; will be charged on all past due accounts before and after judgement. Accounts are due and payable 30 days from the invoice date following service. Customer agrees to pay attorney's fees and other costs incurred in collections. Estimate pricing are good for 45 days. Once services begin, both parties are agreeable to the terms above.

Total $189,848.51

Signature

Signature