Estimate #802230

Salesperson: Nathan Johnson E-mail: nathan@d2bldg.com Phone: (435) 862-7375

Date Printed: 8/18/2025
Date Generated:8/18/2025

D2 Building Solutions
5099 Wheeler Way
Hurricane, UT 84737
Phone: (435) 688-1337

Customer
RAC Inc.
1267 N 1390 W
St George, UT 84770
Phone: (435) 229-7360

Project Address
Oak Valley Estates Lot 5
Liberty lane
Kanaraville,

Base Estimate

Work Area	Description	R Value
Ceiling Area	Open Cell Foam	49
Exterior Walls	R-23 MESH & BLOW FIBERGLASS - HIGH PERFORMANCE INSULATION SYSTEM	R-23
Rim Joist	R-38 UnFaced Fiberglass Batt	R-38
Foam - Windows/Doors/Penetration & Cracks	Foam windows, doors, penetrations and cracks	
Basement-Furred Walls	R-15 MESH & BLOW FIBERGLASS - HIGH PERFORMANCE INSULATION SYSTEM	R-15
Fire Blocking	R-15 Rockwool Batt	R-15 Rock Wool
Knee Walls	R-19 Unfaced batts with FSK Air Barrier	R-19

Base Estimate Total $31,064.74

Additional Options/Upgrades

Work Area	Description	R Value	Upgrade Details
Ceiling Area	R-38 High Performance Conditioned Attic (HPCA) Owens Corning ProPink Complete L77	R-38	To upgrade the **Open Cell Foam** item **Add $563.30**
Exterior Walls	Closed Cell Foam	7	**Add $6,077.00**
Note: Adding 1" of Closed Cell Foam to the Exterior Walls, then Blowing Fiberglass to fill the cavity.			
Between Floors	R-38 Net & Blow Cellulose	R-38	**Add $6,605.00**
Sound Walls	R-15 MESH & BLOW FIBERGLASS - HIGH PERFORMANCE INSULATION SYSTEM	R-15	**Add $13.00**
Note: $10/Linear Ft. (Example; 10'x10' wall = $100)			
Sound Walls	R-23 MESH & BLOW FIBERGLASS - HIGH PERFORMANCE INSULATION SYSTEM	R-23 DP	**Add $17.00**
Note: $17/Linear Ft. (Example; 10'x10' wall = $170)			

To accept this proposal, please sign and date below. Quote expires in 30 days. Per our company policy, all invoice payments must be received within 30 days or interest charges of 1.5% of the invoiced amount will be assessed. This interest will accrue per month until paid in full.

* This quote is valid for 30 days.
* According to local standards and practices, any alteration or deviation from above specifications involving extra costs will be executed upon written or verbal change orders, and will become an extra charge over and above this quote. Prices quoted are good for thirty days. We reserve the right to adjust all quoted prices in the event of shortages, environmental impacts, freight surcharge increases, manufacturer price increases, or environmental regulations.
By signing I agree to pay all amount(s) owed within 30 days of when such amount(s) are incurred. I understand that it is my responsibility to provide my correct/updated information. I agree that interest will accrue on all past-due amounts at the rate of 18% per annum (1.5% per month) until paid in full. In the event any amount(s) is/are referred to a third party dept collection agency, I agree I will be responsible for a collection fee of up to 40% of the principal amount(s) owing as allowed by Utah Code Annotated, sec. 12-1-11, as well as interest, court costs, and reasonable attorney's fees. The terms of this paragraph shall apply to all amount(s) incurred by me or by any individual for whom I have legal responsibility whether such amount(s) are incurred today or after today.

Spray Foam Installation Disclaimer – Nominal Thickness
Spray foam insulation is applied based on nominal thickness, which represents the average installed depth over a given area. Due to the nature of spray application, surface irregularities, framing variations, and substrate conditions, minor fluctuations in thickness are common and expected.
Per industry standards, open cell acceptable variance installed thickness is ±1/2 inch. This tolerance range is recognized by spray foam manufacturers, industry associations, and building codes as being within normal installation practices.
While our installers are trained to meet specified R-values and coverage targets, exact uniform thickness at every point is not guaranteed nor required. The final insulation performance is based on the average application thickness, and localized deviations within the accepted range do not constitute a defect in workmanship or materials.
By approving this installation, the customer acknowledges an understanding of nominal thickness standards and the allowable variance in spray foam insulation applications.

Spray Foam Installation Disclaimer – Nominal Thickness
Spray foam insulation is applied based on nominal thickness, which represents the average installed depth over a given area. Due to the nature of spray application, surface irregularities, framing variations, and substrate conditions, minor fluctuations in thickness are common and expected.
Per industry standards, closed cell spray foam acceptable variance installed thickness is ±1/4 inch. This tolerance range is recognized by spray foam manufacturers, industry associations, and building codes as being within normal installation practices.
While our installers are trained to meet specified R-values and coverage targets, exact uniform thickness at every point is not guaranteed nor required. The final insulation performance is based on the average application thickness, and localized deviations within the accepted range do not constitute a defect in workmanship or materials.
By approving this installation, the customer acknowledges an understanding of nominal thickness standards and the allowable variance in spray foam insulation applications.

RAC Inc. - Authorized Signature Date