Bid #STG25-319
3376 E 380 St N
St George, UT 84790
(435) 466-1100
Facsimile 913-764-9933
www.bsmresidential.com

Customer:	RAC Inc. racinc19@gmail.com 435-229-7360	Date: Plan Date: Address:	9/10/2025 8/17/2025 TBD
Project:	Oak Valley Estates lot 5	Location:	Kannarville, 84742

SCOPE OF WORK: 092400 - Portland Cement Plastering

Acrylic color coat, over conventional cement coat. Lath: 1# 1" foam, 1" 20 gauge wire, double ply black paper, standard corners.
Soffit & fascia: Typical; 1" foam on soffit. Acrylic color coat over conventional cement coat.
Lids: 2-ply black paper and 1.75 metal lath. (Installed over OSB board or drywall which has been supplied & installed by the framing contractor). Acrylic color coat over conventional cement coat.
Rock: 1.5" 17 gauge wire and scratch for rock prep.
No courtyard, privacy or retaining walls included in this bid.

Project Total - Labor & Materials	**$57,850.00**
Option Add: Apply Master Wall dark colored acrylic finish on all Fascia and soffit with Sealer	**$2,400.00**
Option Add: Tyvek Commercial D	**$5,720.00**
Option Deduct: No Colored Acrylic Finish on 2893 sq.ft "Rammed Earth"	**-$3,500.00**

***EXCLUDES EIFS, RAINSCREEN, AND PEBBLE DASH AND/OR RAMMED EARTH FINISHES.**

IF ANY OF THE 'ADD' ITEMS ARE SELECTED, PLEASE BE SURE TO INITIAL NEXT TO THE SELECTED ITEM AND THEN INCLUDE THE PRICE ADDITION TO THE MAIN BID PRICE BELOW

STANDARD EXCLUSIONS

Excludes Courtyard, privacy, retaining or foundation walls, except as may be described above, unless bid & authorized at a later date.

Excludes any specialty finishes. Excludes Hauling off any Lath or Stucco debris. Excludes tarp and heating for winter conditions.

NOTES:

Bid with Masterwall Medium Sand Finish. Upgrade to TEXTURE OR SMOOTH BASE can be bid at later date

Scaffolding is to remain set till completion of our scope. Any scaffolding that needs to be disassembled and reassembled prior to completion will incur a fee.

TERMS AND CONDITIONS:

PROGRESSIVE BILLING MAY APPLY

All products sold come with the original manufacturer's warranty. Sipco-BSM makes no implied warranties about the goods sold. By accepting the goods accompanying this estimate, purchaser agrees to pay interest on any past due balances at the rate of 1.5% per month, together with all costs of collections, including reasonable attorney fees.

WE RESERVE THE RIGHT TO RE-MEASURE AT FRAME UP AND ADJUST THIS PRELIMINARY BID(+/-) DEPENDING ON ACTUAL.

1.Our payment terms are 40% of contract at lath install, 30% of contract at brown install and final 30% at color coat; due net 10 days from invoice. Finance charges of 1-1/2% will be charged on balances over 30 days. In the event of failure to pay this contract, Sipco-BSM will demand full payment plus interest, costs, late fees, attorney fees, recording fees, costs of a foreclosure report and such other reasonable fees and expenses, and any other remedy allowed under the laws of the State of Utah.

NOTICE TO OWNER:

Sipco-BSM is a supplier or subcontractor providing materials or labor on the aforementioned project under an agreement with Utah law will allow this supplier or subcontractor to file a lien against your property for materials or labor not paid for by your contractor. Prices are void if contract is not signed and returned within 14 days of date above.

ACCEPTANCE OF CONTRACT

The above prices and conditions are satisfactory and hereby accepted.

WARRANTY DISCLAIMER

All of our masons are fully insured and provide a 1 year limited warranty on their stucco installation. These labor warranties DO NOT cover any circumstances uncontrollable by the installer.

BSM is not responsible for water-proofing. Stucco products do allow minimal water penetration. Upon completion of all exterior projects, it is recommended that the customer caulk any areas of concern. These areas may include, but are not limited to: where stucco meets siding, stucco meets windows, or stucco meets any other non-masonry material. Hariline fractures are common with the installation of stucco. Follow manufacturer guidlines to use primer and elastomeric paint after installation.

Contract Price:	$57,850.00	BSM Residential	
Acceptance Date:		Rep: Josette Stubbs	
By:		Phone: (702) 755-1216	
Customer Name:		E-Mail: josette@bsmmasonry.com	

Phone:	Signature:
Title:	Approval Date: