
Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	A1	Monopitch	5	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:26:49 Page: 1
ID:SVpAuat2InILVCMm2PLOEizgeSK-bBp1rIXWn_X_faB6HGvyfWGM_hc4Box?f2MY?BzUlqa



Scale = 1:38.9

Plate Offsets (X, Y): [1:0-5-12,Edge], [5:0-1-9,0-2-0], [9:0-3-8,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.83	Vert(LL)	-0.33	7-9	>812	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.77	Vert(CT)	-0.55	7-9	>483	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.93	Horz(CT)	0.06	6	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 100 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W1:2x6 DF No.2, W4,W6:2x4 DF No.2
OTHERS 2x8 DF 2250F 1.6E or 2x8 DF SS *Except* SB1:2x4 DF Stud

REACTIONS (lb/size) 6=1081/0-5-8, (min. 0-1-8), 12=1008/ Mechanical
Max Horiz 12=54 (LC 9)
Max Uplift 6=-187 (LC 10), 12=-174 (LC 6)

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 4-6

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-3500/1455, 2-3=-3256/1361, 3-4=-3248/1362, 5-6=-292/159
BOT CHORD 9-10=-295/789, 8-9=-1406/3492, 7-8=-1406/3492, 6-7=-1306/3250
WEBS 1-9=-1138/2768, 2-9=-511/294, 4-7=0/289, 4-6=-3153/1301, 1-12=-1332/561

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 187 lb uplift at joint 6 and 174 lb uplift at joint 12.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	A2	Half Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:26:49 Page: 1
ID:pSc3xHxB7Kwdb_FkrywZxlzgeSF-bBp1rIXWn_X_faB6HGvyfWGQjhdXBoG?f2MY?BzUlqa



Scale = 1:41

Plate Offsets (X, Y): [1:0-5-12,Edge], [3:0-2-0,Edge], [11:0-2-8,0-1-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.59	Vert(LL)	-0.30	9-11	>877	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.74	Vert(CT)	-0.51	9-11	>520	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.91	Horz(CT)	0.06	7	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 102 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W1:2x6 DF No.2
OTHERS 2x8 DF 2250F 1.6E or 2x8 DF SS

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 5-6.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 4-8

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 7=1081/0-5-8, (min. 0-1-8), 14=1008/ Mechanical
Max Horiz 14=53 (LC 9)
Max Uplift 7=-187 (LC 6), 14=-174 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-3407/1416, 2-3=-3394/1419, 3-4=-3386/1420, 4-5=-927/402
BOT CHORD 11-12=-285/765, 10-11=-1367/3398, 9-10=-1367/3398, 8-9=-1364/3388, 7-8=-319/862
WEBS 1-11=-1112/2705, 2-11=-537/301, 4-8=-2548/1060, 5-8=-242/748, 5-7=-1501/613, 1-14=-1322/556

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 187 lb uplift at joint 7 and 174 lb uplift at joint 14.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	A3	Half Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:26:50 Page: 1
ID:SmKbSO5il0Rw1q92YT8NQHzgeS3-3ONP2eY9YIfrGkmIqzQBBjocl5y0wKE9ui56XdzUlqZ



Scale = 1:41

Plate Offsets (X, Y): [1:0-5-4,0-3-0], [2:0-0-8,0-1-12], [11:0-4-0,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.51	Vert(LL)	-0.27	8-10	>969	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.79	Vert(CT)	-0.48	8-10	>557	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.60	Horz(CT)	0.08	7	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 100 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W1:2x6 DF No.2
OTHERS 2x8 DF 2250F 1.6E or 2x8 DF SS *Except* SB1:2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 2-11, 3-8

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 7=1081/0-5-8, (min. 0-1-8), 12=1008/ Mechanical
Max Horiz 12=48 (LC 9)
Max Uplift 7=-187 (LC 6), 12=-174 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-12=-275/742, 1-2=-980/383, 2-3=-3476/1385, 3-4=-1821/751, 4-5=-1815/752
BOT CHORD 10-12=-1429/3453, 9-10=-1463/3531, 8-9=-1463/3531, 7-8=-675/1768
WEBS 2-12=-2530/1117, 2-10=0/281, 3-8=-1783/804, 5-8=-174/592, 5-7=-1987/789, 1-12=-1279/541

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 187 lb uplift at joint 7 and 174 lb uplift at joint 12.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	A4	Half Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:26:50 Page: 1
ID:2SAuOAFU?JCxjzEkMPOf_EzgeRr-3ONP2eY9YIfrGkmIqzQBBjodG5y?wJI9ui56XdzUlqZ



Scale = 1:40.7

Plate Offsets (X, Y): [1:0-5-4,0-3-0], [2:0-0-12,0-1-12], [6:Edge,0-1-8], [11:0-4-0,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.48	Vert(LL)	-0.27	8-10	>974	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.79	Vert(CT)	-0.48	8-10	>557	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.66	Horz(CT)	0.08	7	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 100 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W1:2x6 DF No.2
OTHERS 2x8 DF 2250F 1.6E or 2x8 DF SS *Except* SB1:2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 2-11, 5-7

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 7=1081/0-5-8, (min. 0-1-8), 12=1008/ Mechanical
Max Horiz 12=47 (LC 9)
Max Uplift 7=-187 (LC 6), 12=-174 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-12=-290/769, 1-2=-927/365, 2-3=-3405/1368, 3-4=-3396/1369, 4-5=-2559/1061
BOT CHORD 10-12=-1333/3240, 9-10=-1491/3622, 8-9=-1491/3622, 7-8=-991/2519
WEBS 2-12=-2379/1043, 2-10=0/332, 4-10=-260/207, 4-8=-1120/515, 5-8=-105/424, 5-7=-2539/1027, 1-12=-1267/533

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 187 lb uplift at joint 7 and 174 lb uplift at joint 12.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	A5	Half Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:26:50 Page: 1
ID:PQ_nRuJdqrqEpk6h9y_qhIzgeRm-3ONP2eY9YIfrGkmIqzQBBjoWs5yKwF39ui56XdzUlqZ



Scale = 1:40

Plate Offsets (X, Y): [1:0-5-12,Edge], [4:0-3-8,Edge], [8:0-3-8,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.95	Vert(LL)	-0.32	6-8	>821	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.77	Vert(CT)	-0.54	6-8	>490	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.93	Horz(CT)	0.06	5	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 100 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W1:2x6 DF No.2, W6:2x4 DF No.2
OTHERS 2x8 DF 2250F 1.6E or 2x8 DF SS *Except* SB1:2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 3-5

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 5=1081/0-5-8, (min. 0-1-8), 11=1008/ Mechanical
Max Horiz 11=48 (LC 9)
Max Uplift 5=-187 (LC 6), 11=-174 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-3523/1469, 2-3=-3193/1325, 4-5=-309/169
BOT CHORD 8-9=-290/786, 7-8=-1418/3515, 6-7=-1418/3515, 5-6=-1267/3171
WEBS 1-8=-1155/2794, 2-8=-516/296, 2-6=-337/156, 3-6=0/293, 3-5=-3048/1248, 1-11=-1329/560

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 187 lb uplift at joint 5 and 174 lb uplift at joint 11.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	A6	Half Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:26:50 Page: 1
ID:lOngUbNmeOSWvW?fyWa?OLzgeRh-3ONP2eY9YIfrGkmIqzQBBjoYD5_swG19ui56XdzUlqZ



Scale = 1:38.9

Plate Offsets (X, Y): [1:0-5-12,Edge], [9:0-2-8,0-1-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.80	Vert(LL)	-0.27	7-9	>970	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.67	Vert(CT)	-0.44	7-9	>601	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.87	Horz(CT)	0.05	6	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 99 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W1:2x6 DF No.2
OTHERS 2x8 DF 2250F 1.6E or 2x8 DF SS

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 4-6

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 6=1081/0-5-8, (min. 0-1-8), 12=1008/ Mechanical
Max Horiz 12=47 (LC 9)
Max Uplift 6=-186 (LC 6), 12=-174 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-3261/1366, 2-3=-3518/1442, 3-4=-3489/1432
BOT CHORD 9-10=-264/729, 8-9=-1314/3253, 7-8=-1314/3253, 6-7=-992/2372
WEBS 1-9=-1085/2607, 2-9=-592/311, 2-7=-90/266, 3-7=-373/215, 4-7=-405/1195, 4-6=-2393/1064, 1-12=-1304/546

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 186 lb uplift at joint 6 and 174 lb uplift at joint 12.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	A7	Half Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:26:51 Page: 1
ID:aX8xleSXEEDgdRSpImhPdczgeRb-XaxoGzZnIbniuuLVOhxQkxLm0VPhfiiI7Mrf43zUlqY



Scale = 1:41.4

Plate Offsets (X, Y): [4:0-3-8,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.61	Vert(LL)	-0.11	8-10	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.38	Vert(CT)	-0.18	8-10	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.72	Horz(CT)	0.01	6	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 98 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 6=-29/0-5-8, (min. 0-1-8), 7=1465/0-5-8, (min. 0-1-9), 11=720/ Mechanical
Max Horiz 11=55 (LC 7)
Max Uplift 6=-51 (LC 20), 7=-252 (LC 6), 11=-126 (LC 10)
Max Grav 6=44 (LC 10), 7=1465 (LC 1), 11=720 (LC 1)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-11=-670/308, 1-2=-1704/700, 2-3=-1348/561, 3-4=-1377/583, 4-5=-256/689
BOT CHORD 9-10=-649/1699, 8-9=-649/1699, 7-8=-689/316
WEBS 1-10=-677/1616, 2-10=-356/215, 2-8=-373/152, 3-8=-394/225, 5-7=-764/318, 4-7=-1127/533, 4-8=-870/2142

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 126 lb uplift at joint 11, 51 lb uplift at joint 6 and 252 lb uplift at joint 7.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	A8	Half Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:26:51 Page: 1
ID:HkH9QtnTtXdrNa0?NxgkElzgeRA-XaxoGzZnIbniuuLVOhxQkxLh0VJPfhdI7Mrf43zUlqY



Scale = 1:54.2

Plate Offsets (X, Y): [3:0-2-0,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.93	Vert(LL)	-0.37	13-14	>818	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.72	Vert(CT)	-0.61	13-14	>498	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.98	Horz(CT)	0.08	9	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 135 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud
OTHERS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 8-10, 6-10, 2-15

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 9=-656/0-5-8, (min. 0-1-8), 10=2614/0-5-8, (min. 0-2-13), 15=1039/ Mechanical
Max Horiz 15=54 (LC 7)
Max Uplift 9=-656 (LC 1), 10=-449 (LC 6), 15=-181 (LC 6)
Max Grav 9=149 (LC 10), 10=2614 (LC 1), 15=1039 (LC 1)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-15=-253/109, 2-3=-3760/1136, 3-4=-3753/1137, 4-5=-2193/654, 5-6=-2220/670, 6-17=-800/2756, 7-17=-800/2756, 7-18=-800/2756, 8-18=-800/2756, 8-9=-168/659
BOT CHORD 14-15=-928/3237, 13-14=-928/3238, 12-13=-1086/3754, 11-12=-1086/3754
WEBS 5-11=-371/160, 8-10=-2887/875, 7-10=-508/209, 6-11=-661/2390, 6-10=-2976/924, 2-15=-3089/936, 4-11=-1623/506, 2-13=-163/531

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 26-8-12, Corner (3) 26-8-12 to 30-8-12 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 181 lb uplift at joint 15, 656 lb uplift at joint 9 and 449 lb uplift at joint 10.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	A9	Half Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:26:51 Page: 1
ID:xsazeQY_1tZvQGK6agIWHbzgeQB-XaxoGzZnIbniuuLVOhxQkxLg9VHQfhDI7Mrf43zUlqY



Scale = 1:54.2

Plate Offsets (X, Y): [11:0-2-4,0-2-4]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.98	Vert(LL)	-0.43	10-11	>709	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.84	Vert(CT)	-0.70	10-11	>432	180		
TCDL	12.0	Rep Stress Incr	YES	WB	1.00	Horz(CT)	0.06	8	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 132 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF 2100F 1.8E *Except* T2:2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W2,W4:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 6-8, 4-8

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 7=-624/0-5-8, (min. 0-1-8), 8=2576/0-5-8, (min. 0-2-12), 13=1046/ Mechanical
Max Horiz 13=52 (LC 7)
Max Uplift 7=-624 (LC 1), 8=-441 (LC 6), 13=-182 (LC 6)
Max Grav 7=140 (LC 10), 8=2576 (LC 1), 13=1046 (LC 1)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-13=-971/337, 1-14=-3850/1161, 2-14=-3843/1162, 2-3=-3027/894, 3-4=-2977/878, 4-15=-788/2684, 5-15=-788/2684, 5-16=-788/2684, 6-16=-788/2684, 6-7=-161/623
BOT CHORD 12-13=-49/348, 11-12=-49/348, 10-11=-1115/3841, 9-10=-229/721, 8-9=-229/721
WEBS 1-11=-1081/3542, 2-11=-499/232, 2-10=-835/280, 3-10=-467/199, 6-8=-2794/861, 5-8=-544/224, 4-8=-3574/1127, 4-10=-624/2375


NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 26-8-12, Corner (3) 26-8-12 to 30-8-12 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 182 lb uplift at joint 13, 624 lb uplift at joint 7 and 441 lb uplift at joint 8.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	A10	Half Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:26:51 Page: 1
ID:AadNXVfdwehd0eXqb3yd8UzgeQ2-XaxoGzZnIbniuuLVOhxQkxLhbVl1fjFl7Mrf43zUlqY





Scale = 1:54.2

Plate Offsets (X, Y): [7:0-2-0,Edge], [8:0-3-8,0-1-8], [16:0-3-8,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.95	Vert(LL)	-0.90	13-15	>407	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.80	Vert(CT)	-1.48	13-15	>249	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.87	Horz(CT)	0.22	10	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 137 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2 *Except* T1:2x4 DF 2100F 1.8E
BOT CHORD 2x4 DF 2100F 1.8E
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 2-18, 8-10, 6-11

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 10=1499/0-5-8, (min. 0-1-10), 18=1499/ Mechanical
Max Horiz 18=51 (LC 7)
Max Uplift 10=-258 (LC 6), 18=-259 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-6510/1949, 3-4=-7284/2180, 4-5=-7270/2187, 5-6=-6078/1837, 6-7=-3667/1127, 7-8=-3667/1127
BOT CHORD 17-18=-1207/4176, 16-17=-1207/4176, 15-16=-1899/6505, 14-15=-2135/7297, 13-14=-2135/7297, 12-13=-2132/7270, 11-12=-1782/6078, 10-11=-1072/3667
WEBS 2-18=-4148/1253, 3-15=-239/817, 8-10=-3745/1122, 5-12=-1264/371, 6-12=-100/487, 6-11=-2557/752, 8-11=-213/884, 2-16=-724/2436, 3-16=-651/237

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 26-8-12, Corner (3) 26-8-12 to 30-8-12 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 259 lb uplift at joint 18 and 258 lb uplift at joint 10.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	A11	Half Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:26:53 Page: 1
ID:FHcJN3S1Nw?GwnZWTw85pPzgeP0-Ty2Yhfa1qD1Q8CVtW6zupMQ13lz37cKbagKm8yzUlqW



Scale = 1:54.2

Plate Offsets (X, Y): [2:0-3-12,0-2-12], [3:0-5-0,0-2-8], [5:0-3-0,Edge], [6:0-3-8,0-1-8], [7:Edge,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.96	Vert(LL)	-0.96	11-13	>382	240	M18AHS	169/162
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.83	Vert(CT)	-1.57	11-13	>234	180	MT20	220/195
TCDL	12.0	Rep Stress Incr	YES	WB	0.90	Horz(CT)	0.24	8	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 135 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2 *Except* T2:2x4 DF 2100F 1.8E
BOT CHORD 2x4 DF 2100F 1.8E
WEBS 2x4 DF Stud *Except* W2:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 6-8, 5-9, 3-14, 2-15

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 8=1499/0-5-8, (min. 0-1-10), 15=1499/ Mechanical
Max Horiz 15=49 (LC 7)
Max Uplift 8=-258 (LC 6), 15=-259 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-15=-258/109, 1-16=-281/74, 2-16=-274/75, 2-3=-5084/1528, 3-4=-7635/2295, 4-17=-6613/1987, 5-17=-6613/1987, 5-6=-4105/1255
BOT CHORD 14-15=-1476/5076, 13-14=-2082/7140, 12-13=-2085/7132, 11-12=-2085/7132, 10-11=-2241/7635, 9-10=-1914/6503, 8-9=-1202/4105
WEBS 6-8=-4112/1228, 3-11=-207/528, 4-10=-1070/322, 5-10=-73/410, 5-9=-2531/752, 6-9=-197/839, 3-14=-2136/628, 2-14=-112/591, 2-15=-4939/1489

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 26-8-12, Corner (3) 26-8-12 to 30-8-12 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 259 lb uplift at joint 15 and 258 lb uplift at joint 8.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	A12	Half Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:26:53 Page: 1
ID:UYjaPmz?F8Q9bOMnUSPB3TzgeOL-Ty2Yhfa1qD1Q8CVtW6zupMQ1flx_7bEbagKm8yzUlqW



Scale = 1:54.2

Plate Offsets (X, Y): [1:0-2-12,0-2-12], [3:0-4-0,0-3-7], [7:0-4-0,0-3-4], [8:Edge,0-1-8], [11:0-6-12,Edge], [13:0-5-12,Edge], [14:0-3-8,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.92	Vert(LL)	-1.01	11-12	>363	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.90	Vert(CT)	-1.65	11-12	>222	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.97	Horz(CT)	0.21	9	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 134 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2 *Except* T2:2x4 DF 2100F 1.8E
BOT CHORD 2x4 DF 2100F 1.8E *Except* B1:2x4 DF No.2
WEBS 2x4 DF Stud *Except* W2:2x4 DF No.2

REACTIONS (lb/size) 9=1499/0-5-8, (min. 0-1-10), 15=1499/ Mechanical
Max Horiz 15=48 (LC 7)
Max Uplift 9=-258 (LC 6), 15=-260 (LC 6)

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 5-10
WEBS 2 Rows at 1/3 pts 7-9


MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-15=-1431/459, 1-16=-4391/1315, 2-16=-4384/1315, 2-3=-6643/1984, 3-4=-7858/2358, 4-5=-7218/2168, 5-6=-4603/1403, 6-7=-4603/1403
BOT CHORD 13-14=-1267/4381, 12-13=-1942/6664, 11-12=-2305/7858, 10-11=-2114/7192, 9-10=-1350/4603
WEBS 2-13=-695/2358, 3-13=-601/225, 2-14=-1100/382, 1-14=-1305/4324, 7-9=-4556/1360, 4-12=-271/137, 3-12=-377/1239, 4-11=-665/234, 5-11=-32/287, 5-10=-2683/791, 7-10=-161/748

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 26-8-12, Corner (3) 26-8-12 to 30-8-12 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 260 lb uplift at joint 15 and 258 lb uplift at joint 9.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	A13	Half Hip	1	1	Job Reference (optional)



Scale = 1:54.2

Plate Offsets (X, Y): [3:0-4-0,0-3-7], [7:0-5-0,0-1-12], [8:Edge,0-2-0], [13:0-4-8,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.98	Vert(LL)	-1.05	11-12	>348	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.91	Vert(CT)	-1.73	11-12	>212	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.86	Horz(CT)	0.23	9	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 133 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2 *Except* T2:2x4 DF 2100F 1.8E
BOT CHORD 2x4 DF 2100F 1.8E *Except* B1:2x4 DF No.2
WEBS 2x4 DF Stud *Except* W7:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 2-14, 7-9, 5-10

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 9=1499/0-5-8, (min. 0-1-10), 14=1499/ Mechanical
Max Horiz 14=47 (LC 7)
Max Uplift 9=-258 (LC 6), 14=-260 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-15=-5743/1695, 3-15=-5742/1696, 3-4=-7950/2385, 4-5=-7710/2312, 5-6=-5098/1549, 6-7=-5098/1549, 8-9=-254/110
BOT CHORD 13-14=-1045/3544, 12-13=-1709/5915, 11-12=-2334/7950, 10-11=-2263/7695, 9-10=-1498/5098
WEBS 3-13=-816/294, 2-13=-648/2367, 2-14=-3617/1144, 7-9=-5003/1492, 4-12=-434/191, 3-12=-644/2097, 4-11=-302/202, 5-10=-2671/786, 7-10=-136/681

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 26-8-12, Corner (3) 26-8-12 to 30-8-12 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 260 lb uplift at joint 14 and 258 lb uplift at joint 9.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	A14	Half Hip Girder	1	2	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:26:54 Page: 1
ID:8D4Fmx8rPxeOjlGQgKfwVwzgeMq-x9cwu?bfbW9HlL333pV7MZzE0iIos3JkpK3JgOzUlqV



Scale = 1:54.2

Plate Offsets (X, Y): [10:0-3-8,0-1-8], [19:0-3-8,0-1-8], [21:0-3-8,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.75	Vert(LL)	-0.98	16-18	>376	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.86	Vert(CT)	-1.54	16-18	>239	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	NO	WB	0.92	Horz(CT)	0.16	12	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	7.0										Weight: 318 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2 *Except* T2:2x4 DF 2100F 1.8E
BOT CHORD 2x6 DF 1950F 1.5E or 2x6 DF SS
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 3-1-14 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 12=2783/0-5-8, (min. 0-1-8), 22=2779/ Mechanical
Max Horiz 22=42 (LC 23)
Max Uplift 12=-501 (LC 4), 22=-502 (LC 4)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-22=-2523/464, 1-2=-5243/941, 2-3=-9167/1648, 3-4=-13244/2388, 4-5=-15609/2816, 5-6=-16150/2915, 6-23=-14876/2687, 7-23=-14876/2687, 7-8=-11769/2129, 8-9=-11769/2129, 9-10=-6806/1236, 10-11=-264/60
BOT CHORD 21-25=-920/5238, 20-25=-920/5238, 20-26=-1659/9338, 19-26=-1659/9338, 19-27=-2364/13244, 27-28=-2364/13244, 18-28=-2364/13244, 18-29=-2792/15609, 17-29=-2792/15609, 17-30=-2792/15609, 16-30=-2792/15609, 16-31=-2891/16150, 31-32=-2891/16150, 15-32=-2891/16150, 15-33=-2663/14876, 14-33=-2663/14876, 14-34=-2105/11769, 13-34=-2105/11769, 13-35=-1219/6806, 35-36=-1219/6806, 12-36=-1219/6806
WEBS 3-20=-1562/304, 2-20=-787/4384, 2-21=-2174/414, 1-21=-991/5486, 10-12=-6942/1248, 4-19=-1125/239, 3-19=-769/4164, 4-18=-469/2510, 5-18=-495/123, 5-16=-171/574, 6-15=-1353/343, 7-15=-152/805, 7-14=-3297/592, 9-14=-234/1454, 9-13=-5266/947, 10-13=-337/2044

NOTES
1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 2 rows staggered at 0-6-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
4) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
5) Provide adequate drainage to prevent water ponding.
6) All plates are MT20 plates unless otherwise indicated.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Refer to girder(s) for truss to truss connections.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 502 lb uplift at joint 22 and 501 lb uplift at joint 12.
11) "NAILED" indicates Girder: 3-10d (0.148" x 3") toe-nails per NDS guidelines.

LOAD CASE(S) Standard
1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15

Continued on page 2

Uniform Loads (lb/ft)


Vert: 1-11=-84, 12-22=-14

Concentrated Loads (lb)

Vert: 20=-171 (F), 14=-171 (F), 24=-171 (F), 25=-171 (F), 26=-171 (F), 27=-171 (F), 28=-171 (F), 29=-171 (F), 30=-171 (F), 31=-171 (F), 32=-171 (F), 33=-171 (F), 34=-171 (F), 35=-171 (F), 36=-171 (F)

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	A15	Monopitch	11	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:26:54 Page: 1
ID:s8g1sMG620vzwr1LFQqHv1zgeMg-x9cwu?bfbW9HIL333pV7MZzMCiMZsE2kpK3JgOzUlqV



Scale = 1:20.5

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.23	Vert(LL)	-0.22	4-5	>446	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.62	Vert(CT)	-0.37	4-5	>263	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.23	Horz(CT)	0.01	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 36 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=392/ Mechanical, 5=392/ Mechanical
Max Horiz 5=47 (LC 7)
Max Uplift 4=-65 (LC 10), 5=-71 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
BOT CHORD 4-5=-480/605
WEBS 2-5=-639/561, 2-4=-639/533

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 71 lb uplift at joint 5 and 65 lb uplift at joint 4.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	AJ1	Jack-Closed	14	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:26:54 Page: 1
ID:oFGMjE4iaP06dXOTtn3lotzgeMv-x9cwu?bfbW9HIL333pV7MZzH2iT6sHDkpK3JgOzUlqV



Scale = 1:30.8

0-5-8

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.56	Vert(LL)	-0.02	7-8	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.14	Vert(CT)	-0.03	7-8	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.03	Horz(CT)	0.00	7	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 36 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 3=560/0-4-0, (min. 0-1-8), 7=185/ Mechanical
Max Horiz 3=45 (LC 7)
Max Uplift 3=-146 (LC 6), 7=-26 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 26 lb uplift at joint 7 and 146 lb uplift at joint 3.
8) Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 3.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard


Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	AJ2	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:26:55 Page: 1
ID:oFGMjE4iaP06dXOTtn3lotzgeMv-QLAI6LcHMqH8NVeGdX0MunVSo6rqbkAu1_ptDqzUlqU



37-8-14 36-5-12

2-11-12



Scale = 1:35.1

0-5-8

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.56	Vert(LL)	-0.01	9	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.04	Vert(CT)	0.01	9	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.05	Horz(CT)	0.00	7	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 37 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 5-6.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 3=560/0-4-0, (min. 0-1-8), 7=185/ Mechanical
Max Horiz 3=46 (LC 7)
Max Uplift 3=-146 (LC 6), 7=-27 (LC 7)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 27 lb uplift at joint 7 and 146 lb uplift at joint 3.
8) Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 3.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	AJ3	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:26:55 Page: 1
ID:GSqkwZ5KLj8zFhzfRUa_K4zgeMu-QLAI6LcHMqH8NVeGdX0MunVSo6pLbkQu1_ptDqzUlqU



37-8-14 36-5-12



Scale = 1:39.8

0-5-8

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.56	Vert(LL)	-0.02	7-8	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.14	Vert(CT)	-0.03	7-8	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.03	Horz(CT)	0.00	7	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 36 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 5-6.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 3=560/0-4-0, (min. 0-1-8), 7=185/ Mechanical
Max Horiz 3=44 (LC 7)
Max Uplift 3=-146 (LC 6), 7=-27 (LC 7)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 27 lb uplift at joint 7 and 146 lb uplift at joint 3.
8) Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 3.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	AJ4	Monopitch	21	1	Job Reference (optional)



Scale = 1:23.6

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.07	Vert(LL)	n/a	-	n/a	999	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.02	Vert(CT)	n/a	-	n/a	999		
TCDL	12.0	Rep Stress Incr	YES	WB	0.04	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 10 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 2-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 2=0/ Mechanical, 3=167/ Mechanical
Max Horiz 2=115 (LC 1), 3=-115 (LC 1)
Max Uplift 3=-57 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 57 lb uplift at joint 3.
9) Non Standard bearing condition. Review required.
10) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	AJ5	Roof Special	1	1	Job Reference (optional)



Scale = 1:31.7

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.15	Vert(LL)	n/a	-	n/a	999	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.04	Vert(CT)	n/a	-	n/a	999		
TCDL	12.0	Rep Stress Incr	YES	WB	0.08	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 13 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 2-8-7 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 2=0/ Mechanical, 3=236/ Mechanical
Max Horiz 2=229 (LC 1), 3=-229 (LC 1)
Max Uplift 3=-81 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-256/230
WEBS 1-3=-256/272

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 81 lb uplift at joint 3.
9) Non Standard bearing condition. Review required.
10) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	B1	Monopitch	11	1	Job Reference (optional)



Scale = 1:38.3

0-2-12

Plate Offsets (X, Y): [6:0-2-15,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.34	Vert(LL)	-0.12	8-9	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.43	Vert(CT)	-0.20	8-9	>950	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.88	Horz(CT)	0.03	7	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 80 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W9:2x6 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 7=744/0-5-8, (min. 0-1-8), 11=975/0-5-8, (min. 0-1-8)
Max Horiz 11=60 (LC 9)
Max Uplift 7=-127 (LC 12), 11=-207 (LC 8)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1898/864, 3-4=-1830/866
BOT CHORD 8-9=-929/1893, 7-8=-884/1825
WEBS 2-11=-907/489, 4-7=-1754/834, 3-9=-399/261, 2-9=-921/1910


NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 207 lb uplift at joint 11 and 127 lb uplift at joint 7.
7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	B2	Half Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:26:56 Page: 1
ID:B2SdJ0ddmqQ9nnC6b_jnGFzgeAa-uXkgJhdw78P??fDSBEXbR_2h3W5iK2f1GeYQlHzUlqT





Scale = 1:39.2

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.27	Vert(LL)	-0.10	10-11	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.39	Vert(CT)	-0.17	10-11	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.61	Horz(CT)	0.03	8	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 82 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W11:2x6 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 6-7, 7-15.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 8=744/0-5-8, (min. 0-1-8), 13=975/0-5-8, (min. 0-1-8)
Max Horiz 13=61 (LC 9)
Max Uplift 8=-124 (LC 8), 13=-208 (LC 8)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1764/799, 3-4=-1981/933, 4-5=-1975/933, 5-6=-835/417
BOT CHORD 10-11=-868/1760, 9-10=-960/1977, 8-9=-392/790
WEBS 6-9=-158/428, 6-8=-1045/497, 2-13=-890/475, 5-9=-1206/581, 3-11=-436/271, 2-11=-874/1817

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 208 lb uplift at joint 13 and 124 lb uplift at joint 8.
7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
8) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	B3	Half Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:26:56 Page: 1
ID:9YgVbe40i51IhSlVhLmEE9zge0y-uXkgJhdw78P??fDSBEXbR_2fTW4ZK1e1GeYQlHzUlqT



Scale = 1:39.2

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.43	Vert(LL)	-0.12	7-8	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.46	Vert(CT)	-0.20	7-8	>937	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.67	Horz(CT)	0.03	6	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 80 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W9:2x6 DF No.2

REACTIONS (lb/size) 6=744/0-5-8, (min. 0-1-8), 10=975/0-5-8, (min. 0-1-8)
Max Horiz 10=61 (LC 9)
Max Uplift 6=-124 (LC 8), 10=-208 (LC 8)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-2051/945, 3-4=-1501/717
BOT CHORD 7-8=-1000/2044, 6-7=-718/1475
WEBS 4-6=-1514/721, 2-10=-923/504, 2-8=-977/2009, 3-8=-363/256, 3-7=-565/287

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 4-5, 5-12.
BOT CHORD Rigid ceiling directly applied.


MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 208 lb uplift at joint 10 and 124 lb uplift at joint 6.
7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
8) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	B4	Half Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:26:56 Page: 1
ID:p7wTgZRCt?hefv03txo1vHzge0V-uXkgJhdw78P??fDSBEXbR_2fqW5DK2M1GeYQlHzUlqT



Scale = 1:39.2

Plate Offsets (X, Y): [5:0-3-0,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.41	Vert(LL)	-0.12	7-8	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.42	Vert(CT)	-0.19	7-8	>965	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.63	Horz(CT)	0.03	6	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 80 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W9:2x6 DF No.2

REACTIONS (lb/size) 6=744/0-5-8, (min. 0-1-8), 10=975/0-5-8, (min. 0-1-8)
Max Horiz 10=61 (LC 9)
Max Uplift 6=-124 (LC 8), 10=-208 (LC 8)

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 4-5, 5-12.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 4-6


MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1839/840, 3-4=-1899/893, 5-6=-256/157
BOT CHORD 7-8=-907/1834, 6-7=-915/1890
WEBS 4-6=-1746/832, 2-10=-898/484, 3-8=-419/265, 2-8=-908/1873

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 208 lb uplift at joint 10 and 124 lb uplift at joint 6.
7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
8) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	B5	Half Hip	1	1	Job Reference (optional)



Scale = 1:39.2

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.25	Vert(LL)	-0.09	8	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.40	Vert(CT)	-0.16	7-8	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.57	Horz(CT)	0.03	7	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 79 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W9:2x6 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (4-1-7 max.): 4-6, 6-12.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 7=744/0-5-8, (min. 0-1-8), 10=975/0-5-8, (min. 0-1-8)
Max Horiz 10=62 (LC 11)
Max Uplift 7=-123 (LC 8), 10=-208 (LC 8)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-2044/914, 4-5=-2068/934
BOT CHORD 9-10=-810/1550, 8-9=-810/1550, 7-8=-777/1526
WEBS 4-8=-270/178, 2-10=-323/197, 3-8=-183/520, 3-10=-1658/868, 5-8=-204/574, 5-7=-1501/781

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 208 lb uplift at joint 10 and 123 lb uplift at joint 7.
7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
8) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	B6	Half Hip Girder	1	2	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:26:56 Page: 1
ID:_n8U7y_RHqMFZqyj0u5bEmzge?o-uXkgJhdw78P??fDSBEXbR_2fBW3EK3w1GeYQlHzUlqT



Scale = 1:39.2

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.39	Vert(LL)	-0.12	8-9	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.55	Vert(CT)	-0.18	8-9	>999	180		
TCDL	12.0	Rep Stress Incr	NO	WB	0.53	Horz(CT)	0.03	7	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	7.0										Weight: 186 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x6 DF No.2
WEBS 2x4 DF Stud *Except* W9:2x6 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (5-7-3 max.): 4-6, 6-14.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 12-13.

REACTIONS (lb/size) 7=1616/0-5-8, (min. 0-1-8), 12=1638/0-5-8, (min. 0-1-8)
Max Horiz 12=59 (LC 23)
Max Uplift 7=-280 (LC 4), 12=-338 (LC 4)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-2853/510, 4-5=-4989/915, 5-6=-363/93
BOT CHORD 11-12=-474/2851, 10-11=-474/2851, 9-10=-861/4906, 9-15=-772/4463, 15-16=-772/4463, 8-16=-772/4463, 8-17=-772/4463, 17-18=-772/4463, 7-18=-772/4463
WEBS 2-12=-310/80, 4-10=-2279/434, 4-9=-125/738, 5-8=-57/554, 5-9=-164/545, 5-7=-4245/744, 3-10=-138/845, 3-12=-2946/554


NOTES
1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc, 2x6 - 2 rows staggered at 0-9-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
4) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
5) Provide adequate drainage to prevent water ponding.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 280 lb uplift at joint 7 and 338 lb uplift at joint 12.
9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
10) Use Simpson Strong-Tie THJA26 (THJA26 on 2 ply, Left Hand Hip) or equivalent at 8-0-6 from the left end to connect truss(es) BJ1 (1 ply 2x4 DF), BJ11 (1 ply 2x4 DF) to front face of bottom chord.
11) Fill all nail holes where hanger is in contact with lumber.
12) "NAILED" indicates Girder: 3-10d (0.148" x 3") toe-nails per NDS guidelines.

LOAD CASE(S) Standard
1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-6=-84, 7-13=-14
Concentrated Loads (lb)
Vert: 9=-640 (F), 15=-224 (F), 16=-224 (F), 17=-224 (F), 18=-224 (F)

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	B6	Half Hip Girder	1	**2**	Job Reference (optional)

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	B7	Monopitch	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:26:57 Page: 1
ID:MdZxU9MBBlWQWFyhlfpOrPzgeAx-MkI3W1eYuRYscpoeIx2q_CbqkvRi3SZBVIIzHjzUlqS



Scale = 1:38.5

Plate Offsets (X, Y): [6:0-2-12,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.40	Vert(LL)	-0.10	8-9	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.40	Vert(CT)	-0.17	8-9	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.82	Horz(CT)	0.01	14	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 79 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud
OTHERS 2x8 DF 2250F 1.6E or 2x8 DF SS *Except* BL1:2x6 DF No.2

REACTIONS (lb/size) 13=936/0-4-0, (min. 0-1-8), 14=722/0-4-0, (min. 0-1-8)
Max Horiz 13=52 (LC 9)
Max Uplift 13=-197 (LC 6), 14=-125 (LC 10)

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-1650/784, 4-5=-1646/785, 7-14=-217/525
BOT CHORD 9-10=-835/1892, 8-9=-843/1877, 7-8=-737/1646
WEBS 3-10=-1728/783, 5-7=-1601/742, 2-13=-296/461, 10-13=-189/470, 2-13=-189/470

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Bearing at joint(s) 13, 14 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 197 lb uplift at joint 13 and 125 lb uplift at joint 14.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	B8	Half Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:26:57 Page: 1
ID:mvgmX?5GoURp6BvjTNeT3mzgdsc-MkI3W1eYuRYscpoelx2q_CbsLvSE3UuBVIlzHjzUlqS



Scale = 1:38.5

Plate Offsets (X, Y): [7:0-2-12,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.30	Vert(LL)	-0.09	10-11	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.37	Vert(CT)	-0.15	10-11	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.67	Horz(CT)	0.01	16	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 81 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud
OTHERS 2x8 DF 2250F 1.6E or 2x8 DF SS *Except* BL1:2x6 DF No.2

REACTIONS (lb/size) 15=936/0-4-0, (min. 0-1-8), 16=722/0-4-0, (min. 0-1-8)
Max Horiz 15=51 (LC 7)
Max Uplift 15=-197 (LC 6), 16=-123 (LC 6)

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 6-7.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-1817/863, 4-5=-1812/864, 5-6=-621/309, 8-16=-343/730
BOT CHORD 11-12=-776/1751, 10-11=-776/1751, 9-10=-817/1813, 8-9=-240/574
WEBS 6-9=-172/460, 6-8=-918/429, 3-12=-1650/760, 5-9=-1261/592, 2-15=-193/283, 12-15=-212/509, 2-15=-212/509


NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Bearing at joint(s) 15, 16 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 197 lb uplift at joint 15 and 123 lb uplift at joint 16.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	B9	Half Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:26:57 Page: 1
ID:nSjdgeWboxj?BQVGSWFSRxzgds4-MkI3W1eYuRYscpoeIx2q_CbpAvRD3TZBVIIzHjzUlqS





Scale = 1:38.5

Plate Offsets (X, Y): [5:0-2-12,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.50	Vert(LL)	-0.10	7-8	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.43	Vert(CT)	-0.17	7-8	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.76	Horz(CT)	0.01	13	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 79 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud
OTHERS 2x8 DF 2250F 1.6E or 2x8 DF SS *Except* BL1:2x6 DF No.2

REACTIONS (lb/size) 12=936/0-4-0, (min. 0-1-8), 13=722/0-4-0, (min. 0-1-8)
Max Horiz 12=49 (LC 9)
Max Uplift 12=-197 (LC 6), 13=-123 (LC 6)

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 4-5.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 3-9

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-1972/929, 6-13=-271/615
BOT CHORD 8-9=-879/1967, 7-8=-573/1302, 6-7=-576/1295
WEBS 4-6=-1382/643, 3-9=-1804/830, 4-8=-315/685, 2-12=-288/452, 9-12=-192/475, 2-12=-192/475

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Bearing at joint(s) 12, 13 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 197 lb uplift at joint 12 and 123 lb uplift at joint 13.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	B10	Half Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:26:57 Page: 1
ID:UesqKsqXRE7AwZ4SXhEn1dzgdrf-MkI3W1eYuRYscpoelx2q_CbpvvS53SsBVIlzHjzUlqS



Scale = 1:38.5

Plate Offsets (X, Y): [5:0-2-12,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.45	Vert(LL)	-0.10	7-8	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.38	Vert(CT)	-0.17	7-8	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.80	Horz(CT)	0.01	13	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 79 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud
OTHERS 2x8 DF 2250F 1.6E or 2x8 DF SS *Except* BL1:2x6 DF No.2

REACTIONS (lb/size) 12=936/0-4-0, (min. 0-1-8), 13=722/0-4-0, (min. 0-1-8)
Max Horiz 12=48 (LC 7)
Max Uplift 12=-197 (LC 6), 13=-123 (LC 6)

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 4-5.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-1813/852, 6-13=-195/490
BOT CHORD 8-9=-802/1808, 7-8=-772/1721, 6-7=-768/1726
WEBS 4-6=-1620/741, 3-9=-1693/779, 2-12=-214/319, 9-12=-207/502, 2-12=-207/502

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Bearing at joint(s) 12, 13 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 197 lb uplift at joint 12 and 123 lb uplift at joint 13.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	B11	Half Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:26:58 Page: 1
ID:jeQfol9qJDOT2Z3R39it56zgdrF-qwsRkNeAflgjEzNrIfZ3WP70NJmFoz4Kky1Xp9zUlqR



Scale = 1:38.5

Plate Offsets (X, Y): [6:0-2-12,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.34	Vert(LL)	-0.09	8-9	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.45	Vert(CT)	-0.18	8-9	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.55	Horz(CT)	0.00	13	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 78 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud
OTHERS 2x8 DF 2250F 1.6E or 2x8 DF SS *Except* BL1:2x6 DF No.2

REACTIONS (lb/size) 12=936/0-4-0, (min. 0-1-8), 13=722/0-4-0, (min. 0-1-8)
Max Horiz 12=47 (LC 7)
Max Uplift 12=-197 (LC 6), 13=-123 (LC 6)

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (4-3-7 max.): 4-6.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-1934/869, 4-5=-1956/888, 7-13=-242/566
BOT CHORD 8-9=-716/1530, 7-8=-656/1399
WEBS 4-8=-254/166, 5-8=-193/596, 5-7=-1399/701, 3-8=-111/453, 3-9=-1485/732, 9-12=-233/547, 2-12=-233/547

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Bearing at joint(s) 12, 13 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 197 lb uplift at joint 12 and 123 lb uplift at joint 13.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	B12	Half Hip Girder	1	2	Job Reference (optional)




Plate Offsets (X, Y): [6:0-5-4,0-3-0], [7:0-4-0,0-4-4]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.56	Vert(LL)	-0.14	8-9	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.73	Vert(CT)	-0.22	8-9	>844	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	NO	WB	0.76	Horz(CT)	0.00	19	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	7.0										Weight: 180 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x6 DF No.2
WEBS	2x4 DF Stud *Except* W11:2x6 DF No.2
OTHERS	2x6 DF No.2 *Except* BL2:2x8 DF 2250F 1.6E or 2x8 DF SS

BRACING

TOP CHORD	Structural wood sheathing directly applied or 5-3-8 oc purlins, except end verticals, and 2-0-0 oc purlins (5-1-12 max.): 4-6.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 11-12.

REACTIONS (lb/size) 13=1933/0-4-0, (min. 0-1-8), 19=2198/0-4-0, (min. 0-1-8)
Max Horiz 13=37 (LC 5)
Max Uplift 13=-396 (LC 4), 19=-415 (LC 4)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	2-3=-399/87, 3-4=-6212/1170, 4-5=-5920/1124, 5-6=-1634/314, 7-19=-361/1990, 6-19=-361/1990
BOT CHORD	9-10=-708/3755, 9-20=-1159/6217, 20-21=-1159/6217, 8-21=-1159/6217, 8-22=-1108/5920, 22-23=-1108/5920, 23-24=-1108/5920, 7-24=-1108/5920
WEBS	5-7=-4446/840, 3-9=-495/2721, 3-10=-3685/716, 5-8=-139/818, 4-8=-324/112, 2-13=-523/88, 10-13=-288/1581, 2-13=-288/1581, 6-19=-3665/698

NOTES

1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
   Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc, 2x6 - 2 rows staggered at 0-9-0 oc.
   Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
   Web connected as follows: 2x4 - 1 row at 0-6-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
4) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
5) Provide adequate drainage to prevent water ponding.
6) All plates are MT20 plates unless otherwise indicated.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Bearing at joint(s) 13, 19 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 396 lb uplift at joint 13 and 415 lb uplift at joint 19.
11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
12) Use Simpson Strong-Tie THJA26 (THJA26 on 2 ply, Right Hand Hip) or equivalent at 8-0-6 from the left end to connect truss(es) BJ5 (1 ply 2x4 DF), BJ12 (1 ply 2x4 DF) to back face of bottom chord.
13) Use Simpson Strong-Tie LUS24 (4-10d Girder, 2-10d Truss) or equivalent spaced at 2-0-0 oc max. starting at 10-0-12 from the left end to 16-0-12 to connect truss(es) BJ5 (1 ply 2x4 DF) to back face of bottom chord.
14) Use Simpson Strong-Tie LUS24 (4-10d Girder, 2-10d Truss) or equivalent at 16-5-12 from the left end to connect truss(es) BJ5 (1 ply 2x4 DF) to back face of bottom chord, skewed 0.0 deg.to the left, sloping 0.0 deg. down.

Continued on page 2


15) Fill all nail holes where hanger is in contact with lumber.

LOAD CASE(S) Standard

1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
   Uniform Loads (lb/ft)
   Vert: 1-6=-84, 11-12=-14, 7-10=-14
   Concentrated Loads (lb)
   Vert: 9=-879 (B), 20=-320 (B), 21=-320 (B), 22=-320 (B), 23=-320 (B), 24=-320 (B)

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	BJ1	Jack-Closed	5	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:26:58 Page: 1
ID:_n8U7y_RHqMFZqyj0u5bEmzge?o-qwsRkNeAflgjEzNrIfZ3WP7?zJqGo4hKky1Xp9zUlqR



Scale = 1:27.7

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.43	Vert(LL)	-0.03	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.19	Vert(CT)	-0.05	4-5	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.12	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 36 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=238/ Mechanical, 5=518/0-5-8, (min. 0-1-8)
Max Horiz 5=45 (LC 7)
Max Uplift 4=-31 (LC 6), 5=-134 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-5=-471/429

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 31 lb uplift at joint 4 and 134 lb uplift at joint 5.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	BJ2	Jack-Closed	2	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:26:58 Page: 1
ID:_n8U7y_RHqMFZqyj0u5bEmzge?o-qwsRkNeAflgjEzNrIfZ3WP73yJr9o43Kky1Xp9zUlqR



Scale = 1:28.2

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.18	Vert(LL)	0.00	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.07	Vert(CT)	-0.01	4-5	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.10	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 27 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 4=113/ Mechanical, 5=438/0-5-8, (min. 0-1-8)
Max Horiz 5=44 (LC 7)
Max Uplift 4=-14 (LC 10), 5=-126 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-5=-341/347

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 126 lb uplift at joint 5 and 14 lb uplift at joint 4.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	BJ3	Jack-Closed	2	1	Job Reference (optional)



Scale = 1:31.7

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.32	Vert(LL)	0.00	3-4	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.04	Vert(CT)	0.00	3-4	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.11	Horz(CT)	0.00	3	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 18 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 3-10-15 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 3=-63/ Mechanical, 4=418/0-5-8, (min. 0-1-8)
Max Horiz 4=42 (LC 7)
Max Uplift 3=-63 (LC 1), 4=-145 (LC 6)
Max Grav 3=49 (LC 6), 4=418 (LC 1)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-279/263
WEBS 1-4=-301/310, 2-4=-340/389

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 63 lb uplift at joint 3 and 145 lb uplift at joint 4.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	BJ4	Jack-Closed	2	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:26:59 Page: 1
ID:_n8U7y_RHqMFZqyj0u5bEmzge?o-I6QpxifoQ3oas7y1sM4I3dgFRjCAXYGTycn4MbzUlqQ



Scale = 1:23

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.07	Vert(LL)	n/a	-	n/a	999	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.02	Vert(CT)	n/a	-	n/a	999		
TCDL	12.0	Rep Stress Incr	YES	WB	0.04	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 10 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 1-10-15 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 2=0/ Mechanical, 3=159/ Mechanical
Max Horiz 2=103 (LC 1), 3=-103 (LC 1)
Max Uplift 3=-54 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 54 lb uplift at joint 3.
9) Non Standard bearing condition. Review required.
10) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	BJ5	Jack-Closed	6	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:26:59 Page: 1
ID:zaomvu7ykvRjbO5R2jEn5uzgdwS-I6QpxifoQ3oas7y1sM4I3dg7Hj6BXTtTycn4MbzUlqQ



Scale = 1:33.6

Plate Offsets (X, Y): [2:0-3-8,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.59	Vert(LL)	-0.09	4-5	>886	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.40	Vert(CT)	-0.16	4-5	>519	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.32	Horz(CT)	0.01	4	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 33 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud
OTHERS 2x6 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 4=334/ Mechanical, 7=417/0-4-1, (min. 0-1-8)
Max Horiz 7=38 (LC 9)
Max Uplift 4=-56 (LC 6), 7=-100 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
BOT CHORD 4-5=-323/406
WEBS 2-4=-414/354, 2-7=-606/471

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) This truss has been designed for greater of min roof live load of 20.0 psf or 2.00 times flat roof load of 30.0 psf on overhangs non-concurrent with other live loads.
4) Provide adequate drainage to prevent water ponding.
5) All plates are MT20 plates unless otherwise indicated.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Refer to girder(s) for truss to truss connections.
9) Bearing at joint(s) 7 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 56 lb uplift at joint 4 and 100 lb uplift at joint 7.
11) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	BJ6	Jack-Closed	1	1	Job Reference (optional)



Scale = 1:33.6

Plate Offsets (X, Y): [2:0-4-8,0-2-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.28	Vert(LL)	-0.02	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.18	Vert(CT)	-0.03	4-5	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.08	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 24 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud
OTHERS	2x6 DF No.2

REACTIONS (lb/size) 4=230/ Mechanical, 7=316/0-4-1, (min. 0-1-8)
Max Horiz 7=36 (LC 9)
Max Uplift 4=-39 (LC 10), 7=-84 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-7=-401/341

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.


MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

NOTES

1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) This truss has been designed for greater of min roof live load of 20.0 psf or 2.00 times flat roof load of 30.0 psf on overhangs non-concurrent with other live loads.
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Bearing at joint(s) 7 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 39 lb uplift at joint 4 and 84 lb uplift at joint 7.
10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	BJ7	Jack-Closed	1	1	Job Reference (optional)



Scale = 1:33.3

Plate Offsets (X, Y): [2:0-4-8,0-2-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.23	Vert(LL)	0.00	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.05	Vert(CT)	0.00	4-5	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.02	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 16 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud
OTHERS	2x6 DF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied or 3-1-15 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=126/ Mechanical, 7=224/0-4-1, (min. 0-1-8)
Max Horiz 7=35 (LC 9)
Max Uplift 4=-20 (LC 10), 7=-70 (LC 6)
Max Grav 4=126 (LC 1), 7=251 (LC 16)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES

1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) This truss has been designed for greater of min roof live load of 20.0 psf or 2.00 times flat roof load of 30.0 psf on overhangs non-concurrent with other live loads.
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Bearing at joint(s) 7 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 20 lb uplift at joint 4 and 70 lb uplift at joint 7.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	BJ8	Jack-Closed	1	1	Job Reference (optional)



Scale = 1:39.5

Plate Offsets (X, Y): [2:0-4-8,0-2-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.23	Vert(LL)	0.00	5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.01	Vert(CT)	0.00	5	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.01	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 11 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud
OTHERS	2x6 DF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied or 1-7-7 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=51/ Mechanical, 7=148/0-4-1, (min. 0-1-8)
Max Horiz 7=34 (LC 9)
Max Uplift 4=-5 (LC 10), 7=-58 (LC 6)
Max Grav 4=51 (LC 1), 7=220 (LC 16)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES

1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) This truss has been designed for greater of min roof live load of 20.0 psf or 2.00 times flat roof load of 30.0 psf on overhangs non-concurrent with other live loads.
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Bearing at joint(s) 7 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 5 lb uplift at joint 4 and 58 lb uplift at joint 7.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	BJ9	Jack-Closed	1	1	Job Reference (optional)



Scale = 1:28.2

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.22	Vert(LL)	-0.01	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.08	Vert(CT)	-0.01	4-5	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.29	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 28 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud
OTHERS	2x6 DF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=121/ Mechanical, 8=419/0-4-0, (min. 0-1-8)
Max Horiz 8=44 (LC 7)
Max Uplift 4=-23 (LC 10), 8=-113 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES

1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Bearing at joint(s) 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 23 lb uplift at joint 4 and 113 lb uplift at joint 8.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	BJ10	Jack-Closed	1	1	Job Reference (optional)



Scale = 1:28.2

0-5-8

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.15	Vert(LL)	0.00	5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.02	Vert(CT)	0.00	5	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.33	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 20 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud
OTHERS	2x6 DF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied or 3-10-15 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=-47/ Mechanical, 8=391/0-4-0, (min. 0-1-8)
Max Horiz 8=42 (LC 7)
Max Uplift 4=-47 (LC 1), 8=-116 (LC 6)
Max Grav 4=23 (LC 6), 8=391 (LC 1)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES

1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Bearing at joint(s) 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 47 lb uplift at joint 4 and 116 lb uplift at joint 8.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	BJ11	Diagonal Hip Girder	1	1	Job Reference (optional)



Scale = 1:33.3

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.27	Vert(LL)	-0.03	5-6	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.50	Vert(CT)	-0.05	5-6	>999	180		
TCDL	12.0	Rep Stress Incr	NO	WB	0.30	Horz(CT)	0.00	5	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	7.0										Weight: 50 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 5=436/ Mechanical, 7=1008/0-7-12, (min. 0-1-8)
Max Horiz 7=40 (LC 5)
Max Uplift 5=-93 (LC 8), 7=-354 (LC 4)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	1-2=-110/256, 2-3=-623/227
BOT CHORD	7-10=-253/126, 6-10=-253/126, 6-11=-212/621, 5-11=-212/621
WEBS	1-7=-290/118, 2-7=-616/184, 2-6=-282/903, 3-5=-557/220


NOTES

1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 354 lb uplift at joint 7 and 93 lb uplift at joint 5.
8) "NAILED" indicates Girder: 3-10d (0.148" x 3") toe-nails per NDS guidelines.
9) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
   Uniform Loads (lb/ft)
   Vert: 1-4=-84, 5-8=-14
   Concentrated Loads (lb)
   Vert: 7=-278 (F=-139, B=-139), 10=89 (F=44, B=44), 11=-187 (F=-93, B=-93)

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	BJ12	Diagonal Hip Girder	1	1	Job Reference (optional)




35-4-12 34-3-12

3-6-6

3-3-10

2-8-6



0-2-12

0-7-4

0-2-12

Scale = 1:48.5

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.36	Vert(LL)	-0.04	7-8	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.62	Vert(CT)	-0.06	7-8	>999	180		
TCDL	12.0	Rep Stress Incr	NO	WB	0.28	Horz(CT)	0.01	7	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	7.0										Weight: 56 lb	FT = 20%

LUMBER
TOP CHORD 2x6 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W3,W4,W5:2x4 DF No.2

REACTIONS (lb/size) 3=892/0-5-11, (min. 0-1-8), 7=579/ Mechanical
Max Horiz 3=37 (LC 5)
Max Uplift 3=-241 (LC 4), 7=-110 (LC 8)

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 12-13.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
BOT CHORD 9-15=-227/964, 8-15=-227/964, 8-16=-227/964, 7-16=-227/964
WEBS 4-9=-94/385, 5-7=-901/229, 5-9=-1015/239, 5-8=-71/340

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 110 lb uplift at joint 7 and 241 lb uplift at joint 3.
8) Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 3.
9) "NAILED" indicates Girder: 3-10d (0.148" x 3") toe-nails per NDS guidelines.
10) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-6=-84, 11-13=-14, 7-10=-14
Concentrated Loads (lb)
Vert: 10=-31 (B), 15=-69 (F=38, B=-107), 16=-311 (F=-101, B=-210)

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	BJ13	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:27:00 Page: 1
ID:_n8U7y_RHqMFZqyj0u5bEmzge?o-mJzB92gQBMwRTGXDQ4bXbqDQD7YPG?YdBGWeu2zUlqP



Scale = 1:28.2

0-7-4

Plate Offsets (X, Y): [3:0-1-12,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.06	Vert(LL)	n/a	-	n/a	999	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.02	Vert(CT)	n/a	-	n/a	999		
TCDL	12.0	Rep Stress Incr	YES	WB	0.04	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 13 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud
OTHERS	2x6 DF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied or 2-4-7 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 2=0/ Mechanical, 3=159/0-4-0, (min. 0-1-8)
Max Horiz 2=92 (LC 1), 3=-92 (LC 1)
Max Uplift 3=-54 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


NOTES

1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Bearing at joint(s) 3 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 54 lb uplift at joint 3.
9) Non Standard bearing condition. Review required.
10) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	C1	Roof Special	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:27:01 Page: 1
ID:NE_PLMY?xTwCHeWSGiReEZzcXsP-EVXZMOh2yg2I5Q6Q_n7m82lObXiJ?GemQwGBQUzUlqO



Scale = 1:56.1

Plate Offsets (X, Y): [2:0-3-8,0-2-0], [3:0-3-8,0-2-0], [9:0-3-8,0-2-0], [12:0-3-8,0-2-0], [13:0-3-8,0-2-0], [16:0-3-8,0-2-0], [17:0-4-8,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.92	Vert(LL)	-0.91	14-15	>393	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.81	Vert(CT)	-1.49	14-15	>240	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.82	Horz(CT)	0.15	11	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 142 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF 2100F 1.8E *Except* B1:2x4 DF No.2
WEBS 2x4 DF Stud *Except* W4,W16:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 11=1451/0-6-4, (min. 0-1-9), 18=1669/0-5-8, (min. 0-1-12)
Max Horiz 18=38 (LC 7)
Max Uplift 11=-212 (LC 7), 18=-250 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-20=-3784/1059, 3-20=-3780/1060, 3-4=-6037/1737, 4-5=-6893/1999, 5-6=-6892/1999, 6-7=-7229/2109, 7-8=-6355/1867, 8-9=-6359/1867, 9-10=-4029/1200, 10-11=-1386/429
BOT CHORD 16-17=-1013/3779, 15-16=-1685/6032, 14-15=-2067/7250, 13-14=-1816/6355, 12-13=-1153/4025
WEBS 2-18=-1576/509, 4-15=-272/905, 3-17=-1094/368, 2-17=-1150/3904, 3-16=-706/2365, 4-16=-664/239, 6-15=-382/177, 7-14=-252/918, 7-13=-659/229, 9-13=-695/2438, 9-12=-1104/368, 10-12=-1166/4005

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 27-11-13, Corner (3) 27-11-13 to 31-11-13 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 212 lb uplift at joint 11 and 250 lb uplift at joint 18.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	C2	Roof Special	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:27:01 Page: 1
ID:Z9krLZIuKWjPjAFNvkYBlezcXrR-EVXZMOh2yg2I5Q6Q_n7m82lSiXfY?GkmQwGBQUzUlqO



Scale = 1:56.2

Plate Offsets (X, Y): [2:0-3-8,0-2-8], [3:0-3-8,0-1-8], [8:0-3-8,0-2-0], [10:0-3-8,0-2-8], [14:0-3-8,0-2-8], [15:0-3-8,0-2-0], [19:0-3-8,0-1-8], [20:0-3-8,0-2-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.66	Vert(LL)	-0.64	17-18	>511	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.98	Vert(CT)	-1.05	17-18	>312	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.81	Horz(CT)	0.11	13	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 149 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2 *Except* B2:2x4 DF 2100F 1.8E
WEBS 2x4 DF Stud *Except* W4,W16:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 13=1746/1-5-7, (min. 0-1-14), 22=1531/0-5-8, (min. 0-1-10)
Max Horiz 22=-35 (LC 6)
Max Uplift 13=-335 (LC 7), 22=-237 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-24=-3174/836, 3-24=-3170/837, 3-4=-5062/1372, 4-5=-5738/1557, 5-6=-5737/1557, 6-7=-5911/1592, 7-8=-4929/1293, 8-9=-2623/610, 9-10=-2626/610, 10-11=-242/399
BOT CHORD 19-20=-789/3169, 18-19=-1320/5057, 17-18=-1539/5908, 16-17=-1243/4926, 15-16=-1243/4926, 14-15=-563/2623, 13-14=-396/286
WEBS 11-13=-439/301, 2-22=-1429/443, 4-18=-193/719, 3-20=-990/320, 2-20=-931/3318, 3-19=-561/1995, 4-19=-589/204, 10-13=-1515/472, 6-17=-280/126, 7-17=-312/1037, 7-15=-690/244, 8-15=-715/2420, 8-14=-1065/347, 10-14=-903/3211

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 29-7-0, Corner (3) 29-7-0 to 33-7-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) All plates are 3x4 (=) MT20 unless otherwise indicated.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 237 lb uplift at joint 22 and 335 lb uplift at joint 13.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	C3	Roof Special	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:27:01 Page: 1
ID:KnJaIYDZRtIdrs3zMhv?qgzcXqF-EVXZMOh2yg2I5Q6Q_n7m82lVeXfe?DvmQwGBQUzUlqO



Scale = 1:53.2

Plate Offsets (X, Y): [2:0-2-4,0-2-0], [10:0-2-0,0-1-12], [14:0-2-4,0-2-8], [20:0-2-0,0-1-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.47	Vert(LL)	-0.50	16-18	>610	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.98	Vert(CT)	-0.82	16-18	>373	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.99	Horz(CT)	0.11	13	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 141 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 13=1650/1-5-7, (min. 0-1-12), 21=1431/0-5-8, (min. 0-1-8)
Max Horiz 21=-36 (LC 6)
Max Uplift 13=-321 (LC 7), 21=-226 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-23=-2710/724, 3-23=-2706/725, 3-4=-4359/1204, 4-5=-4954/1370, 5-6=-4952/1370, 6-7=-4197/1117, 7-8=-2418/570, 8-9=-2417/567, 9-10=-2420/567, 10-11=-244/381
BOT CHORD 19-20=-677/2705, 18-19=-1153/4355, 17-18=-1341/5079, 16-17=-1341/5079, 15-16=-1341/5079, 14-15=-1064/4194, 13-14=-378/288
WEBS 11-13=-414/302, 2-21=-1325/425, 4-18=-174/638, 3-20=-916/304, 2-20=-824/2865, 3-19=-506/1756, 4-19=-552/195, 10-13=-1416/460, 6-15=-941/295, 7-15=-84/383, 7-14=-1921/589, 10-14=-855/2959

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 27-7-0, Corner (3) 27-7-0 to 31-7-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 226 lb uplift at joint 21 and 321 lb uplift at joint 13.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	C4	Roof Special	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:27:01 Page: 1
ID:SMjCIECMMmV83IlYbCs?clzcXp_-EVXZMOh2yg2I5Q6Q_n7m82lXFXi7?F0mQwGBQUzUlqO



Scale = 1:50.2

Plate Offsets (X, Y): [2:0-3-8,0-2-0], [10:0-3-8,0-2-0], [14:0-3-8,0-2-0], [20:0-3-8,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.37	Vert(LL)	-0.37	16-18	>770	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.82	Vert(CT)	-0.60	16-18	>471	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.86	Horz(CT)	0.07	13	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 133 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 13=1554/1-5-7, (min. 0-1-11), 21=1331/0-5-8, (min. 0-1-8)
Max Horiz 21=-36 (LC 6)
Max Uplift 13=-308 (LC 7), 21=-214 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-2284/904, 3-4=-3699/1585, 4-5=-4212/1756, 5-6=-4211/1758, 6-23=-4290/1645, 7-23=-4292/1645, 7-8=-3598/1306, 8-9=-1991/646, 9-10=-1994/645, 10-11=-251/401
BOT CHORD 19-20=-859/2280, 18-19=-1537/3695, 17-18=-1592/4289, 16-17=-1592/4289, 15-16=-1256/3595, 14-15=-598/1991, 13-14=-398/295
WEBS 2-21=-1219/522, 10-13=-1320/524, 11-13=-442/310, 7-16=-363/749, 7-15=-581/276, 8-15=-708/1724, 8-14=-891/380, 10-14=-955/2555, 4-18=-179/556, 3-20=-844/391, 2-20=-1019/2461, 3-19=-729/1521, 4-19=-509/288

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 12-1-12, Exterior (2) 12-1-12 to 17-7-0, Corner (3) 17-7-0 to 29-7-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) All plates are 3x4 (=) MT20 unless otherwise indicated.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 214 lb uplift at joint 21 and 308 lb uplift at joint 13.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	C5	Roof Special	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:27:02 Page: 1
ID:XoAja?o5qphBRq?yz_FU54zcXoD-jh5yakhgj_A8jahcXVe?hFIi?w4hkifwea?kywzUlqN



Scale = 1:47.2

Plate Offsets (X, Y): [2:0-3-8,0-1-8], [9:0-3-8,0-2-0], [13:0-3-8,0-2-0], [18:0-3-8,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.37	Vert(LL)	-0.27	14-16	>949	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.67	Vert(CT)	-0.45	14-16	>578	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.89	Horz(CT)	0.05	12	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 123 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 12=1458/1-5-7, (min. 0-1-9), 19=1231/0-5-8, (min. 0-1-8)
Max Horiz 19=-36 (LC 6)
Max Uplift 12=-295 (LC 7), 19=-203 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1891/588, 3-4=-3081/994, 4-5=-3534/1130, 5-21=-3529/1130, 6-21=-3534/1130, 6-7=-3485/1094, 7-8=-2188/631, 8-9=-2191/630, 9-10=-254/374
BOT CHORD 17-18=-540/1887, 16-17=-943/3078, 15-16=-1043/3482, 14-15=-1043/3482, 13-14=-582/2188, 12-13=-371/298
WEBS 2-19=-1114/414, 4-16=-146/496, 3-18=-771/299, 2-18=-707/2087, 3-17=-438/1294, 4-17=-466/188, 9-12=-1231/476, 10-12=-404/312, 6-14=-369/174, 7-14=-485/1363, 7-13=-752/312, 9-13=-920/2674

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 12-1-12, Exterior (2) 12-1-12 to 15-7-0, Corner (3) 15-7-0 to 27-7-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 203 lb uplift at joint 19 and 295 lb uplift at joint 12.
7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	C6	Roof Special	1	1	Job Reference (optional)



Scale = 1:46.5

Plate Offsets (X, Y): [7:0-2-12,Edge], [9:0-2-0,Edge], [13:0-3-8,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.53	Vert(LL)	-0.18	14-15	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.53	Vert(CT)	-0.29	14-15	>795	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.72	Horz(CT)	0.05	12	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 112 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2 *Except* T3:2x6 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 11=0/1-3-15, (min. 0-1-8), 12=1332/0-3-8, (min. 0-1-8), 18=1133/0-5-8, (min. 0-1-8)
Max Horiz 18=-37 (LC 8)
Max Uplift 11=REL, 12=-372 (LC 11), 18=-185 (LC 6)
Max Grav 11=148 (LC 11), 12=1332 (LC 1), 18=1133 (LC 1)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-2055/669, 4-5=-2908/944, 5-21=-2905/944, 21-22=-2905/944, 6-22=-2908/944, 6-7=-2833/841, 7-8=-1779/335, 9-11=-799/167
BOT CHORD 17-18=-459/1522, 16-17=-800/2517, 15-16=-800/2517, 14-15=-786/2831, 13-14=-249/1702, 12-13=-654/590, 11-12=-654/590
WEBS 2-18=-277/142, 8-12=-1136/1066, 8-11=-729/738, 4-15=-96/432, 3-18=-1753/656, 3-17=-214/728, 4-17=-649/259, 6-14=-359/212, 7-14=-570/1199, 7-13=-616/317, 8-13=-914/2142

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 12-1-12, Exterior (2) 12-1-12 to 13-8-12, Corner (3) 13-8-12 to 25-8-12 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) This truss has been designed for greater of min roof live load of 20.0 psf or 2.00 times flat roof load of 30.0 psf on overhangs non-concurrent with other live loads.
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 185 lb uplift at joint 18 and 372 lb uplift at joint 12.
8) "/\" indicates Released bearing: allow for upward movement at joint(s) 11.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	C7	Roof Special Girder	1	2	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:27:02 Page: 1
ID:MrE_pkJWODQSx23_ol_ofRzcXmG-jh5yakhgj_A8jahcXVe?hFIcOw7Nkicwea?kywzUlqN



Scale = 1:48.1

Plate Offsets (X, Y): [10:Edge,0-4-12], [13:0-2-8,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.73	Vert(LL)	-0.16	12-13	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.50	Vert(CT)	-0.24	12-13	>860	180		
TCDL	12.0	Rep Stress Incr	NO	WB	0.83	Horz(CT)	0.01	11	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	7.0										Weight: 225 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x6 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 5-3-11 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS (lb/size) 10=-3577/1-3-15, (min. 0-1-8), 11=5757/1-3-15, (min. 0-1-8), 17=1637/0-5-8, (min. 0-1-8)
Max Horiz 17=36 (LC 7)
Max Uplift 10=-3577 (LC 1), 11=-1016 (LC 5), 17=-329 (LC 4)
Max Grav 10=589 (LC 4), 11=5757 (LC 1), 17=1637 (LC 1)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-3028/575, 3-4=-4794/892, 4-5=-5387/980, 5-6=-5410/988, 6-7=-1823/332, 7-8=-101/369, 8-10=-835/257
BOT CHORD 15-16=-587/3024, 14-15=-587/3024, 14-19=-903/4792, 13-19=-903/4792, 13-20=-344/1815, 20-21=-344/1815, 12-21=-344/1815, 12-22=-2970/561, 11-22=-2970/561, 10-11=-2576/492
WEBS 3-16=-1069/192, 2-17=-1406/279, 2-16=-554/3055, 6-12=-1306/278, 6-13=-673/3695, 7-12=-942/4981, 7-11=-4562/799, 7-10=-654/3571, 4-13=-142/672, 4-14=-531/106, 3-14=-351/1960

NOTES
1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
4) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
5) This truss has been designed for greater of min roof live load of 20.0 psf or 2.00 times flat roof load of 30.0 psf on overhangs non-concurrent with other live loads.
6) Provide adequate drainage to prevent water ponding.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 3577 lb uplift at joint 10, 329 lb uplift at joint 17 and 1016 lb uplift at joint 11.
10) This truss has large uplift reaction(s) from gravity load case(s). Proper connection is required to secure truss against upward movement at the bearings. Building designer must provide for uplift reactions indicated.
11) Use Simpson Strong-Tie TJC37 (4 nail, 150-157) or equivalent at 5-6-7 from the left end to connect truss(es) CJ13 (1 ply 2x4 DF) to back face of bottom chord, skewed 67.5 deg.to the right, sloping 0.0 deg. down.
12) Use Simpson Strong-Tie HGUS26-2 (20-10d Girder, 6-10d Truss) or equivalent at 10-8-10 from the left end to connect truss(es) C14 (2 ply 2x4 DF) to back face of bottom chord, skewed 0.0 deg.to the right, sloping 0.0 deg. down.
13) Fill all nail holes where hanger is in contact with lumber.

Continued on page 2


14) "NAILED" indicates Girder: 3-10d (0.148" x 3") toe-nails per NDS guidelines.

LOAD CASE(S) Standard

1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
   Uniform Loads (lb/ft)
   Vert: 1-8=-84, 8-9=-84, 10-18=-14
   Concentrated Loads (lb)
   Vert: 15=-117 (B), 16=-55 (B), 13=-778 (B), 19=-233 (B), 20=-239 (B), 21=-125 (B)

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	C8	Roof Special	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:27:02 Page: 1
ID:0mEzqalihdnZlBU5UdfPnYzcY_U-jh5yakhgj_A8jahcXVe?hFIdsw?YkkFwea?kywzUlqN



Scale = 1:55.7

Plate Offsets (X, Y): [2:0-3-8,0-2-8], [3:0-3-8,0-1-8], [10:0-6-8,Edge], [14:0-5-8,0-3-4], [15:0-3-8,0-1-8], [16:0-3-8,0-2-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.70	Vert(LL)	-0.69	13-14	>483	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	1.00	Vert(CT)	-1.17	13-14	>286	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.73	Horz(CT)	0.10	20	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 134 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2 *Except* B2:2x4 DF 2100F 1.8E
WEBS 2x4 DF Stud *Except* W16:2x8 DF 2250F 1.6E or 2x8 DF SS, W4:2x4 DF No.2
OTHERS 2.0 RigidLam DF LVL 1-1/2 x 11-7/8

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 17=1573/0-5-8, (min. 0-1-11), 20=1239/ Mechanical
Max Horiz 17=-27 (LC 8)
Max Uplift 17=-238 (LC 6), 20=-178 (LC 7)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-21=-3299/944, 3-21=-3295/945, 3-4=-5287/1566, 4-5=-6095/1797, 5-6=-6094/1798, 6-7=-5618/1675, 7-8=-5615/1672, 8-22=-5616/1672, 9-22=-5618/1672, 9-10=-1291/397, 11-20=-322/1101, 10-20=-322/1101
BOT CHORD 15-16=-930/3294, 14-15=-1547/5283, 13-14=-1913/6332, 12-13=-1075/3545, 11-12=-1075/3545
WEBS 2-17=-1474/491, 4-14=-242/859, 3-16=-1024/357, 2-16=-1044/3446, 3-15=-652/2102, 4-15=-640/226, 6-14=-257/187, 6-13=-764/274, 7-13=-322/140, 9-13=-610/2177, 9-11=-2485/762, 10-20=-2074/641

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 24-10-1, Corner (3) 24-10-1 to 28-10-1 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 238 lb uplift at joint 17 and 178 lb uplift at joint 20.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	C9	Roof Special	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:27:03 Page: 1
ID:ziIhI17b3JK9w5XpaFg_k4zcXjw-BufKn4iJUHI?KkFo5C9EDTrqDKMqTDu3tEIlVNzUlqM



Scale = 1:52.7

Plate Offsets (X, Y): [10:0-6-8,Edge], [13:0-4-12,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.53	Vert(LL)	-0.51	12-13	>609	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.93	Vert(CT)	-0.86	12-13	>362	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.64	Horz(CT)	0.10	18	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 125 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2 *Except* B2:2x4 DF 2100F 1.8E
WEBS 2x4 DF Stud *Except* W15:2x8 DF 2250F 1.6E or 2x8 DF SS
OTHERS 2.0 RigidLam DF LVL 1-1/2 x 11-7/8

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 15=1476/0-5-8, (min. 0-1-9), 18=1140/ Mechanical
Max Horiz 15=-28 (LC 8)
Max Uplift 15=-226 (LC 6), 18=-164 (LC 7)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-3836/1269, 4-5=-3836/1272, 5-19=-5294/1771, 6-19=-5292/1772, 6-20=-5292/1772, 7-20=-5294/1771, 7-8=-4857/1645, 8-9=-4858/1642, 9-10=-1175/392, 11-18=-338/1020, 10-18=-338/1020
BOT CHORD 14-15=-710/2185, 13-14=-1610/4798, 12-13=-1883/5494, 11-12=-1058/3050
WEBS 2-15=-282/131, 3-14=-602/1829, 3-15=-2475/892, 5-14=-1088/403, 5-13=-158/557, 7-12=-686/277, 8-12=-297/148, 9-12=-601/1912, 9-11=-2110/764, 10-18=-1905/661

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 12-1-12, Exterior (2) 12-1-12 to 14-10-1, Corner (3) 14-10-1 to 26-10-1 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 226 lb uplift at joint 15 and 164 lb uplift at joint 18.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	C10	Roof Special	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:27:03 Page: 1
ID:GaGBv2cJPvVLLO9hUMwbvjzcXjH-BufKn4iJUHI?KkFo5C9EDTrsAKLKTEA3tEIlVNzUlqM



Scale = 1:49.6

Plate Offsets (X, Y): [10:0-6-8,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.40	Vert(LL)	-0.39	12-13	>737	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.96	Vert(CT)	-0.65	12-13	>438	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.56	Horz(CT)	0.08	19	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 117 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W15:2x8 DF 2250F 1.6E or 2x8 DF SS
OTHERS 2.0 RigidLam DF LVL 1-1/2 x 11-7/8

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 16=1378/0-5-8, (min. 0-1-8), 19=1042/ Mechanical
Max Horiz 16=-28 (LC 8)
Max Uplift 16=-215 (LC 6), 19=-150 (LC 7)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-3269/1406, 4-5=-3269/1409, 5-6=-4547/2021, 6-20=-4544/2022, 7-20=-4547/2022, 7-8=-4154/1710, 8-9=-4154/1707, 9-10=-1063/420, 11-19=-371/934, 10-19=-371/934
BOT CHORD 15-16=-771/1846, 14-15=-1854/4107, 13-14=-1854/4107, 12-13=-2017/4698, 11-12=-1064/2592
WEBS 2-16=-266/133, 3-15=-700/1600, 3-16=-2148/972, 5-15=-963/529, 5-13=-168/502, 7-12=-594/354, 8-12=-280/145, 9-12=-670/1666, 9-11=-1767/760, 10-19=-1738/710

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 12-1-12, Exterior (2) 12-1-12 to 12-10-1, Corner (3) 12-10-1 to 24-10-1 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 215 lb uplift at joint 16 and 150 lb uplift at joint 19.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	C11	Roof Special	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:27:03 Page: 1
ID:ZaQU5?0R8oUBHa0qVgbSGKzcWeK-BufKn4iJUHI?KkFo5C9EDTrnmKP5T9r3tEIlVNzUlqM



Scale = 1:46.7

Plate Offsets (X, Y): [3:0-1-12,0-1-8], [6:0-2-12,0-1-8], [7:0-6-8,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.75	Vert(LL)	-0.31	9-10	>840	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.72	Vert(CT)	-0.52	9-10	>506	180	M18AHS	132/127
TCDL	12.0	Rep Stress Incr	YES	WB	0.83	Horz(CT)	0.06	15	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 108 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W12:2x8 DF 2250F 1.6E or 2x8 DF SS
OTHERS 2.0 RigidLam DF LVL 1-1/2 x 11-7/8

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (2-11-5 max.): 4-5.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 13=1280/0-5-8, (min. 0-1-8), 15=943/ Mechanical
Max Horiz 13=-28 (LC 8)
Max Uplift 13=-258 (LC 6), 15=-161 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-3788/1422, 4-16=-4003/1547, 5-16=-4003/1547, 5-6=-4003/1543, 6-7=-1451/565, 7-15=-260/731
BOT CHORD 12-13=-861/2205, 11-12=-861/2205, 10-11=-1436/3816, 9-10=-1333/3448, 9-15=-1339/3462
WEBS 4-11=-340/201, 4-10=-139/251, 5-10=-254/139, 6-10=-209/566, 6-15=-2044/788, 3-13=-2399/1040, 3-11=-572/1629, 7-15=-1549/611

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 258 lb uplift at joint 13 and 161 lb uplift at joint 15.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	C12	Roof Special	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:27:03 Page: 1
ID:VE3g5VFMfetV3VzU69QvXLzcWe1-BufKn4iJUHI?KkFo5C9EDTrriKSZTDp3tEIlVNzUlqM



Scale = 1:43.7

Plate Offsets (X, Y): [7:0-6-8,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.50	Vert(LL)	-0.21	9-10	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.57	Vert(CT)	-0.34	9-10	>691	180	M18AHS	132/127
TCDL	12.0	Rep Stress Incr	YES	WB	0.58	Horz(CT)	0.05	15	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 98 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W11:2x8 DF 2250F 1.6E or 2x8 DF SS
OTHERS 2.0 RigidLam DF LVL 1-1/2 x 11-7/8

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (2-11-4 max.): 4-5.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 12=1183/0-5-8, (min. 0-1-8), 15=845/ Mechanical
Max Horiz 12=-31 (LC 8)
Max Uplift 12=-241 (LC 6), 15=-144 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-2958/1178, 4-16=-3381/1368, 5-16=-3381/1368, 5-6=-3351/1347, 6-7=-919/350, 8-15=-266/693, 7-15=-266/693
BOT CHORD 11-12=-744/1868, 10-11=-744/1868, 9-10=-1182/2995, 8-9=-1043/2487
WEBS 4-10=-392/211, 4-9=-174/404, 5-9=-319/186, 6-9=-300/905, 6-8=-1693/763, 2-12=-305/166, 3-10=-451/1179, 3-12=-2045/908, 7-15=-1431/599

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 241 lb uplift at joint 12 and 144 lb uplift at joint 15.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	C13	Roof Special Girder	1	2	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:27:04 Page: 1
ID:Sujr4?UGBUGoqQw8keGNoLzcWdk-f4Di_QjxFbQsyuq_fwgTmgN3xkoqCkLC6uUr1pzUlqL



Scale = 1:40.7

Plate Offsets (X, Y): [7:0-6-8,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.27	Vert(LL)	-0.15	9-10	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.56	Vert(CT)	-0.23	9-10	>949	180	M18AHS	132/127
TCDL	12.0	Rep Stress Incr	NO	WB	0.37	Horz(CT)	0.02	15	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	7.0										Weight: 208 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x6 DF No.2
WEBS	2x4 DF Stud *Except* W11:2x8 DF 2250F 1.6E or 2x8 DF SS
OTHERS	2.0 RigidLam DF LVL 1-1/2 x 11-7/8

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (5-5-4 max.): 4-6.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 13-14.

REACTIONS (lb/size) 13=1738/0-5-8, (min. 0-1-8), 15=1311/ Mechanical
Max Horiz 13=-26 (LC 6)
Max Uplift 13=-385 (LC 4), 15=-275 (LC 5)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	3-4=-4404/925, 4-5=-5648/1163, 5-6=-5648/1163, 6-7=-2098/445, 7-15=-209/1059
BOT CHORD	12-13=-536/2480, 11-12=-536/2480, 11-16=-938/4470, 16-17=-938/4470, 10-17=-938/4470, 10-18=-1067/5058, 9-18=-1067/5058, 9-19=-1071/5080, 15-19=-1072/5087
WEBS	4-11=-596/135, 4-10=-246/1249, 5-10=-287/92, 6-10=-113/625, 6-15=-3040/638, 2-13=-273/72, 3-11=-450/2208, 3-13=-2809/599, 7-15=-2107/448

NOTES

1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
   Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc, 2x8 - 2 rows staggered at 0-9-0 oc.
   Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
   Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
4) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
5) Provide adequate drainage to prevent water ponding.
6) All plates are MT20 plates unless otherwise indicated.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Refer to girder(s) for truss to truss connections.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 385 lb uplift at joint 13 and 275 lb uplift at joint 15.
11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
12) Use Simpson Strong-Tie SUL24 (4-10d Girder, 4-10dx1 1/2 Truss) or equivalent at 6-10-1 from the left end to connect truss(es) CJ3 (1 ply 2x4 DF) to front face of bottom chord, skewed 45.0 deg.to the left, sloping 0.0 deg. down.
13) Fill all nail holes where hanger is in contact with lumber.
14) "NAILED" indicates Girder: 3-10d (0.148" x 3") toe-nails per NDS guidelines.
15) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 319 lb down and 88 lb up at 13-11-4 on bottom chord. The design/ selection of such connection device(s) is the responsibility of others.


Continued on page 2

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	C13	Roof Special Girder	1	**2**	Job Reference (optional)

LOAD CASE(S) Standard

1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
   Uniform Loads (lb/ft)
   Vert: 1-7=-84, 8-14=-14
   Concentrated Loads (lb)
   Vert: 11=-341 (F), 9=-319 (F), 16=-163 (F), 17=-163 (F), 18=-163 (F), 19=-68 (F)

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	C14	Diagonal Hip Girder	1	2	Job Reference (optional)



Scale = 1:30.2

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.16	Vert(LL)	-0.02	6-7	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.36	Vert(CT)	-0.02	6-7	>999	180		
TCDL	12.0	Rep Stress Incr	NO	WB	0.19	Horz(CT)	0.00	6	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	7.0										Weight: 116 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 8-9.


REACTIONS (lb/size) 6=792/ Mechanical, 9=1100/0-9-14, (min. 0-1-8)
Max Horiz 9=41 (LC 5)
Max Uplift 6=-127 (LC 8), 9=-349 (LC 4)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-142/427, 2-3=-633/177, 3-11=-1129/204, 4-11=-1127/205
BOT CHORD 9-13=-424/158, 8-13=-424/158, 8-14=-162/630, 7-14=-162/630, 7-15=-188/1127, 6-15=-188/1127
WEBS 1-9=-484/151, 2-9=-785/209, 4-6=-1136/200, 3-8=-447/81, 2-8=-296/1142, 3-7=-55/541

NOTES
1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
4) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
5) Provide adequate drainage to prevent water ponding.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Refer to girder(s) for truss to truss connections.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 127 lb uplift at joint 6 and 349 lb uplift at joint 9.
10) "NAILED" indicates Girder: 3-10d (0.148" x 3") toe-nails per NDS guidelines.

LOAD CASE(S) Standard
1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-5=-84, 6-10=-14
Concentrated Loads (lb)
Vert: 12=-130 (F), 13=78 (F=49, B=28), 14=-183 (F=-87, B=-96), 15=-422 (F=-208, B=-214)

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ1	Diagonal Hip Girder	1	1	Job Reference (optional)



Scale = 1:42.2

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.51	Vert(LL)	-0.02	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.10	Vert(CT)	-0.02	4-5	>999	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	NO	WB	0.13	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 35 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud
OTHERS	2x6 DF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied or 7-4-3 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=171/ Mechanical, 8=471/0-4-6, (min. 0-1-8)
Max Horiz 8=44 (LC 7)
Max Uplift 4=-53 (LC 8), 8=-149 (LC 4)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES


1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Bearing at joint(s) 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 53 lb uplift at joint 4 and 149 lb uplift at joint 8.
10) Use Simpson Strong-Tie TJC37 (4 nail, 22-30) or equivalent at 4-11-3 from the left end to connect truss(es) CJ10 (1 ply 2x4 DF) to front face of bottom chord, skewed 67.5 deg.to the left, sloping 0.0 deg. down.
11) Use Simpson Strong-Tie TJC37 (4 nail, 150-157) or equivalent at 4-11-3 from the left end to connect truss(es) CJ9 (1 ply 2x4 DF) to back face of bottom chord, skewed 67.5 deg.to the right, sloping 0.0 deg. down.
12) Fill all nail holes where hanger is in contact with lumber.
13) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard


1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-3=-84, 6-7=-14, 4-5=-14
Concentrated Loads (lb)
Vert: 13=39 (F=43, B=-4)

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ2	Jack-Closed	4	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:27:04 Page: 1
ID:xKkZXTcpYcHxelGPfWNH5WzcXgi-f4Di_QjxFbQsyuq_fwgTmgN2tkuNCn2C6uUr1pzUlqL



38-9-7 38-3-12



Scale = 1:39.2

0-5-8

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.34	Vert(LL)	-0.02	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.14	Vert(CT)	-0.03	4-5	>999	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.13	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 33 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud
OTHERS	2x6 DF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=177/ Mechanical, 8=454/0-4-1, (min. 0-1-8)
Max Horiz 8=44 (LC 7)
Max Uplift 4=-23 (LC 10), 8=-121 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES

1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Bearing at joint(s) 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 23 lb uplift at joint 4 and 121 lb uplift at joint 8.
10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ3	Diagonal Hip Girder	1	1	Job Reference (optional)



Scale = 1:32.1

0-3-11

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.58	Vert(LL)	-0.05	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.29	Vert(CT)	-0.05	4-5	>999	180		
TCDL	12.0	Rep Stress Incr	NO	WB	0.11	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	7.0										Weight: 42 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 4=361/ Mechanical, 5=941/0-7-6, (min. 0-1-8)
Max Horiz 5=39 (LC 27)
Max Uplift 4=-93 (LC 8), 5=-333 (LC 4)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-5=-572/161, 2-4=-94/285

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 93 lb uplift at joint 4 and 333 lb uplift at joint 5.
8) "NAILED" indicates Girder: 3-10d (0.148" x 3") toe-nails per NDS guidelines.
9) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-3=-84, 4-6=-14
Concentrated Loads (lb)
Vert: 8=-278 (F=-139, B=-139), 9=82 (F=38, B=44), 10=-201 (F=-104, B=-97)

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ4	Jack-Closed	1	1	Job Reference (optional)



Scale = 1:39.2

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.20	Vert(LL)	-0.01	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.08	Vert(CT)	-0.01	4-5	>999	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.14	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 29 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud
OTHERS	2x6 DF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=120/ Mechanical, 8=420/0-4-1, (min. 0-1-8)
Max Horiz 8=44 (LC 7)
Max Uplift 4=-19 (LC 10), 8=-118 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES

1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Bearing at joint(s) 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 19 lb uplift at joint 4 and 118 lb uplift at joint 8.
10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ5	Jack-Closed	1	1	Job Reference (optional)


2-3-3

2-1-10

2-0-7 3-10-15
2-0-7 1-7-12

0-1-3

0-1-9



38-9-7 38-3-12

2-4-12

1-11-4 3-10-15
1-11-4 1-6-3

Scale = 1:39.2

0-5-8

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.08	Vert(LL)	0.00	5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.02	Vert(CT)	0.00	5	>999	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.14	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 21 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud
OTHERS	2x6 DF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied or 3-10-15 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=-47/ Mechanical, 8=392/0-4-1, (min. 0-1-8)
Max Horiz 8=42 (LC 7)
Max Uplift 4=-47 (LC 1), 8=-128 (LC 6)
Max Grav 4=35 (LC 6), 8=392 (LC 1)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES

1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Bearing at joint(s) 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 47 lb uplift at joint 4 and 128 lb uplift at joint 8.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ6	Jack-Closed	2	1	Job Reference (optional)



Scale = 1:23

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.07	Vert(LL)	n/a	-	n/a	999	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.02	Vert(CT)	n/a	-	n/a	999		
TCDL	12.0	Rep Stress Incr	YES	WB	0.04	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 10 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 1-10-15 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 2=0/ Mechanical, 3=159/ Mechanical
Max Horiz 2=103 (LC 1), 3=-103 (LC 1)
Max Uplift 3=-54 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 54 lb uplift at joint 3.
9) Non Standard bearing condition. Review required.
10) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ7	Jack-Closed	1	1	Job Reference (optional)



Scale = 1:28.2

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.18	Vert(LL)	0.00	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.07	Vert(CT)	-0.01	4-5	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.10	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 27 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 4=113/ Mechanical, 5=438/0-5-8, (min. 0-1-8)
Max Horiz 5=44 (LC 7)
Max Uplift 4=-14 (LC 10), 5=-126 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-5=-341/347

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 126 lb uplift at joint 5 and 14 lb uplift at joint 4.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ8	Jack-Closed	1	1	Job Reference (optional)



Scale = 1:31.7

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.32	Vert(LL)	0.00	3-4	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.04	Vert(CT)	0.00	3-4	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.11	Horz(CT)	0.00	3	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 18 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 3-10-15 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 3=-63/ Mechanical, 4=418/0-5-8, (min. 0-1-8)
Max Horiz 4=42 (LC 7)
Max Uplift 3=-63 (LC 1), 4=-145 (LC 6)
Max Grav 3=49 (LC 6), 4=418 (LC 1)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-279/263
WEBS 1-4=-301/310, 2-4=-340/389

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 63 lb uplift at joint 3 and 145 lb uplift at joint 4.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ9	Jack-Closed	1	1	Job Reference (optional)



Scale = 1:39.2

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.08	Vert(LL)	0.00	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.02	Vert(CT)	0.00	4-5	>999	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.15	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 23 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud
OTHERS	2x6 DF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=6/ Mechanical, 8=386/0-4-1, (min. 0-1-8)
Max Horiz 8=43 (LC 7)
Max Uplift 4=-7 (LC 7), 8=-121 (LC 6)
Max Grav 4=21 (LC 8), 8=386 (LC 1)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES

1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Bearing at joint(s) 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 7 lb uplift at joint 4 and 121 lb uplift at joint 8.
10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ10	Jack-Closed	1	1	Job Reference (optional)



Scale = 1:35

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.37	Vert(LL)	-0.01	7	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.15	Vert(CT)	0.01	7	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.02	Horz(CT)	0.01	6	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 19 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2 *Except* B2,B3:2x4 DF Stud
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 3=399/0-6-9, (min. 0-1-8), 6=-18/ Mechanical
Max Horiz 3=43 (LC 7)
Max Uplift 3=-119 (LC 6), 6=-21 (LC 19)
Max Grav 3=399 (LC 1), 6=13 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 21 lb uplift at joint 6 and 119 lb uplift at joint 3.
8) Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 3.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ11	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:27:06 Page: 1
ID:qoNE8qKejRBYf7I2s?7yeGzcXu_-bTLSP6lBmCgaBB_NmKixr5TOxYZjgiNVZCzy5hzUlqJ



39-6-12 38-3-12



Scale = 1:25.1

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.37	Vert(LL)	-0.01	7	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.15	Vert(CT)	-0.01	7	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.02	Horz(CT)	0.01	6	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 24 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2 *Except* B2,B3:2x4 DF Stud
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 3=415/0-6-9, (min. 0-1-8), 6=88/ Mechanical
Max Horiz 3=43 (LC 7)
Max Uplift 3=-118 (LC 6), 6=-23 (LC 10)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 23 lb uplift at joint 6 and 118 lb uplift at joint 3.
8) Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 3.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ13	Jack-Closed Girder	1	1	Job Reference (optional)





Scale = 1:27.7

0-3-0

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.20	Vert(LL)	0.00	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.07	Vert(CT)	-0.01	4-5	>999	180		
TCDL	12.0	Rep Stress Incr	NO	WB	0.07	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 27 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 5-9-13 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 4=89/ Mechanical, 5=456/0-5-15, (min. 0-1-8)
Max Horiz 5=43 (LC 5)
Max Uplift 4=-22 (LC 5), 5=-138 (LC 4)
Max Grav 4=89 (LC 15), 5=456 (LC 1)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-5=-344/110

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 138 lb uplift at joint 5 and 22 lb uplift at joint 4.
8) Use Simpson Strong-Tie TJC37 (4 nail, 150-157) or equivalent at 5-0-10 from the left end to connect truss(es) CJ14 (1 ply 2x4 DF) to back face of bottom chord, skewed 67.5 deg.to the right, sloping 0.0 deg. down.
9) Fill all nail holes where hanger is in contact with lumber.
10) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-3=-84, 4-6=-14
Concentrated Loads (lb)
Vert: 7=-3 (B)

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ14	Jack-Closed	1	1	Job Reference (optional)



Scale = 1:28.2

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.40	Vert(LL)	0.00	3-4	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.04	Vert(CT)	0.00	3-4	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.12	Horz(CT)	0.00	3	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 21 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 3=5/ Mechanical, 4=408/0-5-8, (min. 0-1-8)
Max Horiz 4=43 (LC 7)
Max Uplift 3=-13 (LC 7), 4=-132 (LC 6)
Max Grav 3=28 (LC 8), 4=408 (LC 1)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-321/304
WEBS 1-4=-348/360, 2-4=-352/397

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 13 lb uplift at joint 3 and 132 lb uplift at joint 4.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ15	Jack-Closed	1	1	Job Reference (optional)



Scale = 1:28.3

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.78	Vert(LL)	-0.01	3-4	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.09	Vert(CT)	-0.01	3-4	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.15	Horz(CT)	0.00	3	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 28 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 3=137/ Mechanical, 4=450/0-5-8, (min. 0-1-8)
Max Horiz 4=44 (LC 7)
Max Uplift 3=-20 (LC 10), 4=-127 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-427/416
WEBS 1-4=-476/484, 2-4=-435/470

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 20 lb uplift at joint 3 and 127 lb uplift at joint 4.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ16	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:27:07 Page: 1
ID:MrE_pkJWODQSx23_ol_ofRzcXmG-3furdSlpXWoRpLZZK2DANJ?a1xuvP7SfosjVe8zUlqI



Scale = 1:25.4

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.28	Vert(LL)	-0.03	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.22	Vert(CT)	-0.06	4-5	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.15	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 36 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=253/ Mechanical, 5=529/0-5-8, (min. 0-1-8)
Max Horiz 5=45 (LC 7)
Max Uplift 4=-34 (LC 6), 5=-136 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
BOT CHORD 4-5=-165/284
WEBS 1-5=-229/265, 2-5=-583/535, 2-4=-299/199

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 136 lb uplift at joint 5 and 34 lb uplift at joint 4.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ17	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:27:07 Page: 1
ID:MrE_pkJWODQSx23_ol_ofRzcXmG-3furdSlpXWoRpLZZK2DANJ?Y6xvaP8zfosjVe8zUlqI



Scale = 1:24.7

0-2-12

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.41	Vert(LL)	-0.03	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.18	Vert(CT)	-0.04	4-5	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.12	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 35 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

REACTIONS (lb/size) 4=228/ Mechanical, 5=510/0-5-8, (min. 0-1-8)
Max Horiz 5=45 (LC 7)
Max Uplift 4=-29 (LC 6), 5=-133 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-5=-458/420

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.


MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 29 lb uplift at joint 4 and 133 lb uplift at joint 5.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ18	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:27:07 Page: 1
ID:MrE_pkJWODQSx23_ol_ofRzcXmG-3furdSlpXWoRpLZZK2DANJ?UyxwCP7pfosjVe8zUlqI



Scale = 1:28.3

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.67	Vert(LL)	0.00	3-4	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.07	Vert(CT)	-0.01	3-4	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.13	Horz(CT)	0.00	3	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 26 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 3=107/ Mechanical, 4=435/0-5-8, (min. 0-1-8)
Max Horiz 4=44 (LC 7)
Max Uplift 3=-13 (LC 10), 4=-126 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-403/388
WEBS 1-4=-445/456, 2-4=-412/451

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 13 lb uplift at joint 3 and 126 lb uplift at joint 4.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ19	Jack-Closed	1	1	Job Reference (optional)



Scale = 1:28.2

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.31	Vert(LL)	0.00	3-4	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.04	Vert(CT)	0.00	3-4	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.11	Horz(CT)	0.00	3	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 18 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 3-9-14 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 3=-76/ Mechanical, 4=422/0-5-8, (min. 0-1-8)
Max Horiz 4=42 (LC 7)
Max Uplift 3=-76 (LC 1), 4=-148 (LC 6)
Max Grav 3=54 (LC 6), 4=422 (LC 1)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-273/257
WEBS 1-4=-294/303, 2-4=-340/390

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 76 lb uplift at joint 3 and 148 lb uplift at joint 4.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ20	Jack-Closed	1	1	Job Reference (optional)



Scale = 1:23

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.06	Vert(LL)	n/a	-	n/a	999	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.02	Vert(CT)	n/a	-	n/a	999		
TCDL	12.0	Rep Stress Incr	YES	WB	0.04	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 10 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud

BRACING

TOP CHORD	Structural wood sheathing directly applied or 1-9-14 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 2=0/ Mechanical, 3=150/ Mechanical
Max Horiz 2=92 (LC 1), 3=-92 (LC 1)
Max Uplift 3=-51 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


NOTES

1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 51 lb uplift at joint 3.
9) Non Standard bearing condition. Review required.
10) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ21	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:27:07 Page: 1
ID:MrE_pkJWODQSx23_ol_ofRzcXmG-3furdSlpXWoRpLZZK2DANJ?Vjxx3P9kfosjVe8zUlqI



Scale = 1:19.6

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.62	Vert(LL)	0.00	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.02	Vert(CT)	0.00	4-5	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.01	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 12 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 1-9-10 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 4=-57/ Mechanical, 5=387/0-11-4, (min. 0-1-8)
Max Horiz 5=43 (LC 7)
Max Uplift 4=-196 (LC 16), 5=-156 (LC 6)
Max Grav 4=56 (LC 6), 5=566 (LC 16)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-5=-555/376

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) This truss has been designed for greater of min roof live load of 20.0 psf or 2.00 times flat roof load of 30.0 psf on overhangs non-concurrent with other live loads.
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 156 lb uplift at joint 5 and 196 lb uplift at joint 4.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ22	Jack-Closed	1	1	Job Reference (optional)



Scale = 1:19.6

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.67	Vert(LL)	-0.01	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.10	Vert(CT)	-0.01	4-5	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.01	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 20 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 3-9-10 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=116/ Mechanical, 5=411/0-11-4, (min. 0-1-8)
Max Horiz 5=44 (LC 7)
Max Uplift 4=-30 (LC 16), 5=-134 (LC 6)
Max Grav 4=116 (LC 1), 5=476 (LC 16)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-5=-451/375

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) This truss has been designed for greater of min roof live load of 20.0 psf or 2.00 times flat roof load of 30.0 psf on overhangs non-concurrent with other live loads.
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 134 lb uplift at joint 5 and 30 lb uplift at joint 4.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ23	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:27:08 Page: 1
ID:MrE_pkJWODQSx23_ol_ofRzcXmG-XrSDqnmRIqwIRV8mullPwWYgkLDO8cmo1WS3AazUlqH



Scale = 1:19.8

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.61	Vert(LL)	-0.05	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.27	Vert(CT)	-0.08	4-5	>804	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.02	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 28 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 4=234/ Mechanical, 5=488/0-11-4, (min. 0-1-8)
Max Horiz 5=46 (LC 7)
Max Uplift 4=-36 (LC 10), 5=-140 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-5=-450/423

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) This truss has been designed for greater of min roof live load of 20.0 psf or 2.00 times flat roof load of 30.0 psf on overhangs non-concurrent with other live loads.
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 140 lb uplift at joint 5 and 36 lb uplift at joint 4.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ24	Jack-Closed	1	1	Job Reference (optional)



Scale = 1:20.5

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.61	Vert(LL)	-0.07	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.32	Vert(CT)	-0.11	4-5	>634	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.03	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 30 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 4=259/ Mechanical, 5=508/0-11-4, (min. 0-1-8)
Max Horiz 5=46 (LC 7)
Max Uplift 4=-41 (LC 10), 5=-142 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-5=-466/429

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) This truss has been designed for greater of min roof live load of 20.0 psf or 2.00 times flat roof load of 30.0 psf on overhangs non-concurrent with other live loads.
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 142 lb uplift at joint 5 and 41 lb uplift at joint 4.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ25	Jack-Closed	1	1	Job Reference (optional)



Scale = 1:19.6

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.64	Vert(LL)	-0.01	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.13	Vert(CT)	-0.02	4-5	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.01	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 22 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=144/ Mechanical, 5=426/0-11-4, (min. 0-1-8)
Max Horiz 5=44 (LC 7)
Max Uplift 4=-18 (LC 10), 5=-134 (LC 6)
Max Grav 4=144 (LC 1), 5=473 (LC 16)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-5=-446/386

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) This truss has been designed for greater of min roof live load of 20.0 psf or 2.00 times flat roof load of 30.0 psf on overhangs non-concurrent with other live loads.
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 134 lb uplift at joint 5 and 18 lb uplift at joint 4.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ26	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:27:08 Page: 1
ID:MrE_pkJWODQSx23_oI_ofRzcXmG-XrSDqnmRIqwIRV8mullPwWYgTLH68c_o1WS3AazUlqH



Scale = 1:19.6

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.62	Vert(LL)	0.00	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.03	Vert(CT)	0.00	4-5	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.01	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 14 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 2-3-1 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 4=-5/ Mechanical, 5=379/0-11-4, (min. 0-1-8)
Max Horiz 5=43 (LC 7)
Max Uplift 4=-135 (LC 16), 5=-144 (LC 6)
Max Grav 4=36 (LC 6), 5=522 (LC 16)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-5=-509/361

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) This truss has been designed for greater of min roof live load of 20.0 psf or 2.00 times flat roof load of 30.0 psf on overhangs non-concurrent with other live loads.
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 144 lb uplift at joint 5 and 135 lb uplift at joint 4.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ27	Monopitch	11	1	Job Reference (optional)



Scale = 1:23.6

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.22	Vert(LL)	n/a	-	n/a	999	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.02	Vert(CT)	n/a	-	n/a	999		
TCDL	12.0	Rep Stress Incr	YES	WB	0.08	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 10 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud

REACTIONS (lb/size) 2=0/ Mechanical, 3=167/ Mechanical
Max Horiz 2=279 (LC 2), 3=-279 (LC 2)
Max Uplift 3=-57 (LC 8)
Max Grav 3=407 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-134/282
WEBS 1-3=-341/149

BRACING

TOP CHORD	Structural wood sheathing directly applied or 2-0-0 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.


MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

NOTES

1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Refer to girder(s) for truss to truss connections.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 57 lb uplift at joint 3.
10) Non Standard bearing condition. Review required.
11) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	D1	Common	1	1	Job Reference (optional)



Scale = 1:42

Plate Offsets (X, Y): [6:0-3-0,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.18	Vert(LL)	-0.06	10-11	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.36	Vert(CT)	-0.12	10-11	>999	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.41	Horz(CT)	0.02	15	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 82 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud
OTHERS	2x6 DF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 13=891/0-5-8, (min. 0-1-8), 15=873/0-4-1, (min. 0-1-8)
Max Horiz 13=37 (LC 9)
Max Uplift 13=-168 (LC 6), 15=-164 (LC 7)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-1632/687, 4-5=-1632/687
BOT CHORD 12-13=-498/1213, 11-12=-498/1213, 10-11=-520/1205
WEBS 2-13=-293/177, 3-11=-145/444, 3-13=-1349/684, 5-11=-122/452, 5-10=-1201/578, 10-15=-213/510, 6-15=-213/510


NOTES

1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Bearing at joint(s) 15 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 168 lb uplift at joint 13 and 164 lb uplift at joint 15.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	D2	Hip Girder	1	2	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:27:09 Page: 1
ID:t4ZY6vl8SkVvxYSJNCf?YUzcWc5-?10b27n337292fjySTGeTk5y9lVBty5yGACci0zUlqG



Scale = 1:48

Plate Offsets (X, Y): [7:0-2-12,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.18	Vert(LL)	-0.09	13-14	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.55	Vert(CT)	-0.13	13-14	>999	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	NO	WB	0.47	Horz(CT)	0.01	18	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	7.0										Weight: 193 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x6 DF No.2
WEBS 2x4 DF Stud
OTHERS 2x6 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or 5-11-14 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 4-5.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS (lb/size) 16=1642/0-5-8, (min. 0-1-8), 18=1616/0-4-1, (min. 0-1-8)
Max Horiz 16=34 (LC 5)
Max Uplift 16=-329 (LC 4), 18=-323 (LC 5)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-4895/849, 4-23=-4834/850, 5-23=-4834/850, 5-6=-4850/854, 6-7=-2850/486
BOT CHORD 15-16=-481/2819, 14-15=-481/2819, 14-24=-840/4882, 13-24=-840/4882, 12-13=-497/2847, 11-12=-65/326
WEBS 2-16=-283/74, 3-16=-2999/574, 7-12=-501/2782, 3-14=-398/2236, 6-13=-406/2152, 6-12=-1077/221, 7-18=-461/91

NOTES
1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
4) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
5) Provide adequate drainage to prevent water ponding.
6) All plates are MT20 plates unless otherwise indicated.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Bearing at joint(s) 18 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 329 lb uplift at joint 16 and 323 lb uplift at joint 18.
11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
12) Use Simpson Strong-Tie THJA26 (THJA26 on 2 ply, Left Hand Hip) or equivalent at 8-0-6 from the left end to connect truss(es) DJ1 (1 ply 2x4 DF), DJ7 (1 ply 2x4 DF) to front face of bottom chord.
13) Use Simpson Strong-Tie THJA26 (THJA26 on 2 ply, Right Hand Hip) or equivalent at 10-4-8 from the left end to connect truss(es) DJ1 (1 ply 2x4 DF), DJ8 (1 ply 2x4 DF) to front face of bottom chord.
14) Fill all nail holes where hanger is in contact with lumber.
15) "NAILED" indicates Girder: 3-10d (0.148" x 3") toe-nails per NDS guidelines.

LOAD CASE(S) Standard

Continued on page 2

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	D2	Hip Girder	1	**2**	Job Reference (optional)

1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-8=-84, 11-17=-14, 9-10=-14
Concentrated Loads (lb)
Vert: 14=-638 (F), 13=-626 (F), 24=-229 (F)

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	DJ1	Jack-Closed	3	1	Job Reference (optional)




Plate Offsets (X, Y): [2:0-2-12,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.56	Vert(LL)	-0.04	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.25	Vert(CT)	-0.07	4-5	>962	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.12	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 37 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud
OTHERS	2x6 DF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=243/ Mechanical, 8=502/0-4-1, (min. 0-1-8)
Max Horiz 8=45 (LC 7)
Max Uplift 4=-35 (LC 6), 8=-128 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


NOTES

1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Bearing at joint(s) 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 35 lb uplift at joint 4 and 128 lb uplift at joint 8.
10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	DJ2	Jack-Closed	3	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:27:09 Page: 1
ID:t4ZY6vl8SkVvxYSJNCf?YUzcWc5-?10b27n337292fjySTGeTk5xnlcUt1AyGACci0zUlqG



Scale = 1:39.2

0-5-8

Plate Offsets (X, Y): [2:0-2-12,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.20	Vert(LL)	-0.01	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.08	Vert(CT)	-0.01	4-5	>999	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.14	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 29 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud
OTHERS	2x6 DF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=120/ Mechanical, 8=420/0-4-1, (min. 0-1-8)
Max Horiz 8=44 (LC 7)
Max Uplift 4=-19 (LC 10), 8=-118 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES

1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Bearing at joint(s) 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 19 lb uplift at joint 4 and 118 lb uplift at joint 8.
10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	DJ3	Jack-Closed	3	1	Job Reference (optional)



Scale = 1:39.2

0-5-8

Plate Offsets (X, Y): [2:0-2-12,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.08	Vert(LL)	0.00	5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.02	Vert(CT)	0.00	5	>999	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.14	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 21 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud
OTHERS	2x6 DF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied or 3-10-15 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=-47/ Mechanical, 8=392/0-4-1, (min. 0-1-8)
Max Horiz 8=42 (LC 7)
Max Uplift 4=-47 (LC 1), 8=-128 (LC 6)
Max Grav 4=35 (LC 6), 8=392 (LC 1)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES

1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Bearing at joint(s) 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 47 lb uplift at joint 4 and 128 lb uplift at joint 8.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	DJ4	Jack-Closed	4	1	Job Reference (optional)



Scale = 1:23

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.07	Vert(LL)	n/a	-	n/a	999	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.02	Vert(CT)	n/a	-	n/a	999		
TCDL	12.0	Rep Stress Incr	YES	WB	0.04	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 10 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 1-10-15 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 2=0/ Mechanical, 3=159/ Mechanical
Max Horiz 2=103 (LC 1), 3=-103 (LC 1)
Max Uplift 3=-54 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 54 lb uplift at joint 3.
9) Non Standard bearing condition. Review required.
10) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	DJ5	Jack-Closed	1	1	Job Reference (optional)



Scale = 1:28.2

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.18	Vert(LL)	0.00	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.07	Vert(CT)	-0.01	4-5	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.10	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 27 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 4=113/ Mechanical, 5=438/0-5-8, (min. 0-1-8)
Max Horiz 5=44 (LC 7)
Max Uplift 4=-14 (LC 10), 5=-126 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-5=-341/347

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 126 lb uplift at joint 5 and 14 lb uplift at joint 4.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	DJ6	Jack-Closed	1	1	Job Reference (optional)



Scale = 1:31.7

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.32	Vert(LL)	0.00	3-4	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.04	Vert(CT)	0.00	3-4	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.11	Horz(CT)	0.00	3	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 18 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 3-10-15 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 3=-63/ Mechanical, 4=418/0-5-8, (min. 0-1-8)
Max Horiz 4=42 (LC 7)
Max Uplift 3=-63 (LC 1), 4=-145 (LC 6)
Max Grav 3=49 (LC 6), 4=418 (LC 1)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-279/263
WEBS 1-4=-301/310, 2-4=-340/389

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 63 lb uplift at joint 3 and 145 lb uplift at joint 4.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	DJ7	Diagonal Hip Girder	1	1	Job Reference (optional)





Scale = 1:37.9

0-9-4

Plate Offsets (X, Y): [2:0-3-4,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.29	Vert(LL)	-0.03	5-6	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.49	Vert(CT)	-0.05	5-6	>999	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	NO	WB	0.32	Horz(CT)	0.00	5	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	7.0										Weight: 52 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud
OTHERS	2x10 DF SS

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 5=428/ Mechanical, 10=1014/0-5-6, (min. 0-1-8)
Max Horiz 10=40 (LC 27)
Max Uplift 5=-85 (LC 8), 10=-357 (LC 4)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	2-3=-595/198
BOT CHORD	6-17=-182/592, 5-17=-182/592
WEBS	2-6=-256/826, 3-5=-526/188, 8-10=-152/387, 2-10=-152/387

NOTES

1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Bearing at joint(s) 10 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 85 lb uplift at joint 5 and 357 lb uplift at joint 10.
10) "NAILED" indicates Girder: 3-10d (0.148" x 3") toe-nails per NDS guidelines.
11) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 139 lb down and 63 lb up at 2-5-15, and 139 lb down and 63 lb up at 2-5-15 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
12) Special hanger(s) or other connection device(s) shall be provided at 2-9-8 from the left end sufficient to connect trusses DJ4 (1 ply 2x4 DF) to front face of bottom chord, skewed 45.0 deg. to the left, sloping 0.0 deg down.. The design/selection of such special connection device(s) is the responsibility of others.
13) Special hanger(s) or other connection device(s) shall be provided at 2-9-8 from the left end sufficient to connect trusses DJ4 (1 ply 2x4 DF) to back face of bottom chord, skewed 45.0 deg. to the right, sloping 0.0 deg down.. The design/selection of such special connection device(s) is the responsibility of others.
14) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard


1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-4=-84, 8-9=-14, 5-7=-14
Concentrated Loads (lb)

Continued on page 2

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	DJ7	Diagonal Hip Girder	1	1	Job Reference (optional)

Vert: 8=-278 (F=-139, B=-139), 16=82 (F=38, B=44), 17=-194 (F=-101, B=-93)

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	DJ8	Diagonal Hip Girder	1	1	Job Reference (optional)



Scale = 1:37.9

Plate Offsets (X, Y): [2:0-2-8,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.25	Vert(LL)	-0.03	5-6	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.49	Vert(CT)	-0.05	5-6	>999	180	M18AHS	132/127
TCDL	12.0	Rep Stress Incr	NO	WB	0.34	Horz(CT)	0.00	5	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	7.0										Weight: 52 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud
OTHERS 2.0 RigidLam DF LVL 1-1/2 x 11-7/8

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 5=417/ Mechanical, 10=1036/0-5-12, (min. 0-1-8)
Max Horiz 10=40 (LC 7)
Max Uplift 5=-78 (LC 8), 10=-356 (LC 4)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-556/170
BOT CHORD 6-17=-154/554, 5-17=-154/554
WEBS 2-6=-243/834, 3-5=-486/157, 8-10=-154/394, 2-10=-154/394

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Bearing at joint(s) 10 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 78 lb uplift at joint 5 and 356 lb uplift at joint 10.
10) "NAILED" indicates Girder: 3-10d (0.148" x 3") toe-nails per NDS guidelines.
11) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 139 lb down and 63 lb up at 2-6-7, and 139 lb down and 63 lb up at 2-6-7 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
12) Special hanger(s) or other connection device(s) shall be provided at 2-9-8 from the left end sufficient to connect trusses DJ4 (1 ply 2x4 DF) to front face of bottom chord, skewed 45.0 deg. to the left, sloping 0.0 deg down.. The design/selection of such special connection device(s) is the responsibility of others.
13) Special hanger(s) or other connection device(s) shall be provided at 2-9-8 from the left end sufficient to connect trusses DJ4 (1 ply 2x4 DF) to back face of bottom chord, skewed 45.0 deg. to the right, sloping 0.0 deg down.. The design/selection of such special connection device(s) is the responsibility of others.
14) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).


LOAD CASE(S) Standard
1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-4=-84, 8-9=-14, 5-7=-14
Concentrated Loads (lb)

Continued on page 2


Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	DJ8	Diagonal Hip Girder	1	1	Job Reference (optional)

Vert: 8=-278 (F=-139, B=-139), 16=76 (F=38, B=38), 17=-201 (F=-101, B=-101)

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	E1	Jack-Closed	3	1	Job Reference (optional)



30-3-12 30-3-12



Scale = 1:32.3

0-2-12

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.31	Vert(LL)	-0.06	5-6	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.30	Vert(CT)	-0.11	5-6	>837	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.19	Horz(CT)	0.01	5	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 44 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 5=346/ Mechanical, 6=606/0-5-8, (min. 0-1-8)
Max Horiz 6=46 (LC 7)
Max Uplift 5=-58 (LC 10), 6=-147 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
BOT CHORD 5-6=-298/489
WEBS 2-6=-292/235, 3-5=-438/324, 3-6=-566/485

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 147 lb uplift at joint 6 and 58 lb uplift at joint 5.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard


Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	E3	Half Hip Girder	2	**2**	Job Reference (optional)



THJA26

30-3-12 30-3-12

2-2-12



Scale = 1:32.3

0-2-12

Loading	(psf)	**Spacing**	2-0-0	**CSI**		**DEFL**	in	(loc)	l/defl	L/d	**PLATES**	**GRIP**
TCLL	30.0	Plate Grip DOL	1.15	TC	0.26	Vert(LL)	-0.01	6-7	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.14	Vert(CT)	-0.02	6-7	>999	180		
TCDL	12.0	Rep Stress Incr	NO	WB	0.15	Horz(CT)	0.00	5	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	7.0										Weight: 104 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x6 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 3-4.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.


REACTIONS (lb/size) 5=818/ Mechanical, 7=774/0-5-8, (min. 0-1-8)
Max Horiz 7=42 (LC 23)
Max Uplift 5=-155 (LC 4), 7=-183 (LC 4)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1039/201
BOT CHORD 5-6=-176/993
WEBS 3-6=-69/388, 3-5=-1167/221, 2-7=-694/178, 2-6=-194/898

NOTES
1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
4) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
5) Provide adequate drainage to prevent water ponding.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Refer to girder(s) for truss to truss connections.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 155 lb uplift at joint 5 and 183 lb uplift at joint 7.
10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
11) Use Simpson Strong-Tie THJA26 (THJA26 on 2 ply, Left Hand Hip) or equivalent at 8-0-6 from the left end to connect truss(es) EJ1 (1 ply 2x4 DF), EJ5 (1 ply 2x4 DF) to front face of bottom chord.
12) Fill all nail holes where hanger is in contact with lumber.

LOAD CASE(S) Standard
1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-4=-84, 5-8=-14
Concentrated Loads (lb)
Vert: 6=-640 (F)

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	EGIR	Roof Special Girder	1	2	Job Reference (optional)





Scale = 1:40.7

Plate Offsets (X, Y): [2:0-2-8,0-1-8], [7:0-2-8,0-1-8], [11:0-3-8,0-3-8], [15:0-3-8,0-3-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.55	Vert(LL)	-0.26	12-13	>830	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.90	Vert(CT)	-0.40	12-13	>534	180		
TCDL	12.0	Rep Stress Incr	NO	WB	0.97	Horz(CT)	0.03	10	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	7.0										Weight: 230 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x6 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 3-11-5 oc purlins, except end verticals, and 2-0-0 oc purlins (4-2-12 max.): 4-5.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 16-17,9-10.

REACTIONS (lb/size) 10=2390/0-5-8, (min. 0-1-8), 16=2372/0-5-8, (min. 0-1-8)
Max Horiz 16=34 (LC 23)
Max Uplift 10=-458 (LC 5), 16=-455 (LC 4)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-325/69, 2-3=-5811/1005, 3-4=-9077/1575, 4-5=-8993/1564, 5-6=-8991/1559, 6-7=-5881/1018, 7-8=-323/70
BOT CHORD 15-16=-80/314, 14-15=-983/5806, 13-14=-983/5806, 13-18=-1551/9075, 12-18=-1551/9075, 12-19=-1030/5875, 11-19=-1030/5875, 10-11=-51/312
WEBS 1-16=-72/408, 8-10=-73/406, 2-16=-2163/412, 7-10=-2188/417, 6-12=-605/3281, 6-11=-1395/277, 7-11=-1037/5810, 3-13=-635/3446, 3-15=-1449/287, 2-15=-1022/5735

NOTES
1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
4) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
5) Provide adequate drainage to prevent water ponding.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 455 lb uplift at joint 16 and 458 lb uplift at joint 10.
9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
10) Use Simpson Strong-Tie HGUS26-2 (20-10d Girder, 6-10d Truss) or equivalent at 8-1-8 from the left end to connect truss(es) E3 (2 ply 2x6 DF) to back face of bottom chord, skewed 0.0 deg.to the left, sloping 0.0 deg. down.
11) Use Simpson Strong-Tie LUS24 (4-10d Girder, 2-10d Truss) or equivalent at 10-0-12 from the left end to connect truss(es) E1 (1 ply 2x4 DF) to back face of bottom chord, skewed 0.0 deg.to the left, sloping 0.0 deg. down.
12) Use Simpson Strong-Tie LUS24 (4-10d Girder, 2-10d Truss) or equivalent spaced at 1-1-3 oc max. starting at 11-1-15 from the left end to 12-3-2 to connect truss(es) E1 (1 ply 2x4 DF) to back face of bottom chord.
13) Use Simpson Strong-Tie HGUS26-2 (20-10d Girder, 6-10d Truss) or equivalent at 14-2-6 from the left end to connect truss(es) E3 (2 ply 2x6 DF) to back face of bottom chord, skewed 0.0 deg.to the left, sloping 0.0 deg. down.
14) Fill all nail holes where hanger is in contact with lumber.

Continued on page 2


Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	EGIR	Roof Special Girder	1	**2**	Job Reference (optional)


LOAD CASE(S) Standard

1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
   Uniform Loads (lb/ft)
   Vert: 1-8=-84, 9-17=-14
   Concentrated Loads (lb)
   Vert: 14=-804 (B), 13=-332 (B), 12=-332 (B), 18=-332 (B), 19=-804 (B)

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	EJ1	Jack-Closed	2	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:27:11 Page: 1
ID:dymiiCP?1jtQ?Zp7trY27TzcWW5-yQ8LSpoKbIItIztLZuI6Y9ADhZGILyvEjUhjnvzUlqE





Scale = 1:27.7

0-2-12

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.43	Vert(LL)	-0.03	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.19	Vert(CT)	-0.05	4-5	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.12	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 36 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 4=238/ Mechanical, 5=518/0-5-8, (min. 0-1-8)
Max Horiz 5=45 (LC 7)
Max Uplift 4=-31 (LC 6), 5=-134 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-5=-471/429

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 31 lb uplift at joint 4 and 134 lb uplift at joint 5.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	EJ2	Jack-Closed	4	1	Job Reference (optional)



Scale = 1:31.9

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.69	Vert(LL)	0.00	3-4	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.07	Vert(CT)	-0.01	3-4	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.13	Horz(CT)	0.00	3	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 26 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 3=113/ Mechanical, 4=438/0-5-8, (min. 0-1-8)
Max Horiz 4=44 (LC 7)
Max Uplift 3=-14 (LC 10), 4=-126 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-408/394
WEBS 1-4=-451/462, 2-4=-416/455

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 14 lb uplift at joint 3 and 126 lb uplift at joint 4.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	EJ3	Jack-Closed	4	1	Job Reference (optional)



Scale = 1:31.7

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.32	Vert(LL)	0.00	3-4	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.04	Vert(CT)	0.00	3-4	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.11	Horz(CT)	0.00	3	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 18 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 3-10-15 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 3=-63/ Mechanical, 4=418/0-5-8, (min. 0-1-8)
Max Horiz 4=42 (LC 7)
Max Uplift 3=-63 (LC 1), 4=-145 (LC 6)
Max Grav 3=49 (LC 6), 4=418 (LC 1)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-279/263
WEBS 1-4=-301/310, 2-4=-340/389

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 63 lb uplift at joint 3 and 145 lb uplift at joint 4.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	EJ4	Jack-Closed	4	1	Job Reference (optional)



Scale = 1:23

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.07	Vert(LL)	n/a	-	n/a	999	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.02	Vert(CT)	n/a	-	n/a	999		
TCDL	12.0	Rep Stress Incr	YES	WB	0.04	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 10 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 1-10-15 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 2=0/ Mechanical, 3=159/ Mechanical
Max Horiz 2=103 (LC 1), 3=-103 (LC 1)
Max Uplift 3=-54 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 54 lb uplift at joint 3.
9) Non Standard bearing condition. Review required.
10) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	EJ5	Diagonal Hip Girder	2	1	Job Reference (optional)



Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.27	Vert(LL)	-0.03	5-6	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.50	Vert(CT)	-0.05	5-6	>999	180		
TCDL	12.0	Rep Stress Incr	NO	WB	0.30	Horz(CT)	0.00	5	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	7.0										Weight: 50 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 5=436/ Mechanical, 7=1008/0-7-12, (min. 0-1-8)
Max Horiz 7=40 (LC 5)
Max Uplift 5=-93 (LC 8), 7=-354 (LC 4)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-110/256, 2-3=-623/227
BOT CHORD 7-10=-253/126, 6-10=-253/126, 6-11=-212/621, 5-11=-212/621
WEBS 1-7=-290/118, 2-7=-616/184, 2-6=-282/903, 3-5=-557/220

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 354 lb uplift at joint 7 and 93 lb uplift at joint 5.
8) "NAILED" indicates Girder: 3-10d (0.148" x 3") toe-nails per NDS guidelines.
9) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-4=-84, 5-8=-14
Concentrated Loads (lb)
Vert: 7=-278 (F=-139, B=-139), 10=89 (F=44, B=44), 11=-187 (F=-93, B=-93)