
Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FA1	Floor	2	1	Job Reference (optional)



22-1-14 22-1-14

10-7-9

9-7-9

8-7-9 17-6-12
8-7-9 6-11-3

1-0-0

Scale = 1:44.4

1-0-0

Plate Offsets (X, Y): [1:Edge,0-1-8], [6:0-1-8,Edge], [14:0-1-8,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.73	Vert(LL)	-0.20	14-15	>999	360	MT20	220/195
TCDL	11.0	Lumber DOL	1.00	BC	0.81	Vert(CT)	-0.27	14-15	>786	240		
BCLL	0.0	Rep Stress Incr	YES	WB	0.42	Horz(CT)	0.04	11	n/a	n/a		
BCDL	7.0	Code	IRC2021/TPI2014	Matrix-AS							Weight: 90 lb	FT = 20%F, 11%E

LUMBER
TOP CHORD 2x4 DF No.2(flat)
BOT CHORD 2x4 DF No.2(flat)
WEBS 2x4 DF Stud(flat)

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

REACTIONS (lb/size) 11=1008/0-5-8, (min. 0-1-8), 17=1008/ Mechanical


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1942/0, 3-4=-1942/0, 4-5=-2294/0, 5-6=-2294/0, 6-7=-1769/0, 7-8=-1769/0, 8-9=-1769/0
BOT CHORD 16-17=0/1171, 15-16=0/1171, 14-15=0/2289, 13-14=0/2294, 12-13=0/2294, 11-12=0/910
WEBS 2-17=-1464/0, 2-15=0/972, 4-15=-438/0, 4-14=-232/356, 6-12=-782/0, 7-12=-284/31, 9-12=0/1083, 9-11=-1289/0

NOTES
1) Unbalanced floor live loads have been considered for this design.
2) Refer to girder(s) for truss to truss connections.
3) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
4) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FA2	Floor	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:30 Page: 1
ID:DO0SOwskBCShUJeoNzrXFDzhXzI-Z2g2z_0EhMrXFJHqr__LZLoBJGrwxzIBscg862zUlfd



Scale = 1:65

Plate Offsets (X, Y): [6:0-1-8,Edge], [14:Edge,0-1-8], [17:0-1-8,Edge], [20:0-1-8,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.75	Vert(LL)	-0.20	20-22	>999	360	MT20	220/195
TCDL	11.0	Lumber DOL	1.00	BC	0.84	Vert(CT)	-0.27	20-22	>756	240		
BCLL	0.0	Rep Stress Incr	YES	WB	0.43	Horz(CT)	0.04	17	n/a	n/a		
BCDL	7.0	Code	IRC2021/TPI2014	Matrix-AS							Weight: 106 lb	FT = 20%F, 11%E

LUMBER

TOP CHORD	2x4 DF No.2(flat)
BOT CHORD	2x4 DF No.2(flat)
WEBS	2x4 DF Stud(flat)
OTHERS	2x4 DF Stud(flat)

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.

REACTIONS All bearings 3-2-4. except 23= Mechanical
(lb) - Max Uplift All uplift 100 (lb) or less at joint(s) 14
Max Grav All reactions 250 (lb) or less at joint(s) 14, 15, 16 except
17=1107 (LC 1), 23=985 (LC 1)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


TOP CHORD	2-3=-1882/0, 3-4=-1882/0, 4-5=-2178/0, 5-6=-2178/0, 6-7=-1602/0, 7-8=-1602/0
BOT CHORD	22-23=0/1141, 21-22=0/2198, 20-21=0/2198, 19-20=0/2178, 18-19=0/2178, 17-18=0/726
WEBS	2-23=-1427/0, 2-22=0/935, 4-22=-398/0, 4-20=-258/314, 6-18=-823/0, 7-18=-286/34, 8-18=0/1105, 8-17=-1146/0


NOTES

1) Unbalanced floor live loads have been considered for this design.
2) All plates are 1.5x4 (||) MT20 unless otherwise indicated.
3) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
4) Gable studs spaced at 1-4-0 oc.
5) Refer to girder(s) for truss to truss connections.
6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 14.
7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
8) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
9) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FA3	Floor	5	1	Job Reference (optional)





Scale = 1:50.9

Plate Offsets (X, Y): [6:0-1-8,Edge], [10:0-1-8,Edge], [13:0-1-8,Edge], [16:0-1-8,Edge], [20:0-1-8,0-0-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.88	Vert(LL)	-0.24	14-15	>999	360	M18AHS	169/162
TCDL	11.0	Lumber DOL	1.00	BC	0.95	Vert(CT)	-0.32	14-15	>754	240	MT20	220/195
BCLL	0.0	Rep Stress Incr	YES	WB	0.47	Horz(CT)	0.06	12	n/a	n/a		
BCDL	7.0	Code	IRC2021/TPI2014	Matrix-AS							Weight: 106 lb	FT = 20%F, 11%E

LUMBER

TOP CHORD	2x4 DF No.2(flat)
BOT CHORD	2x4 DF No.2(flat)
WEBS	2x4 DF Stud(flat)
OTHERS	2x4 DF Stud(flat)

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.

REACTIONS (lb/size) 12=1156/0-5-8, (min. 0-1-8), 19=1162/ Mechanical

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


TOP CHORD	2-3=-2344/0, 3-4=-2344/0, 4-5=-3080/0, 5-6=-3080/0, 6-7=-2864/0, 7-8=-2864/0, 8-9=-1203/0, 9-10=-1203/0
BOT CHORD	18-19=0/1373, 17-18=0/2907, 16-17=0/2907, 15-16=0/3080, 14-15=0/3080, 13-14=0/2188, 12-13=0/1203
WEBS	5-16=-419/14, 6-14=-578/83, 7-14=-331/0, 8-14=0/852, 8-13=-1243/0, 10-13=0/814, 10-12=-1609/0, 2-19=-1716/0, 2-18=0/1226, 3-18=-253/0, 4-18=-710/0, 4-16=-50/650


NOTES

1) Unbalanced floor live loads have been considered for this design.
2) All plates are MT20 plates unless otherwise indicated.
3) Refer to girder(s) for truss to truss connections.
4) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
5) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
6) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FA4	Floor	3	1	Job Reference (optional)





Scale = 1:50.9

Plate Offsets (X, Y): [1:Edge,0-1-8], [6:0-1-8,Edge], [10:0-1-8,Edge], [13:0-1-8,Edge], [16:0-1-8,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.90	Vert(LL)	-0.24	14-15	>999	360	M18AHS	169/162
TCDL	11.0	Lumber DOL	1.00	BC	0.96	Vert(CT)	-0.32	14-15	>744	240	MT20	220/195
BCLL	0.0	Rep Stress Incr	YES	WB	0.47	Horz(CT)	0.06	12	n/a	n/a		
BCDL	7.0	Code	IRC2021/TPI2014	Matrix-AS							Weight: 104 lb	FT = 20%F, 11%E

LUMBER

TOP CHORD	2x4 DF No.2(flat)
BOT CHORD	2x4 DF No.2(flat)
WEBS	2x4 DF Stud(flat)

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.

REACTIONS (lb/size) 12=1166/0-5-8, (min. 0-1-8), 19=1166/ Mechanical

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


TOP CHORD	2-3=-2354/0, 3-4=-2354/0, 4-5=-3099/0, 5-6=-3099/0, 6-7=-2889/0, 7-8=-2889/0, 8-9=-1239/0, 9-10=-1239/0
BOT CHORD	18-19=0/1378, 17-18=0/2921, 16-17=0/2921, 15-16=0/3099, 14-15=0/3099, 13-14=0/2218, 12-13=0/1239
WEBS	5-16=-423/11, 6-14=-574/92, 7-14=-333/0, 8-14=0/847, 8-13=-1234/0, 10-13=0/809, 10-12=-1640/0, 2-19=-1722/0, 2-18=0/1231, 3-18=-253/0, 4-18=-716/0, 4-16=-46/657

NOTES

1) Unbalanced floor live loads have been considered for this design.
2) All plates are MT20 plates unless otherwise indicated.
3) Refer to girder(s) for truss to truss connections.
4) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
5) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FA5	Floor	7	1	Job Reference (optional)



Scale = 1:44.4

Plate Offsets (X, Y): [1:0-5-0,Edge], [6:0-1-8,Edge], [10:0-1-8,Edge], [13:0-4-0,Edge], [14:Edge,0-0-12], [16:0-1-8,Edge], [17:0-1-8,Edge], [22:Edge,0-0-12], [23:0-4-8,0-2-0], [25:0-3-12,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.77	Vert(LL)	-0.19	16-17	>999	360	MT20	220/195
TCDL	11.0	Lumber DOL	1.00	BC	0.91	Vert(CT)	-0.27	16-17	>841	240	M18AHS	169/162
BCLL	0.0	Rep Stress Incr	YES	WB	0.64	Horz(CT)	0.03	26	n/a	n/a		
BCDL	7.0	Code	IRC2021/TPI2014	Matrix-AS							Weight: 115 lb	FT = 20%F, 11%E

LUMBER

TOP CHORD	2x4 DF No.2(flat)
BOT CHORD	2x4 DF No.2(flat)
WEBS	2x4 DF Stud(flat)
OTHERS	2x4 DF Stud(flat)

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.

REACTIONS (lb/size) 25=1076/0-6-1, (min. 0-1-8), 26=1080/0-3-8, (min. 0-1-8)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-1417/0, 2-3=-1414/0, 3-4=-1414/0, 4-5=-2716/0, 5-6=-2716/0, 6-7=-2781/0, 7-8=-2781/0, 8-9=-1630/0, 9-10=-1630/0, 10-11=-1395/0, 11-12=-1395/0, 12-13=-1396/0

BOT CHORD 20-21=0/2236, 19-20=0/2236, 18-19=0/2781, 17-18=0/2781, 16-17=0/2372, 15-16=0/1630


WEBS 7-17=-278/0, 1-21=0/1578, 4-21=-1037/0, 4-19=0/606, 5-19=-293/95, 6-19=-523/250, 8-17=0/700, 8-16=-936/0, 10-16=0/630, 10-15=-798/0, 13-15=0/1661, 1-25=-1102/0, 13-26=-1110/0

NOTES

1) Unbalanced floor live loads have been considered for this design.
2) All plates are MT20 plates unless otherwise indicated.
3) All plates are 3x4 (=) MT20 unless otherwise indicated.
4) Bearing at joint(s) 25, 26 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
5) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
6) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FA6	Floor Supported Gable	1	1	Job Reference (optional)



Scale = 1:49.3

Plate Offsets (X, Y): [20:Edge,0-0-12], [36:Edge,0-0-12], [37:0-4-8,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.06	Vert(LL)	n/a	-	n/a	999	MT20	220/195
TCDL	11.0	Lumber DOL	1.00	BC	0.01	Vert(CT)	0.00	21-22	>999	240		
BCLL	0.0	Rep Stress Incr	YES	WB	0.03	Horz(CT)	0.00	39	n/a	n/a		
BCDL	7.0	Code	IRC2021/TPI2014	Matrix-AS							Weight: 105 lb	FT = 20%F, 11%E

LUMBER

TOP CHORD	2x4 DF No.2(flat)
BOT CHORD	2x4 DF No.2(flat)
WEBS	2x4 DF Stud(flat)
OTHERS	2x4 DF Stud(flat)

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.

REACTIONS All bearings 19-5-1. except 39=0-3-8
(lb) - Max Uplift All uplift 100 (lb) or less at joint(s) 39
Max Grav All reactions 250 (lb) or less at joint(s) 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 34, 35, 36, 39

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


NOTES


1) All plates are 1.5x4 (||) MT20 unless otherwise indicated.
2) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
3) Gable studs spaced at 1-4-0 oc.
4) Bearing at joint(s) 39 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 39.
6) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
7) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FA7	Floor	7	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:31 Page: 1
ID:haarbGtMyWaX6SD_whMmnQzhXzH-1FEQAK1sSgzOtTs1PiVa6YKTrgH4gP?K4GPieUzUlfc





Scale = 1:41

Plate Offsets (X, Y): [8:0-1-8,Edge], [10:0-4-8,0-0-0], [12:0-1-8,Edge], [17:0-4-8,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.26	Vert(LL)	-0.06	13-14	>999	360	MT20	220/195
TCDL	11.0	Lumber DOL	1.00	BC	0.47	Vert(CT)	-0.11	13-14	>999	240		
BCLL	0.0	Rep Stress Incr	YES	WB	0.46	Horz(CT)	0.02	17	n/a	n/a		
BCDL	7.0	Code	IRC2021/TPI2014	Matrix-AS							Weight: 90 lb	FT = 20%F, 11%E

LUMBER

TOP CHORD	2x4 DF No.2(flat)
BOT CHORD	2x4 DF No.2(flat)
WEBS	2x4 DF Stud(flat)
OTHERS	2x4 DF Stud(flat)

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.

REACTIONS (lb/size) 15=956/0-5-8, (min. 0-1-8), 17=862/0-6-1, (min. 0-1-8)
Max Grav 15=956 (LC 1), 17=863 (LC 4)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	10-17=-847/0, 3-4=-1549/0, 4-5=-1549/0, 5-6=-1586/0, 6-7=-1586/0, 7-8=-1586/0, 8-9=-1028/0, 9-10=-1032/0
BOT CHORD	14-15=0/955, 13-14=0/1729, 12-13=0/1028
WEBS	3-15=-1205/0, 3-14=0/757, 6-13=-258/0, 8-13=0/698, 8-12=-641/0, 10-12=0/1196

NOTES

1) Unbalanced floor live loads have been considered for this design.
2) Bearing at joint(s) 17 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
3) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
4) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
5) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FA8	Floor	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:32 Page: 1
ID:haarbGtMyWaX6SD_whMmnQzhXzH-WRnoOg2UD_6FVdRDyP0pemtYZ4eNPsbUJw9FAxzUlfb




Plate Offsets (X, Y): [1:Edge,0-0-12], [12:0-1-8,Edge], [15:0-1-8,Edge], [22:0-1-8,0-0-12], [23:0-1-8,0-0-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.64	Vert(LL)	-0.07	16-17	>999	360	MT20	220/195
TCDL	11.0	Lumber DOL	1.00	BC	0.40	Vert(CT)	-0.10	16-17	>999	240	M18AHS	169/162
BCLL	0.0	Rep Stress Incr	YES	WB	0.50	Horz(CT)	0.02	14	n/a	n/a		
BCDL	7.0	Code	IRC2021/TPI2014	Matrix-AS							Weight: 130 lb	FT = 20%F, 11%E

LUMBER

TOP CHORD	2x4 DF No.2(flat)
BOT CHORD	2x4 DF No.2(flat)
WEBS	2x4 DF Stud(flat)
OTHERS	2x4 DF Stud(flat)

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.

REACTIONS (lb/size) 14=617/0-5-8, (min. 0-1-8), 19=2236/0-5-8, (min. 0-1-8)
Max Uplift 14=-9 (LC 3)
Max Grav 14=817 (LC 4), 19=2236 (LC 1)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


TOP CHORD	2-3=0/695, 3-4=0/695, 4-5=0/2420, 5-6=0/2420, 6-7=0/2420, 7-8=-1154/1157, 8-9=-1154/1157, 9-10=-1560/349, 10-11=-1560/349, 11-12=-490/1
BOT CHORD	19-20=-1636/0, 18-19=-1756/380, 17-18=-1756/380, 16-17=-718/1520, 15-16=-138/1191, 14-15=-1/490
WEBS	2-20=-667/0, 4-20=0/1189, 4-19=-1225/0, 7-19=-1721/0, 7-17=0/1305, 9-17=-790/0, 9-16=0/465, 11-16=-265/465, 11-15=-885/173, 12-15=-46/599, 12-14=-945/2

NOTES

1) Unbalanced floor live loads have been considered for this design.
2) All plates are MT20 plates unless otherwise indicated.
3) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 9 lb uplift at joint 14.
4) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
5) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
6) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FA9	Floor	1	1	Job Reference (optional)





Scale = 1:48.5

Plate Offsets (X, Y): [1:Edge,0-0-12], [3:0-1-8,Edge], [11:0-1-8,Edge], [14:0-1-8,Edge], [19:0-1-8,Edge], [21:0-1-8,0-0-12], [22:0-1-8,0-0-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.50	Vert(LL)	-0.07	15-16	>999	360	MT20	220/195
TCDL	11.0	Lumber DOL	1.00	BC	0.43	Vert(CT)	-0.10	15-16	>999	240		
BCLL	0.0	Rep Stress Incr	YES	WB	0.44	Horz(CT)	0.03	13	n/a	n/a		
BCDL	7.0	Code	IRC2021/TPI2014	Matrix-AS							Weight: 122 lb	FT = 20%F, 11%E

LUMBER

TOP CHORD	2x4 DF No.2(flat)
BOT CHORD	2x4 DF No.2(flat)
WEBS	2x4 DF Stud(flat)
OTHERS	2x4 DF Stud(flat)

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.

REACTIONS (lb/size) 13=718/0-5-8, (min. 0-1-8), 18=1936/0-5-8, (min. 0-1-8)
Max Grav 13=849 (LC 4), 18=1936 (LC 1)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=0/700, 3-4=0/1564, 4-5=0/1564, 5-6=-1337/569, 6-7=-1337/569, 7-8=-1337/569, 8-9=-1661/25, 9-10=-1661/25, 10-11=-509/0

BOT CHORD 18-19=-700/0, 17-18=-1040/603, 16-17=-1040/603, 15-16=-262/1662, 14-15=0/1251, 13-14=0/509


WEBS 4-18=-251/0, 2-19=-674/0, 3-19=0/469, 3-18=-1120/0, 5-18=-1547/0, 5-16=0/1143, 8-16=-623/0, 8-15=-1/299, 10-15=-99/517, 10-14=-937/8, 11-14=0/631, 11-13=-982/0

NOTES

1) Unbalanced floor live loads have been considered for this design.
2) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
3) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
4) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FA10	Floor	4	1	Job Reference (optional)





Scale = 1:48.5

Plate Offsets (X, Y): [1:Edge,0-0-12], [3:0-1-8,Edge], [11:0-1-8,Edge], [14:0-1-8,Edge], [19:0-1-8,Edge], [21:0-1-8,0-0-12], [22:0-1-8,0-0-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.40	Vert(LL)	-0.07	15-16	>999	360	MT20	220/195
TCDL	11.0	Lumber DOL	1.00	BC	0.44	Vert(CT)	-0.11	15-16	>999	240		
BCLL	0.0	Rep Stress Incr	YES	WB	0.40	Horz(CT)	0.03	13	n/a	n/a		
BCDL	7.0	Code	IRC2021/TPI2014	Matrix-AS							Weight: 118 lb	FT = 20%F, 11%E

LUMBER

TOP CHORD	2x4 DF No.2(flat)
BOT CHORD	2x4 DF No.2(flat)
WEBS	2x4 DF Stud(flat)
OTHERS	2x4 DF Stud(flat)

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.

REACTIONS (lb/size) 13=775/0-5-8, (min. 0-1-8), 18=1742/0-5-8, (min. 0-1-8)
Max Grav 13=866 (LC 4), 18=1742 (LC 1)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	2-3=0/705, 3-4=0/1093, 4-5=0/1093, 5-6=-1440/238, 6-7=-1440/238, 7-8=-1718/0, 8-9=-1718/0, 9-10=-1718/0, 10-11=-520/0
BOT CHORD	18-19=-705/0, 17-18=-631/730, 16-17=-631/730, 15-16=-5/1742, 14-15=0/1285, 13-14=0/520
WEBS	2-19=-683/0, 3-19=0/472, 3-18=-765/0, 5-18=-1464/0, 5-16=0/1045, 7-16=-531/0, 10-15=-6/546, 10-14=-966/0, 11-14=0/648, 11-13=-1002/0


NOTES

1) Unbalanced floor live loads have been considered for this design.
2) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
3) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
4) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB1	Roof Special	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:32 Page: 1
ID:V1T2Q6Q3LLQiZLM2bLmn7pzgcrd-WRnoOg2UD_6FVdRDyP0pemtVM4YXPksUJw9FAxzUlfb



Scale = 1:65.6

Plate Offsets (X, Y): [2:0-3-8,0-2-8], [3:0-3-8,0-2-8], [6:0-3-7,0-2-0], [7:0-3-7,0-2-9], [9:0-4-0,0-4-12], [15:0-5-8,0-2-8], [16:0-3-8,0-2-8], [20:0-3-8,0-2-8], [21:0-3-8,0-2-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.85	Vert(LL)	-0.63	19-20	>490	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.77	Vert(CT)	-0.74	19-20	>412	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	1.00	Horz(CT)	0.12	15	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.09	19-20	>999	240		
BCDL	7.0										Weight: 225 lb	FT = 20%

LUMBER

TOP CHORD	2x6 DF No.2 *Except* T2:2x6 DF 1950F 1.5E or 2x6 DF SS
BOT CHORD	2x6 DF 1950F 1.5E or 2x6 DF SS *Except* B1:2x6 DF No.2
WEBS	2x4 DF Stud *Except* W12,W11,W6:2x4 DF No.2, W4:2x4 DF 2100F 1.8E

REACTIONS (lb/size) 15=2283/(0-5-8 + bearing block), (req. 0-5-15), 23=1308/0-5-8, (min. 0-3-6)
Max Horiz 23=-46 (LC 8)
Max Uplift 15=-525 (LC 9), 23=-239 (LC 8)
Max Grav 15=5544 (LC 2), 23=3176 (LC 2)

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 9-11.
BOT CHORD	Rigid ceiling directly applied.
WEBS	1 Row at midpt 6-16
WEBS	2 Rows at 1/3 pts 7-15

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	2-25=-5171/442, 3-25=-5159/443, 3-4=-7726/656, 4-5=-7709/581, 5-6=-6050/298, 6-7=-1770/140, 7-8=-1190/5304, 8-9=-1194/5307, 9-26=-696/3415, 10-26=-696/3415, 11-12=-326/50
BOT CHORD	20-21=-383/5158, 19-20=-592/7714, 18-19=-513/7692, 17-18=-247/6038, 16-17=-247/6038, 15-16=-110/1769, 14-15=-3415/751, 13-14=-3415/751, 12-13=-775/243
WEBS	9-15=-2296/606, 9-13=-329/1063, 8-15=-1173/177, 10-13=-2900/557, 10-12=-263/881, 5-19=-242/367, 7-15=-7260/924, 6-18=-100/802, 5-18=-1804/308, 6-16=-4862/671, 7-16=-204/1721, 2-23=-3007/334, 4-19=-770/755, 3-21=-1923/217, 2-21=-503/5321, 3-20=-224/2747, 4-20=-946/106


NOTES

1) 2x6 DF 1950F 1.5E or 2x6 DF SS bearing block 12" long at jt. 15 attached to front face with 3 rows of 10d (0.131"x3") nails spaced 3" o.c. 12 Total fasteners. Bearing is assumed to be DF 1950F 1.5E or SS.
2) Unbalanced roof live loads have been considered for this design.
3) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 32-9-7, Corner (3) 32-9-7 to 36-9-7 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
4) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
5) Provide adequate drainage to prevent water ponding.
6) All plates are MT20 plates unless otherwise indicated.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 239 lb uplift at joint 23 and 525 lb uplift at joint 15.
10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB2	Roof Special	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:33 Page: 1
ID:hElv?7OclcNVYUuEkRgIqTzgcqO-_dLAb037_HE66m?PW6X2BzQgvTrC8DOdYaupiNzUIfa



Scale = 1:65.6

Plate Offsets (X, Y): [3:0-3-7,0-2-1], [8:0-5-8,0-4-8], [14:0-3-8,0-2-0], [16:0-3-8,0-2-12], [19:0-3-8,0-2-8], [20:0-3-8,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.86	Vert(LL)	-0.67	20-21	>462	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.94	Vert(CT)	-0.79	20-21	>388	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.85	Horz(CT)	0.16	16	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.10	20-21	>999	240		
BCDL	7.0										Weight: 200 lb	FT = 20%

LUMBER
TOP CHORD 2x6 DF No.2 *Except* T2:2x6 DF 1950F 1.5E or 2x6 DF SS
BOT CHORD 2x4 DF 2100F 1.8E *Except* B3,B4:2x4 DF No.2
WEBS 2x4 DF Stud *Except* W11,W12:2x4 DF 2100F 1.8E, W4,W13:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (10-0-0 max.): 8-10.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 7-16, 3-24, 4-22

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 16=2276/(0-5-8 + bearing block), (req. 0-5-14), 24=1315/0-5-8, (min. 0-3-7)
Max Horiz 24=49 (LC 11)
Max Uplift 16=-522 (LC 9), 24=-239 (LC 8)
Max Grav 16=5526 (LC 2), 24=3194 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-5057/441, 4-5=-7536/649, 5-6=-7501/570, 6-7=-5909/298, 7-8=-1161/5294, 8-9=-394/1923, 9-27=-46/265, 10-27=-46/265
BOT CHORD 23-24=-374/5046, 22-23=-374/5046, 21-22=-578/7526, 20-21=-510/7536, 19-20=-235/5898, 18-19=-104/1692, 17-18=-104/1692, 16-17=-104/1692, 15-16=-5068/1180, 14-15=-5068/1180, 13-14=-1923/454
WEBS 2-24=-1076/149, 5-20=-635/143, 8-16=-2503/489, 6-20=-291/1734, 6-19=-1704/264, 7-19=-633/4650, 7-16=-7431/942, 3-24=-5379/517, 3-22=-55/1080, 4-22=-2698/222, 4-21=-269/399, 5-21=-795/782, 9-14=-1517/280, 8-14=-806/3498, 9-13=-411/1857, 10-13=-620/85, 11-13=-280/70

NOTES
1) 2x4 DF No.2 bearing block 12" long at jt. 16 attached to front face with 2 rows of 10d (0.131"x3") nails spaced 3" o.c. 8 Total fasteners. Bearing is assumed to be DF No.2.
2) Unbalanced roof live loads have been considered for this design.
3) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 32-9-7, Corner (3) 32-9-7 to 36-9-7 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
4) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
5) Provide adequate drainage to prevent water ponding.
6) All plates are MT20 plates unless otherwise indicated.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 239 lb uplift at joint 24 and 522 lb uplift at joint 16.
10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB3	Roof Special	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:33 Page: 1
ID:pH4gsCy5g3lqgi_G_p0KENzgcpf-_dLAb037_HE66m?PW6X2BzQgQTsw8DzdYaupiNzUIfa



Scale = 1:65.6

Plate Offsets (X, Y): [2:0-3-8,0-2-8], [3:0-3-8,0-2-0], [7:0-3-8,0-2-0], [8:0-8-12,0-3-0], [10:0-4-0,0-4-12], [17:0-3-8,Edge], [19:0-3-8,0-2-0], [21:0-3-8,0-2-0], [22:0-3-8,0-2-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.89	Vert(LL)	-0.58	20-21	>525	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.89	Vert(CT)	-0.70	20-21	>440	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.88	Horz(CT)	0.09	14	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.09	20-21	>999	240		
BCDL	7.0										Weight: 200 lb	FT = 20%

LUMBER
TOP CHORD 2x6 DF No.2 *Except* T3:2x6 DF 1950F 1.5E or 2x6 DF SS
BOT CHORD 2x4 DF No.2 *Except* B2:2x4 DF 2100F 1.8E
WEBS 2x4 DF Stud *Except* W12,W17,W6:2x4 DF No.2, W14,W4:2x4 DF 2100F 1.8E

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (2-2-0 max.): 8-10.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 10-14

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 14=2283/(0-5-8 + bearing block), (req. 0-5-15), 24=1308/0-5-8, (min. 0-3-6)
Max Horiz 24=-49 (LC 8)
Max Uplift 14=-525 (LC 9), 24=-239 (LC 8)
Max Grav 14=5544 (LC 2), 24=3176 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-26=-5010/378, 3-26=-4998/379, 3-4=-7450/538, 4-5=-7435/426, 5-6=-7471/433, 6-7=-6360/293, 7-8=-2920/172, 8-9=-1355/5071, 9-10=-1355/5071, 10-11=-149/915
BOT CHORD 21-22=-316/4997, 20-21=-471/7438, 19-20=-260/6347, 18-19=-141/2911, 17-18=-141/2911, 16-17=-2888/1149, 15-16=-2902/1164, 14-15=-2902/1164, 13-14=-930/218
WEBS 5-20=-544/101, 10-13=-169/426, 9-14=-1296/375, 8-14=-3871/352, 6-19=-1410/253, 6-20=-274/1437, 7-17=-2447/380, 7-19=-588/3725, 8-17=-811/5742, 11-13=-1042/209, 10-14=-4365/1263, 2-24=-3095/322, 4-20=-722/708, 3-22=-1915/197, 2-22=-453/5316, 3-21=-168/2642, 4-21=-956/89

NOTES
1) 2x4 DF No.2 bearing block 12" long at jt. 14 attached to front face with 2 rows of 10d (0.131"x3") nails spaced 3" o.c. 8 Total fasteners. Bearing is assumed to be DF No.2.
2) Unbalanced roof live loads have been considered for this design.
3) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 32-9-7, Corner (3) 32-9-7 to 36-9-7 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
4) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
5) Provide adequate drainage to prevent water ponding.
6) All plates are MT20 plates unless otherwise indicated.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 239 lb uplift at joint 24 and 525 lb uplift at joint 14.
10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB4	Roof Special	1	1	Job Reference (optional)



Scale = 1:50.2

Plate Offsets (X, Y): [1:0-3-12,0-5-0], [2:0-3-8,0-2-8], [6:0-5-4,0-5-4], [8:0-2-12,0-2-0], [9:0-2-9,Edge], [12:0-3-8,0-2-0], [15:0-7-0,Edge], [18:0-1-12,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.93	Vert(LL)	-0.67	14-15	>432	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	1.00	Vert(CT)	-0.80	14-15	>363	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.88	Horz(CT)	0.07	11	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.14	14-15	>999	240		
BCDL	7.0										Weight: 151 lb	FT = 20%

LUMBER

TOP CHORD	2x6 DF No.2 *Except* T4:2x4 DF No.2
BOT CHORD	2x6 DF 1950F 1.5E or 2x6 DF SS
WEBS	2x4 DF Stud *Except* W1:2x8 DF 2250F 1.6E or 2x8 DF SS, W14,W4,W2:2x4 DF No.2
OTHERS	2x4 DF Stud

REACTIONS (lb/size) 11=1230/ Mechanical, 21=1132/0-2-12, (min. 0-2-1)
Max Horiz 21=-49 (LC 8)
Max Uplift 11=-217 (LC 9), 21=-139 (LC 13)
Max Grav 11=3001 (LC 2), 21=2750 (LC 2)

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (2-0-9 max.): 6-8.
BOT CHORD	Rigid ceiling directly applied.
WEBS	1 Row at midpt 8-11, 7-12

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	1-2=-3575/660, 2-3=-5857/1053, 3-4=-5859/1053, 4-5=-8259/1478, 5-22=-9683/1753, 6-22=-9689/1753, 6-7=-8434/1515, 7-8=-4917/880, 9-11=-546/101
BOT CHORD	18-19=-158/994, 17-18=-591/3568, 16-17=-1411/8252, 15-16=-1688/9665, 14-15=-1755/9908, 13-14=-1752/9909, 12-13=-1455/8434, 11-12=-795/4771
WEBS	3-17=-413/83, 8-12=-270/1663, 8-11=-5148/891, 7-12=-3890/704, 7-13=-131/787, 6-13=-1661/335, 4-17=-2940/499, 4-16=-135/882, 5-16=-1777/320, 5-15=-22/272, 6-15=-416/115, 2-17=-514/3002, 2-18=-2309/404, 1-18=-563/3340, 1-21=-3538/599

NOTES


1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-7-2 to 12-7-2, Exterior (2) 12-7-2 to 12-9-8, Corner (3) 12-9-8 to 24-9-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 30.0 psf on overhangs non-concurrent with other live loads.
5) Provide adequate drainage to prevent water ponding.
6) All plates are MT20 plates unless otherwise indicated.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Refer to girder(s) for truss to truss connections.
10) Bearing at joint(s) 21 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
11) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 21.
12) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 217 lb uplift at joint 11 and 139 lb uplift at joint 21.
13) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
14) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

Continued on page 2

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB4	Roof Special	1	1	Job Reference (optional)

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB5	Roof Special	1	1	Job Reference (optional)



Scale = 1:50.1

*** Design Problems ***
REVIEW REQUIRED

Allowable Top Chord Reaction Exceeded: 21

Plate Offsets (X, Y): [1:0-3-12,0-4-0], [2:0-1-12,0-1-8], [5:0-5-4,0-4-12], [9:0-5-4,0-4-0], [11:0-4-0,0-1-0], [12:0-3-12,0-2-8], [15:0-6-12,0-5-4], [17:0-3-4,0-5-0], [18:0-7-0,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.77	Vert(LL)	-0.65	13-14	>446	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	1.00	Vert(CT)	-0.77	13-14	>375	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.89	Horz(CT)	0.04	21	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.12	14	>999	240		
BCDL	7.0										Weight: 157 lb	FT = 20%

LUMBER

TOP CHORD	2x6 DF No.2 *Except* T3:2x6 DF 1950F 1.5E or 2x6 DF SS
BOT CHORD	2x6 DF 1950F 1.5E or 2x6 DF SS *Except* B1:2.0 RigidLam DF LVL 1-1/2 x 11-7/8
WEBS	2x4 DF Stud *Except* W1:2.0 RigidLam DF LVL 1-1/2 x 7-1/4, W13:2x6 DF No.2, W11,W4:2x4 DF No.2
OTHERS	2x4 DF No.2 *Except* BL2:2x8 DF 2250F 1.6E or 2x8 DF SS

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (2-3-0 max.): 5-7.
BOT CHORD	Rigid ceiling directly applied.
WEBS	1 Row at midpt 4-16

REACTIONS (lb/size) 20=1137/0-2-12, (min. 0-1-8), 21=1217/ Mechanical
Max Horiz 20=-23 (LC 10)
Max Uplift 20=-140 (LC 9), 21=-228 (LC 9)
Max Grav 20=2760 (LC 2), 21=2981 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	18-20=-127/766, 1-20=-127/766, 1-2=-3431/611, 2-3=-5917/993, 3-4=-5921/994, 4-5=-8694/1339, 5-6=-9331/1370, 6-7=-7156/1039, 7-22=-7209/1047, 8-22=-7213/1046, 8-9=-1933/281, 9-21=-309/2182
BOT CHORD	17-18=-313/1780, 16-17=-636/3605, 15-16=-1326/8631, 14-15=-1480/9964, 13-14=-1478/9967, 12-13=-1363/9331, 12-21=-685/4627
WEBS	3-16=-489/133, 7-12=-615/107, 4-16=-3212/387, 4-15=-51/740, 5-15=-1598/168, 6-12=-2446/372, 6-13=-37/339, 5-13=-708/127, 8-12=-415/3000, 8-21=-3264/492, 2-16=-454/3032, 2-17=-2273/416, 1-17=-408/2311, 1-20=-3546/614, 9-21=-3463/511

NOTES


1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-7-2 to 4-7-2, Exterior (2) 4-7-2 to 20-9-8, Corner (3) 20-9-8 to 24-9-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 30.0 psf on overhangs non-concurrent with other live loads.
5) Provide adequate drainage to prevent water ponding.
6) All plates are MT20 plates unless otherwise indicated.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.

Continued on page 2

9) Refer to girder(s) for truss to truss connections.
10) Bearing at joint(s) 20 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
11) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 20.
12) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 140 lb uplift at joint 20 and 228 lb uplift at joint 21.
13) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
14) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB6	Roof Special	1	1	Job Reference (optional)



Scale = 1:50.1

*** Design Problems ***
REVIEW REQUIRED

Allowable Top Chord Reaction Exceeded: 20

Plate Offsets (X, Y): [1:0-3-12,0-4-0], [2:0-2-0,0-2-4], [4:0-5-4,0-3-8], [7:0-3-8,0-2-8], [8:0-5-4,0-4-0], [10:0-4-12,0-4-4], [10:0-4-0,0-1-12], [12:0-2-4,0-2-0], [13:0-7-0,0-5-4], [16:0-3-4,0-5-0], [17:0-7-0,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.78	Vert(LL)	-0.65	13-14	>443	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.99	Vert(CT)	-0.78	13-14	>373	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.93	Horz(CT)	0.04	20	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.13	13-14	>999	240		
BCDL	7.0										Weight: 159 lb	FT = 20%

LUMBER

TOP CHORD	2x6 DF No.2 *Except* T3:2x6 DF 1950F 1.5E or 2x6 DF SS
BOT CHORD	2x6 DF 1950F 1.5E or 2x6 DF SS *Except* B1:2.0 RigidLam DF LVL 1-1/2 x 11-7/8
WEBS	2x4 DF Stud *Except* W1:2.0 RigidLam DF LVL 1-1/2 x 7-1/4, W12,W11:2x6 DF No.2, W9,W4:2x4 DF No.2
OTHERS	2x4 DF No.2 *Except* BL2:2x8 DF 2250F 1.6E or 2x8 DF SS

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (2-2-4 max.): 4-6.
BOT CHORD	Rigid ceiling directly applied.
WEBS	1 Row at midpt 4-15

REACTIONS (lb/size) 19=1137/0-2-12, (min. 0-1-8), 20=1217/ Mechanical
Max Horiz 19=-23 (LC 10)
Max Uplift 19=-140 (LC 9), 20=-228 (LC 9)
Max Grav 19=2760 (LC 2), 20=2981 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	17-19=-119/774, 1-19=-119/774, 1-2=-3401/578, 2-3=-6077/1025, 3-4=-6085/1024, 4-21=-9685/1666, 5-21=-9685/1666, 5-6=-8411/1427, 6-7=-8473/1436, 7-8=-1890/316, 8-20=-364/2233
BOT CHORD	16-17=-300/1782, 15-16=-597/3577, 14-15=-1584/9368, 13-14=-1581/9363, 12-13=-1661/9692, 11-12=-928/5548, 11-20=-934/5576
WEBS	6-12=-615/123, 7-12=-547/3188, 7-11=-460/107, 7-20=-4029/677, 5-12=-1448/275, 2-16=-2302/391, 1-16=-376/2269, 2-15=-543/3282, 3-15=-795/160, 4-15=-3698/607, 4-13=-146/563, 1-19=-3547/588, 8-20=-3446/569

NOTES


1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-7-2 to 12-7-2, Exterior (2) 12-7-2 to 12-9-8, Corner (3) 12-9-8 to 24-9-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 30.0 psf on overhangs non-concurrent with other live loads.
5) Provide adequate drainage to prevent water ponding.
6) All plates are MT20 plates unless otherwise indicated.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.

Continued on page 2

9) Refer to girder(s) for truss to truss connections.
10) Bearing at joint(s) 19 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
11) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 19.
12) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 140 lb uplift at joint 19 and 228 lb uplift at joint 20.
13) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
14) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB7	Roof Special	1	1	Job Reference (optional)



Scale = 1:50.1

*** Design Problems ***
REVIEW REQUIRED

Allowable Top Chord Reaction Exceeded: 21

Plate Offsets (X, Y): [1:0-3-12,0-4-0], [2:0-3-8,0-2-8], [8:0-3-8,0-1-8], [9:0-5-4,0-4-0], [11:0-4-12,0-4-4], [11:0-4-0,0-1-12], [13:0-3-8,0-2-8], [14:0-5-8,Edge], [17:0-3-4,0-5-0], [18:0-7-0,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.71	Vert(LL)	-0.60	14-15	>482	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.97	Vert(CT)	-0.72	14-15	>401	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.89	Horz(CT)	0.03	21	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.13	14-15	>999	240		
BCDL	7.0										Weight: 159 lb	FT = 20%

LUMBER

TOP CHORD 2x6 DF No.2 *Except* T3:2x6 DF 1950F 1.5E or 2x6 DF SS
BOT CHORD 2x6 DF 1950F 1.5E or 2x6 DF SS *Except* B1:2.0 RigidLam DF LVL 1-1/2 x 11-7/8
WEBS 2x4 DF Stud *Except* W1:2.0 RigidLam DF LVL 1-1/2 x 7-1/4, W14,W13:2x6 DF No.2, W11,W4:2x4 DF No.2
OTHERS 2x4 DF No.2 *Except* BL2:2x8 DF 2250F 1.6E or 2x8 DF SS

BRACING

TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (2-4-0 max.): 4-6.
BOT CHORD Rigid ceiling directly applied.

REACTIONS (lb/size) 20=1137/0-2-12, (min. 0-1-8), 21=1217/ Mechanical
Max Horiz 20=-23 (LC 10)
Max Uplift 20=-140 (LC 9), 21=-228 (LC 9)
Max Grav 20=2760 (LC 2), 21=2981 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 18-20=-128/763, 1-20=-128/763, 1-2=-3439/619, 2-3=-5876/1066, 3-4=-5878/1066, 4-5=-8373/1528, 5-22=-9128/1756, 6-22=-9128/1756, 6-7=-9135/1755, 7-8=-7750/1451, 8-9=-1831/330, 9-21=-411/2286
BOT CHORD 17-18=-317/1779, 16-17=-641/3612, 15-16=-1507/8321, 14-15=-1809/9489, 13-14=-1444/7740, 12-13=-912/4995, 12-21=-919/5029
WEBS 3-16=-400/81, 4-16=-2998/529, 4-15=-116/730, 6-14=-548/181, 5-15=-1458/333, 5-14=-407/72, 7-14=-348/1605, 7-13=-1467/298, 8-13=-603/3110, 8-12=-490/118, 8-21=-3598/663, 2-16=-540/2967, 2-17=-2262/420, 1-17=-409/2323, 1-20=-3546/624, 9-21=-3433/611

NOTES


1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-7-2 to 12-7-2, Exterior (2) 12-7-2 to 12-9-8, Corner (3) 12-9-8 to 24-9-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 30.0 psf on overhangs non-concurrent with other live loads.
5) Provide adequate drainage to prevent water ponding.
6) All plates are MT20 plates unless otherwise indicated.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.

Continued on page 2

9) Refer to girder(s) for truss to truss connections.
10) Bearing at joint(s) 20 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
11) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 20.
12) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 140 lb uplift at joint 20 and 228 lb uplift at joint 21.
13) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
14) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB8	Roof Special	1	1	Job Reference (optional)



Scale = 1:45.9

*** Design Problems ***
REVIEW REQUIRED

Allowable Top Chord Reaction Exceeded: 22

Plate Offsets (X, Y): [1:0-3-8,0-4-0], [4:0-5-12,0-4-8], [8:0-3-12,0-2-8], [9:0-5-4,0-4-0], [11:0-4-12,0-4-4], [11:0-4-0,0-1-12], [13:0-3-8,0-2-8], [16:0-3-8,0-2-0], [18:0-6-0,Edge], [19:0-7-0,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.84	Vert(LL)	-0.60	14-16	>487	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.88	Vert(CT)	-0.71	14-16	>409	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.94	Horz(CT)	0.03	22	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.14	14-16	>999	240		
BCDL	7.0										Weight: 161 lb	FT = 20%

LUMBER

TOP CHORD	2x6 DF No.2 *Except* T3:2x6 DF 1950F 1.5E or 2x6 DF SS
BOT CHORD	2x6 DF 1950F 1.5E or 2x6 DF SS *Except* B1:2.0 RigidLam DF LVL 1-1/2 x 11-7/8
WEBS	2x4 DF Stud *Except* W1:2.0 RigidLam DF LVL 1-1/2 x 7-1/4, W13,W12:2x6 DF No.2, W10:2x4 DF No.2
OTHERS	2x4 DF No.2 *Except* BL2:2x8 DF 2250F 1.6E or 2x8 DF SS

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (2-3-7 max.): 4-6.
BOT CHORD	Rigid ceiling directly applied.

REACTIONS (lb/size) 21=1137/0-2-12, (min. 0-1-8), 22=1217/ Mechanical
Max Horiz 21=-23 (LC 10)
Max Uplift 21=-140 (LC 9), 22=-228 (LC 9)
Max Grav 21=2760 (LC 2), 22=2981 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	19-21=-144/775, 1-21=-144/775, 1-2=-3465/681, 2-3=-3498/690, 3-4=-6813/1374, 4-5=-8785/1859, 5-6=-9314/1951, 6-7=-9371/1966, 7-8=-8550/1688, 8-9=-1920/357, 9-22=-411/2208
BOT CHORD	18-19=-338/1743, 17-18=-1158/5824, 16-17=-1359/6808, 15-16=-1845/8785, 14-15=-1845/8785, 13-14=-1680/8539, 12-13=-1091/5742, 12-22=-1096/5768
WEBS	4-17=-1835/378, 6-14=-619/200, 7-14=-302/907, 7-13=-1214/286, 8-13=-644/3059, 8-12=-460/120, 8-22=-4171/803, 5-14=-105/790, 5-16=-1160/296, 4-16=-553/2434, 2-18=-458/85, 1-18=-467/2411, 3-18=-3010/622, 3-17=-423/2183, 1-21=-3541/679, 9-22=-3452/634

NOTES

1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-7-2 to 12-7-2, Exterior (2) 12-7-2 to 12-9-8, Corner (3) 12-9-8 to 24-9-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 30.0 psf on overhangs non-concurrent with other live loads.
5) Provide adequate drainage to prevent water ponding.
6) All plates are MT20 plates unless otherwise indicated.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.


Continued on page 2

8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Refer to girder(s) for truss to truss connections.
10) Bearing at joint(s) 21 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
11) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 21.
12) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 140 lb uplift at joint 21 and 228 lb uplift at joint 22.
13) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
14) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB9	Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:35 Page: 1
ID:C1JPte_g8hEx3y1EBgoxnJzgd4P-w0Tx0i4NWvUpM49oeXZWGOV_zHX9c5qw?uNvnGzUlfY



Scale = 1:43.3

*** Design Problems ***
REVIEW REQUIRED

Allowable Top Chord Reaction Exceeded: 20

Plate Offsets (X, Y): [1:0-3-12,0-5-4], [2:0-3-8,0-2-8], [7:0-3-12,0-2-8], [8:0-5-4,0-4-0], [10:0-5-0,0-4-4], [10:0-4-0,0-0-12], [12:0-3-8,0-2-8], [15:0-5-0,0-2-8], [16:0-2-4,Edge], [17:0-7-0,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.95	Vert(LL)	-0.59	12-13	>490	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.90	Vert(CT)	-0.70	12-13	>412	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.98	Horz(CT)	0.03	20	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.13	12-13	>999	240		
BCDL	7.0										Weight: 157 lb	FT = 20%

LUMBER

TOP CHORD	2x6 DF No.2
BOT CHORD	2x6 DF 1950F 1.5E or 2x6 DF SS *Except* B1:2.0 RigidLam DF LVL 1-1/2 x 11-7/8
WEBS	2x4 DF Stud *Except* W1:2.0 RigidLam DF LVL 1-1/2 x 7-1/4, W14:2x6 DF No.2, W11,W4,W2:2x4 DF No.2
OTHERS	2x4 DF No.2 *Except* BL2:2x8 DF 2250F 1.6E or 2x8 DF SS

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (2-2-0 max.): 3-5.
BOT CHORD	Rigid ceiling directly applied.
WEBS	1 Row at midpt 7-10

REACTIONS (lb/size) 19=1137/0-2-12, (min. 0-1-8), 20=1217/ Mechanical
Max Horiz 19=-23 (LC 10)
Max Uplift 19=-197 (LC 9), 20=-235 (LC 9)
Max Grav 19=2760 (LC 2), 20=2981 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	17-19=-105/640, 1-19=-105/640, 1-2=-4051/745, 2-3=-6737/1250, 3-4=-6697/1244, 4-5=-9071/1767, 5-21=-9072/1765, 6-21=-9084/1764, 6-7=-9068/1809, 7-8=-2185/406, 8-20=-381/2084
BOT CHORD	16-17=-320/1771, 15-16=-764/4220, 14-15=-1529/8151, 13-14=-1529/8151, 12-13=-1800/9058, 11-12=-1168/6192, 11-20=-1173/6217
WEBS	3-15=-453/90, 5-13=-624/170, 4-15=-1869/391, 4-13=-275/1156, 6-13=-76/1068, 6-12=-1046/275, 7-12=-676/3064, 7-11=-483/124, 7-20=-4293/818, 2-15=-559/3003, 2-16=-2229/422, 1-16=-516/2856, 1-19=-3546/634, 8-20=-3499/640

NOTES

1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-7-2 to 12-7-2, Exterior (2) 12-7-2 to 12-9-8, Corner (3) 12-9-8 to 24-9-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 30.0 psf on overhangs non-concurrent with other live loads.
5) Provide adequate drainage to prevent water ponding.
6) All plates are MT20 plates unless otherwise indicated.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Refer to girder(s) for truss to truss connections.

Continued on page 2


Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB9	Hip	1	1	Job Reference (optional)

10) Bearing at joint(s) 19 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
11) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 19.
12) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 197 lb uplift at joint 19 and 235 lb uplift at joint 20.
13) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
14) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB10	Hip	2	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:35 Page: 1
ID:Jp7lAvLU4v0ggZK?xzKz?ezgd3x-w0Tx0i4NWvUpM49oeXZWGOV2PHXfc97w?uNvnGzUlfY



Scale = 1:45.7

*** Design Problems ***
REVIEW REQUIRED

Allowable Top Chord Reaction Exceeded: 20

Plate Offsets (X, Y): [1:0-3-12,0-5-4], [2:0-3-8,0-2-8], [8:0-5-4,0-4-0], [10:0-5-0,0-4-4], [10:0-4-0,0-0-12], [12:0-3-8,0-2-8], [13:0-6-12,0-5-0], [14:0-2-12,0-1-8], [15:0-3-8,0-2-8], [16:0-2-8,0-5-4], [17:0-7-0,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.67	Vert(LL)	-0.62	12-13	>469	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.94	Vert(CT)	-0.74	12-13	>394	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.71	Horz(CT)	0.03	20	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.13	12-13	>999	240		
BCDL	7.0										Weight: 159 lb	FT = 20%

LUMBER

TOP CHORD	2x6 DF No.2 *Except* T3:2x6 DF 1950F 1.5E or 2x6 DF SS
BOT CHORD	2x6 DF 1950F 1.5E or 2x6 DF SS *Except* B1:2.0 RigidLam DF LVL 1-1/2 x 11-7/8
WEBS	2x4 DF Stud *Except* W1:2.0 RigidLam DF LVL 1-1/2 x 7-1/4, W14:2x6 DF No.2, W11,W13,W2,W4:2x4 DF No.2
OTHERS	2x4 DF No.2 *Except* BL2:2x8 DF 2250F 1.6E or 2x8 DF SS

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (2-4-14 max.): 4-5.
BOT CHORD	Rigid ceiling directly applied.
WEBS	1 Row at midpt 7-10

REACTIONS (lb/size) 19=1137/0-2-12, (min. 0-1-8), 20=1217/ Mechanical
Max Horiz 19=-23 (LC 16)
Max Uplift 19=-197 (LC 9), 20=-235 (LC 9)
Max Grav 19=2760 (LC 2), 20=2981 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	17-19=-107/673, 1-19=-107/673, 1-2=-3811/666, 2-3=-6284/1102, 3-4=-7672/1359, 4-21=-7662/1358, 5-21=-7662/1358, 5-22=-8447/1507, 6-22=-8460/1506, 6-7=-9385/1708, 7-8=-2236/389, 8-20=-342/2039
BOT CHORD	16-17=-301/1742, 15-16=-686/3984, 14-15=-1086/6277, 13-14=-1478/8373, 12-13=-1698/9372, 11-12=-1194/6815, 11-20=-1198/6835
WEBS	4-14=-291/59, 5-14=-1447/284, 5-13=-139/482, 6-13=-986/580, 6-12=-829/211, 7-12=-532/2696, 7-11=-436/116, 7-20=-4829/851, 1-16=-460/2690, 3-14=-328/1798, 2-16=-2268/409, 2-15=-501/2866, 3-15=-1669/314, 1-19=-3545/605, 8-20=-3514/603

NOTES

1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-7-2 to 12-7-2, Exterior (2) 12-7-2 to 12-9-8, Corner (3) 12-9-8 to 24-9-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 30.0 psf on overhangs non-concurrent with other live loads.
5) Provide adequate drainage to prevent water ponding.
6) All plates are MT20 plates unless otherwise indicated.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

Continued on page 2


Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB10	Hip	2	1	Job Reference (optional)

8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Refer to girder(s) for truss to truss connections.
10) Bearing at joint(s) 19 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
11) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 19.
12) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 197 lb uplift at joint 19 and 235 lb uplift at joint 20.
13) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
14) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB11	Common	2	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:36 Page: 1
ID:4d8CPSeABaA7APkpvjHqWwzgd3Y-OC1JD15?HCcgzEk_BF5lpc2DfhtlLYG3EY7TjizUlfX



Scale = 1:43.3

*** Design Problems ***
REVIEW REQUIRED

Allowable Top Chord Reaction Exceeded: 20

Plate Offsets (X, Y): [1:0-3-12,0-5-4], [2:0-3-8,0-2-8], [7:0-4-4,0-3-8], [8:0-5-4,0-4-0], [10:0-4-12,0-4-4], [10:0-4-0,0-0-12], [12:0-3-8,0-2-8], [15:0-3-8,0-2-8], [16:0-2-4,0-5-4], [17:0-7-0,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.70	Vert(LL)	-0.63	12-14	>457	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.95	Vert(CT)	-0.76	12-14	>384	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.97	Horz(CT)	0.03	20	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.11	12-14	>999	240		
BCDL	7.0										Weight: 156 lb	FT = 20%

LUMBER

TOP CHORD	2x6 DF 1950F 1.5E or 2x6 DF SS *Except* T1:2x6 DF No.2
BOT CHORD	2x6 DF 1950F 1.5E or 2x6 DF SS *Except* B1:2.0 RigidLam DF LVL 1-1/2 x 11-7/8
WEBS	2x4 DF Stud *Except* W1:2.0 RigidLam DF LVL 1-1/2 x 7-1/4, W12:2x6 DF No.2, W2,W4,W11:2x4 DF No.2
OTHERS	2x4 DF No.2 *Except* BL2:2x8 DF 2250F 1.6E or 2x8 DF SS

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.
WEBS	1 Row at midpt 5-14, 7-10

REACTIONS (lb/size) 19=1137/0-2-12, (min. 0-1-8), 20=1217/ Mechanical
Max Horiz 19=-22 (LC 10)
Max Uplift 19=-117 (LC 12), 20=-214 (LC 9)
Max Grav 19=2760 (LC 2), 20=2981 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	17-19=-87/662, 1-19=-87/662, 1-2=-3886/561, 2-21=-6467/915, 3-21=-6461/916, 3-4=-8135/1138, 4-5=-8145/1137, 5-6=-9419/1306, 6-7=-9431/1306, 7-22=-2260/329, 8-22=-2273/328, 8-20=-260/2020
BOT CHORD	16-17=-255/1747, 15-16=-577/4059, 14-15=-902/6459, 13-14=-1296/9417, 12-13=-1296/9417, 11-12=-971/7017, 11-20=-975/7037
WEBS	4-14=-645/117, 3-14=-270/2209, 2-16=-2263/341, 1-16=-383/2754, 2-15=-394/2918, 3-15=-1656/239, 5-14=-2063/488, 7-20=-4983/678, 5-12=-744/144, 7-12=-342/2522, 7-11=-423/99, 1-19=-3545/508, 8-20=-3523/504

NOTES

1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-7-2 to 4-7-2, Exterior (2) 4-7-2 to 20-9-8, Corner (3) 20-9-8 to 24-9-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 30.0 psf on overhangs non-concurrent with other live loads.
5) Provide adequate drainage to prevent water ponding.
6) All plates are MT20 plates unless otherwise indicated.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Refer to girder(s) for truss to truss connections.

Continued on page 2

10) Bearing at joint(s) 19 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
11) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 19.
12) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 117 lb uplift at joint 19 and 214 lb uplift at joint 20.
13) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB12	Hip	1	1	Job Reference (optional)




Plate Offsets (X, Y): [1:0-2-0,0-4-0], [3:0-3-0,0-3-4], [9:0-5-4,0-4-0], [18:0-3-8,Edge], [21:0-4-0,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.67	Vert(LL)	-0.17	12-13	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.73	Vert(CT)	-0.20	12-13	>999	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.75	Horz(CT)	0.03	23	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.04	12-13	>999	240		
BCDL	7.0										Weight: 144 lb	FT = 20%

LUMBER

TOP CHORD	2x6 DF No.2
BOT CHORD	2x4 DF No.2 *Except* B1:2x10 DF SS
WEBS	2x4 DF Stud *Except* W1:2x8 DF 2250F 1.6E or 2x8 DF SS, W15:2x6 DF No.2, W9:2x4 DF No.2
OTHERS	2x4 DF No.2 *Except* BL2:2x8 DF 2250F 1.6E or 2x8 DF SS

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 3-6.
BOT CHORD	Rigid ceiling directly applied.
WEBS	1 Row at midpt 7-14

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 16=1663/0-5-8, (min. 0-4-5), 22=-51/0-2-12, (min. 0-1-8), 23=741/ Mechanical
Max Horiz 22=-29 (LC 10)
Max Uplift 16=-288 (LC 9), 22=-125 (LC 2), 23=-153 (LC 9)
Max Grav 16=4041 (LC 2), 22=438 (LC 31), 23=1825 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	1-2=-327/547, 2-3=-390/1916, 3-4=-546/2750, 4-5=-546/2750, 5-6=-1029/245, 6-24=-968/227, 7-24=-981/227, 7-8=-3286/716, 8-9=-1003/185, 11-23=-180/1020, 9-23=-180/1020
BOT CHORD	17-18=-573/328, 16-17=-1984/434, 15-16=-1393/302, 14-15=-1393/302, 13-14=-694/3275, 12-13=-557/3022, 11-12=-557/3022
WEBS	6-14=-796/205, 7-14=-2502/538, 8-13=-149/273, 8-11=-2247/430, 5-14=-645/3027, 2-18=-95/429, 1-18=-591/147, 2-17=-1684/333, 3-17=-186/1003, 3-16=-1497/281, 4-16=-606/123, 5-16=-2451/498, 1-22=-569/155, 9-23=-2170/388

NOTES

1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-7-2 to 12-7-2, Exterior (2) 12-7-2 to 12-9-8, Corner (3) 12-9-8 to 24-9-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 30.0 psf on overhangs non-concurrent with other live loads.
5) Provide adequate drainage to prevent water ponding.
6) All plates are MT20 plates unless otherwise indicated.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Refer to girder(s) for truss to truss connections.
10) Bearing at joint(s) 22 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
11) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 22.
12) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 288 lb uplift at joint 16, 125 lb uplift at joint 22 and 153 lb uplift at joint 23.
13) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
14) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.


Continued on page 2


Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB12	Hip	1	1	Job Reference (optional)

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB13	Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:36 Page: 1
ID:_0XHfhwfD9W5uirA6_AhpGzgd1u-OC1JD15?HCcgzEk_BF5lpc29vhwfLZm3EY7TJizUlfX





Scale = 1:62.8

Plate Offsets (X, Y): [2:0-3-8,0-2-0], [5:0-3-0,0-3-12], [11:0-5-4,0-4-0], [22:0-3-8,0-2-0], [26:0-4-0,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.94	Vert(LL)	-0.18	15-16	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.76	Vert(CT)	-0.21	15-16	>970	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.94	Horz(CT)	0.06	27	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.03	15-16	>999	240		
BCDL	7.0										Weight: 192 lb	FT = 20%

LUMBER
TOP CHORD 2x6 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W17:2x6 DF No.2
OTHERS 2x8 DF 2250F 1.6E or 2x8 DF SS

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (2-2-0 max.): 5-8.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 5-19, 8-18

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 19=1932/0-5-8, (min. 0-5-0), 24=752/0-5-8, (min. 0-2-2), 27=707/ Mechanical
Max Horiz 24=-38 (LC 10)
Max Uplift 19=-250 (LC 9), 24=-180 (LC 8), 27=-156 (LC 9)
Max Grav 19=4693 (LC 2), 24=1988 (LC 31), 27=1868 (LC 32)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-28=-2070/164, 3-28=-2060/165, 3-4=-2226/573, 4-5=-441/1238, 5-6=-386/3466, 6-7=-386/3466, 7-8=-203/1899, 8-9=-2458/212, 9-10=-3610/372, 10-29=-959/110, 11-29=-972/109, 13-27=-109/1128, 11-27=-109/1128
BOT CHORD 21-22=-151/2060, 20-21=-571/2217, 19-20=-1262/364, 18-19=-1899/227, 17-18=-185/2401, 16-17=-185/2401, 15-16=-353/3602, 14-15=-294/2857, 13-14=-294/2857
WEBS 5-20=-85/1026, 8-16=-54/736, 2-24=-1857/237, 9-16=-1539/183, 9-15=-284/68, 10-15=-64/821, 10-13=-2176/230, 4-20=-2318/257, 3-22=-871/122, 2-22=-236/2293, 3-21=-463/172, 4-21=-10/250, 6-19=-542/71, 7-19=-2789/326, 5-19=-3319/374, 7-18=-149/1527, 8-18=-3873/449, 11-27=-2198/239


NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 30-11-4, Corner (3) 30-11-4 to 34-11-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 30.0 psf on overhangs non-concurrent with other live loads.
5) Provide adequate drainage to prevent water ponding.
6) All plates are MT20 plates unless otherwise indicated.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Refer to girder(s) for truss to truss connections.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 180 lb uplift at joint 24, 250 lb uplift at joint 19 and 156 lb uplift at joint 27.
11) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
12) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB14	Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:37 Page: 1
ID:mKulcX4YeQ5Jczo5RaLnp_zcYYv-sPbhRN6d2WkXbOJBlyc_LpaOy5GC4?7DTCs0r8zUlfW





Scale = 1:62.8

Plate Offsets (X, Y): [2:0-2-8,0-2-0], [5:0-1-12,0-2-0], [6:0-3-8,0-2-0], [9:0-5-4,0-4-0], [11:0-4-0,0-3-0], [13:0-3-8,0-2-0], [14:0-1-12,0-2-0], [16:0-3-8,0-2-0], [18:0-2-0,0-1-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.66	Vert(LL)	-0.17	12-13	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.74	Vert(CT)	-0.21	12-13	>999	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	1.00	Horz(CT)	0.04	22	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.03	12-13	>999	240		
BCDL	7.0										Weight: 190 lb	FT = 20%

LUMBER

TOP CHORD	2x6 DF No.2 *Except* T2:2x6 DF 1950F 1.5E or 2x6 DF SS
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud *Except* W14,W13:2x6 DF No.2, W11,W10:2x4 DF No.2
OTHERS	2x8 DF 2250F 1.6E or 2x8 DF SS

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (4-4-14 max.): 4-7.
BOT CHORD	Rigid ceiling directly applied.
WEBS	2 Rows at 1/3 pts 4-16

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 16=1884/0-5-8, (min. 0-4-14), 20=778/0-5-8, (min. 0-2-2), 22=729/ Mechanical
Max Horiz 20=-36 (LC 10)
Max Uplift 16=-269 (LC 8), 20=-180 (LC 8), 22=-157 (LC 9)
Max Grav 16=4576 (LC 2), 20=1990 (LC 31), 22=1878 (LC 32)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	2-23=-2382/213, 3-23=-2369/214, 3-4=-1605/179, 4-5=-323/2851, 5-24=-1021/102, 6-24=-1021/102, 6-7=-3276/340, 7-8=-3350/373, 8-25=-1232/144, 9-25=-1244/144, 9-22=-103/1081
BOT CHORD	17-18=-211/2369, 16-17=-189/1566, 15-16=-2851/332, 14-15=-2851/332, 13-14=-95/1021, 12-13=-343/3349, 12-22=-368/3354
WEBS	4-17=-6/428, 7-13=-1033/155, 7-12=-385/187, 2-20=-1919/256, 3-17=-1099/114, 3-18=-751/120, 2-18=-272/2470, 6-13=-307/2677, 5-16=-3031/388, 4-16=-4137/464, 5-14=-436/3729, 6-14=-1771/232, 8-12=-296/134, 8-22=-2232/239, 9-22=-2196/246


NOTES

1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 30-11-4, Corner (3) 30-11-4 to 34-11-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 30.0 psf on overhangs non-concurrent with other live loads.
5) Provide adequate drainage to prevent water ponding.
6) All plates are MT20 plates unless otherwise indicated.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Refer to girder(s) for truss to truss connections.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 180 lb uplift at joint 20, 269 lb uplift at joint 16 and 157 lb uplift at joint 22.
11) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
12) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB15	Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:37 Page: 1
ID:uemx1Psha59DHphOB0UnPTzcYXv-sPbhRN6d2WkXbOJBlyc_LpaN25FH4?ODTCs0r8zUlfW



Scale = 1:62.8

Plate Offsets (X, Y): [2:0-3-8,0-2-0], [5:0-3-8,0-1-8], [8:0-3-8,0-2-8], [11:0-5-4,0-4-0], [13:0-4-0,0-3-0], [21:0-3-8,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.72	Vert(LL)	-0.19	15-16	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.80	Vert(CT)	-0.23	15-16	>895	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.98	Horz(CT)	0.06	25	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.03	15-16	>999	240		
BCDL	7.0										Weight: 191 lb	FT = 20%

LUMBER
TOP CHORD 2x6 DF No.2 *Except* T2:2x6 DF 1950F 1.5E or 2x6 DF SS
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W14,W13:2x6 DF No.2, W10:2x4 DF No.2
OTHERS 2x8 DF 2250F 1.6E or 2x8 DF SS

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (4-8-0 max.): 4-9.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 8-18, 5-18

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 18=1901/0-5-8, (min. 0-4-15), 23=769/0-5-8, (min. 0-2-1), 25=722/ Mechanical
Max Horiz 23=-36 (LC 10)
Max Uplift 18=-293 (LC 9), 23=-176 (LC 8), 25=-154 (LC 9)
Max Grav 18=4618 (LC 2), 23=1933 (LC 31), 25=1841 (LC 32)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-26=-1944/172, 3-26=-1933/173, 3-4=-1979/181, 4-5=-344/345, 5-6=-357/3129, 6-27=-357/3129, 7-27=-357/3129, 7-8=-357/3129, 8-9=-1922/182, 9-10=-3498/381, 10-28=-1114/130, 11-28=-1126/129, 11-25=-116/1138
BOT CHORD 20-21=-171/1933, 19-20=-181/1966, 18-19=-345/344, 17-18=-175/1922, 16-17=-175/1922, 15-16=-380/3511, 14-15=-312/2784, 14-25=-316/2807
WEBS 9-15=-296/72, 2-23=-1794/240, 10-15=-70/818, 10-14=-297/57, 10-25=-1838/204, 3-21=-835/127, 2-21=-246/2170, 6-18=-1209/172, 8-16=-41/694, 8-18=-4944/576, 9-16=-1878/219, 5-18=-3428/386, 5-19=-74/914, 4-19=-1977/217, 11-25=-2125/239

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 30-11-4, Corner (3) 30-11-4 to 34-11-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 30.0 psf on overhangs non-concurrent with other live loads.
5) Provide adequate drainage to prevent water ponding.
6) All plates are MT20 plates unless otherwise indicated.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Refer to girder(s) for truss to truss connections.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 176 lb uplift at joint 23, 293 lb uplift at joint 18 and 154 lb uplift at joint 25.
11) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
12) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB16	Hip Girder	1	2	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:37 Page: 1
ID:4ZVN2ccaz8zQjKQJp1cKvYzcYWx-sPbhRN6d2WkXbOJBlyc_LpaOD5DC42pDTCs0r8zUlfW



Scale = 1:62.8

*** Design Problems ***
REVIEW REQUIRED

Allowable Top Chord Reaction Exceeded: 29

Plate Offsets (X, Y): [7:0-3-8,0-2-8], [8:0-3-8,0-2-8], [13:0-5-4,0-4-0], [15:0-4-0,0-4-8], [15:0-3-4,0-3-0], [18:0-5-0,0-2-12], [20:0-3-8,0-4-8], [25:0-3-4,0-4-8], [26:0-3-8,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.65	Vert(LL)	-0.17	17-18	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.93	Vert(CT)	-0.20	17-18	>999	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	NO	WB	0.82	Horz(CT)	0.02	29	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MSH		Wind(LL)	0.03	17-18	>999	240		
BCDL	7.0										Weight: 440 lb	FT = 20%

LUMBER

TOP CHORD	2x6 DF No.2 *Except* T2:2x6 DF 1950F 1.5E or 2x6 DF SS
BOT CHORD	2x6 DF No.2
WEBS	2x4 DF Stud *Except* W16:2x8 DF 2250F 1.6E or 2x8 DF SS, W11:2x4 DF 2100F 1.8E, W12:2x4 DF No.2
OTHERS	2x8 DF 2250F 1.6E or 2x8 DF SS

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (5-11-11 max.): 4-11.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 22-23 5-1-14 oc bracing: 19-22.

REACTIONS (lb/size) 22=4297/(0-5-8 + bearing block), (req. 0-5-11), 27=1200/0-5-8, (min. 0-1-9), 29=1672/ Mechanical
Max Horiz 27=-36 (LC 8)
Max Uplift 22=-721 (LC 7), 27=-261 (LC 6), 29=-351 (LC 7)
Max Grav 22=10682 (LC 2), 27=2987 (LC 29), 29=4169 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=-3354/267, 3-4=-5598/437, 4-5=-3844/322, 5-6=-121/978, 6-7=-496/7171, 7-30=-1696/157, 8-30=-1696/157, 8-9=-6948/466, 9-10=-6948/466, 10-11=-6948/466, 11-12=-7365/518, 12-13=-2836/228, 13-29=-265/3409

BOT CHORD 25-26=-265/3344, 25-31=-432/5575, 24-31=-432/5575, 24-32=-320/3844, 23-32=-320/3844, 23-33=-978/124, 22-33=-978/124, 21-22=-7171/501, 21-34=-7171/501, 34-35=-7171/501, 20-35=-7171/501, 19-20=-7171/501, 19-36=-154/1696, 18-36=-154/1696, 18-37=-517/7395, 17-37=-517/7395, 17-38=-388/5162, 16-38=-388/5162, 16-39=-390/5192, 29-39=-397/5272

WEBS 4-25=-60/454, 11-17=-421/98, 2-27=-2644/233, 3-25=-224/2603, 3-26=-1881/166, 2-26=-285/3711, 12-17=-163/2622, 12-29=-2908/207, 7-22=-5202/377, 6-22=-7096/498, 5-24=-123/1997, 4-24=-1984/169, 5-23=-5520/402, 6-23=-195/3080, 8-19=-2912/233, 7-19=-648/9671, 8-18=-400/5729, 10-18=-895/96, 11-18=-487/67, 13-29=-4891/409

NOTES

1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc, 2x6 - 2 rows staggered at 0-9-0 oc, 2x8 - 2 rows staggered at 0-9-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-4-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) 2x6 DF No.2 bearing block 12" long at jt. 22 attached to each face with 3 rows of 10d (0.131"x3") nails spaced 3" o.c. 12 Total fasteners per block. Bearing is assumed to be DF No.2.
4) Unbalanced roof live loads have been considered for this design.


Continued on page 2


5) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
6) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
7) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 30.0 psf on overhangs non-concurrent with other live loads.
8) Provide adequate drainage to prevent water ponding.
9) All plates are MT20 plates unless otherwise indicated.
10) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
11) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
12) Refer to girder(s) for truss to truss connections.
13) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 261 lb uplift at joint 27, 721 lb uplift at joint 22 and 351 lb uplift at joint 29.
14) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
15) Use Simpson Strong-Tie THJA26 (THJA26 on 2 ply, Left Hand Hip) or equivalent at 8-0-6 from the left end to connect truss(es) FJ4 (1 ply 2x4 DF), FJ8 (1 ply 2x4 DF) to front face of bottom chord.
16) Use Simpson Strong-Tie LUS24 (4-10d Girder, 2-10d Truss) or equivalent spaced at 2-0-0 oc max. starting at 10-0-12 from the left end to 30-10-7 to connect truss(es) FJ4 (1 ply 2x4 DF), FJ3 (1 ply 2x4 DF) to front face of bottom chord.
17) Use Simpson Strong-Tie LUS26 (4-10d Girder, 3-10d Truss) or equivalent spaced at 0-6-0 oc max. starting at 32-10-7 from the left end to 33-4-7 to connect truss(es) FJ2 (1 ply 2x4 DF), FJ1 (1 ply 2x4 DF) to front face of bottom chord.
18) Fill all nail holes where hanger is in contact with lumber.

LOAD CASE(S) Standard

1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
   Uniform Loads (lb/ft)
   Vert: 1-13=-84, 13-14=-84, 15-28=-14
   Concentrated Loads (lb)
   Vert: 25=-645 (F), 17=-224 (F), 23=-224 (F), 19=-224 (F), 18=-224 (F), 15=-224 (F), 31=-224 (F), 32=-224 (F), 33=-224 (F), 34=-224 (F), 35=-224 (F), 36=-224 (F), 37=-224 (F), 38=-224 (F), 39=-224 (F)

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB17	Monopitch	11	1	Job Reference (optional)





Scale = 1:36.4

0-5-8 0-3-8

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	1.00	Vert(LL)	-0.09	5-6	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.36	Vert(CT)	-0.15	5-6	>631	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.48	Horz(CT)	0.02	15	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.00	5	>999	240		
BCDL	7.0										Weight: 50 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud
OTHERS 2x6 DF No.2 *Except* BL2:2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 10=598/0-4-0, (min. 0-1-8), 15=329/0-2-12, (min. 0-1-8)
Max Horiz 10=54 (LC 9)
Max Uplift 10=-140 (LC 8), 15=-58 (LC 12)
Max Grav 10=1466 (LC 2), 15=799 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 5-15=-94/445, 4-15=-94/445
BOT CHORD 5-6=-238/977
WEBS 3-5=-843/258, 3-6=-1052/298, 2-10=-142/409, 6-10=-117/519, 2-10=-117/519, 4-15=-956/241

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Bearing at joint(s) 10, 15 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
8) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 15.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 140 lb uplift at joint 10 and 58 lb uplift at joint 15.
10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC1	Common	20	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:38 Page: 1
ID:93eciZK2KcgmHsyUkrZyCxzgdNK-Kb93ej7FpqsODYuNJg7Du17UVUYrpT4MhscaOazUlfV



Scale = 1:50.5

Plate Offsets (X, Y): [3:0-2-0,0-3-4], [4:0-3-7,0-3-8], [6:0-3-7,0-3-8], [7:0-2-0,0-3-4], [11:0-6-12,0-4-8], [12:0-3-8,0-3-8], [17:0-3-8,0-3-8], [18:0-3-4,0-4-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	1.00	Vert(LL)	-0.76	15	>406	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.97	Vert(CT)	-0.91	15	>341	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.89	Horz(CT)	0.16	11	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.12	15	>999	240		
BCDL	7.0										Weight: 200 lb	FT = 20%

LUMBER
TOP CHORD 2x6 DF No.2
BOT CHORD 2x8 DF 2250F 1.6E or 2x8 DF SS
WEBS 2x4 DF Stud *Except* W4:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 7-11, 6-12, 3-18, 4-17

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 11=1456/0-5-8, (min. 0-3-12), 18=1456/0-5-8, (min. 0-3-12)
Max Horiz 18=43 (LC 9)
Max Uplift 11=-238 (LC 9), 18=-238 (LC 8)
Max Grav 11=3535 (LC 2), 18=3535 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 9-10=-383/29, 5-6=-9935/1222, 6-7=-6449/792, 7-20=-644/80, 8-20=-657/79, 8-9=-528/57, 1-2=-528/27, 2-21=-657/41, 3-21=-645/42, 3-4=-6448/766, 4-5=-9934/1210, 1-19=-383/26
BOT CHORD 17-18=-704/6433, 16-17=-1143/9922, 15-16=-1255/10775, 14-15=-1255/10775, 13-14=-1255/10775, 12-13=-1155/9923, 11-12=-729/6433
WEBS 2-18=-1120/180, 1-18=-48/699, 9-11=-43/699, 8-11=-1120/174, 7-11=-6160/753, 6-13=-220/708, 5-13=-1689/619, 6-12=-3750/458, 7-12=-103/1144, 5-16=-1690/618, 3-17=-108/1145, 3-18=-6160/766, 4-17=-3750/472, 4-16=-220/708


NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 25-10-4, Corner (3) 25-10-4 to 29-10-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) All plates are MT20 plates unless otherwise indicated.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 238 lb uplift at joint 18 and 238 lb uplift at joint 11.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC2	Common	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:39 Page: 1
ID:4eiRlt?2vCOQriqzIlrUy8zcZHV-Kb93ej7FpqsODYuNJg7Du17ZQUYlpS7MhscaOazUlfV





Scale = 1:49.9

Plate Offsets (X, Y): [3:0-3-7,0-2-1], [11:0-3-8,0-2-0], [16:0-3-0,0-2-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.68	Vert(LL)	-0.85	12	>363	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.98	Vert(CT)	-1.01	12	>305	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.95	Horz(CT)	0.20	9	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.15	12	>999	240		
BCDL	7.0										Weight: 169 lb	FT = 20%

LUMBER
TOP CHORD 2x6 DF 1950F 1.5E or 2x6 DF SS
BOT CHORD 2x6 DF 1950F 1.5E or 2x6 DF SS
WEBS 2x4 DF Stud *Except* W13,W12,W11,W4:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 7-9, 3-16, 4-15

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 9=1247/0-5-8, (min. 0-3-4), 16=1468/0-5-8, (min. 0-3-13)
Max Horiz 16=48 (LC 11)
Max Uplift 9=-170 (LC 9), 16=-242 (LC 8)
Max Grav 9=3029 (LC 2), 16=3565 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-6001/818, 4-18=-10342/1446, 5-18=-10334/1447, 5-19=-10328/1447, 6-19=-10342/1447, 6-7=-9720/1382, 7-8=-349/78, 8-9=-526/92
BOT CHORD 15-16=-754/5989, 14-15=-1262/9523, 13-14=-1262/9523, 12-13=-1262/9523, 11-12=-1317/9707, 10-11=-866/6381, 9-10=-866/6381
WEBS 1-16=-13/309, 2-16=-1060/184, 5-12=-525/98, 7-9=-6489/910, 6-12=-754/1543, 6-11=-1216/199, 7-11=-483/3564, 3-16=-6231/893, 3-15=-158/1357, 4-15=-3811/548, 4-12=-637/1656


NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 12-1-12, Exterior (2) 12-1-12 to 15-10-4, Corner (3) 15-10-4 to 27-10-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) All plates are MT20 plates unless otherwise indicated.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 170 lb uplift at joint 9 and 242 lb uplift at joint 16.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC3	Common	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:39 Page: 1
ID:1e?laRFHQ9VfKhmyq8it93zcZFt-onjRs37tZ7_FqhTZtNeSQEghMuwcYwWWwWL7w1zUlfU





Scale = 1:43.5

Plate Offsets (X, Y): [2:0-3-8,0-2-8], [3:0-3-8,0-2-0], [6:0-3-7,0-2-0], [11:0-3-8,0-2-0], [13:0-3-8,0-2-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.86	Vert(LL)	-0.48	10-11	>537	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.81	Vert(CT)	-0.57	10-11	>450	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.87	Horz(CT)	0.12	8	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.09	10-11	>999	240		
BCDL	7.0										Weight: 111 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF 2100F 1.8E *Except* T2:2x4 DF No.2
BOT CHORD 2x4 DF 2100F 1.8E
WEBS 2x4 DF Stud *Except* W4:2x4 DF 2100F 1.8E, W11:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 6-8

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 8=1034/ Mechanical, 14=1259/0-5-8, (min. 0-3-4)
Max Horiz 14=58 (LC 9)
Max Uplift 8=-125 (LC 9), 14=-230 (LC 8)
Max Grav 8=2512 (LC 2), 14=3057 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-4602/717, 3-4=-6685/1079, 4-5=-6432/1053, 5-6=-4638/779, 7-8=-466/93
BOT CHORD 12-13=-653/4591, 11-12=-653/4591, 10-11=-1010/6674, 9-10=-979/6407, 8-9=-705/4626
WEBS 2-14=-2893/510, 5-10=-242/512, 4-10=-1051/731, 3-13=-1887/351, 2-13=-832/5021, 3-11=-389/2270, 4-11=-849/180, 6-9=-97/928, 5-9=-2024/305, 6-8=-4871/776

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) All plates are MT20 plates unless otherwise indicated.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Refer to girder(s) for truss to truss connections.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 125 lb uplift at joint 8 and 230 lb uplift at joint 14.
10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard


Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC4	Common	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:39 Page: 1
ID:V64YMbTZAhm6US9Quw15uszcZFb-onjRs37tZ7_FqhTZtNeSQEgkAuukYxmWwWL7w1zUlfU



22-1-14 22-1-14

2-2-12



Scale = 1:36.3

0-2-12

Plate Offsets (X, Y): [2:0-3-8,0-2-0], [5:0-5-8,0-2-8], [9:0-3-8,0-1-8], [10:0-5-12,0-2-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.68	Vert(LL)	-0.21	9-10	>928	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.93	Vert(CT)	-0.25	9-10	>781	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.79	Horz(CT)	0.06	7	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.05	9-10	>999	240		
BCDL	7.0										Weight: 90 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF 2100F 1.8E *Except* T2:2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W4:2x4 DF No.2

REACTIONS (lb/size) 7=795/ Mechanical, 12=1025/0-5-8, (min. 0-2-10)
Max Horiz 12=63 (LC 9)
Max Uplift 7=-86 (LC 12), 12=-210 (LC 8)
Max Grav 7=1931 (LC 2), 12=2489 (LC 2)

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 5-7

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-3275/585, 3-4=-3273/590, 4-5=-4231/795, 6-7=-430/90
BOT CHORD 9-10=-723/4219, 8-9=-482/2855, 7-8=-484/2852
WEBS 5-7=-3122/567, 2-12=-2334/480, 3-10=-876/198, 4-10=-1064/222, 2-10=-691/3594, 4-9=-641/129, 5-9=-264/1735

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 86 lb uplift at joint 7 and 210 lb uplift at joint 12.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC5	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:39 Page: 1
ID:9Qp5tic5LNHPwI3jbSFvNOzcZFP-onjRs37tZ7_FqhTZtNeSQEgIfu?_YwzWwWL7w1zUlfU



22-1-14 22-1-14



Scale = 1:34.8

0-2-12

Plate Offsets (X, Y): [2:0-3-8,0-2-0], [5:0-0-8,0-1-8], [8:0-3-8,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.59	Vert(LL)	-0.08	7-8	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.46	Vert(CT)	-0.10	7-8	>999	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.85	Horz(CT)	0.02	6	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.02	7-8	>999	240		
BCDL	7.0										Weight: 68 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 6=553/ Mechanical, 9=794/0-5-8, (min. 0-2-1)
Max Horiz 9=66 (LC 9)
Max Uplift 6=-93 (LC 12), 9=-178 (LC 8)
Max Grav 6=1343 (LC 2), 9=1928 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1900/393, 3-4=-1932/429, 5-6=-399/104
BOT CHORD 7-8=-335/1891, 6-7=-366/1922
WEBS 2-9=-1743/426, 4-6=-2030/423, 3-8=-872/239, 2-8=-505/2198

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 93 lb uplift at joint 6 and 178 lb uplift at joint 9.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC6	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:39 Page: 1
ID:Gw5?b8nFINwZ_IZDsg_yP8zcZFC-onjRs37tZ7_FqhTZtNeSQEgnku3UY2?WwWL7w1zUlfU



22-1-14 22-1-14

2-2-12

Scale = 1:30

0-2-12

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.45	Vert(LL)	-0.04	5-6	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.24	Vert(CT)	-0.07	5-6	>999	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.33	Horz(CT)	0.01	5	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.00	5-6	>999	240		
BCDL	7.0										Weight: 44 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 5=304/ Mechanical, 6=570/0-5-8, (min. 0-1-8)
Max Horiz 6=62 (LC 9)
Max Uplift 5=-41 (LC 8), 6=-145 (LC 8)
Max Grav 5=737 (LC 2), 6=1384 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 4-5=-344/106
BOT CHORD 5-6=-145/725
WEBS 2-6=-687/214, 3-5=-736/192, 3-6=-1002/346

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 145 lb uplift at joint 6 and 41 lb uplift at joint 5.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC7	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:40 Page: 1
ID:wVLzh37RSHaSzlHo2G?m4FzcZEl-HzGq3P8WKR66Sr2lQ59hzSC?IISoHYlf9A5gSTzUlfT



Scale = 1:29.9

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.27	Vert(LL)	0.00	4-5	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.04	Vert(CT)	0.00	4-5	>999	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.17	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.00	4-5	>999	240		
BCDL	7.0										Weight: 24 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=-8/ Mechanical, 5=408/0-5-8, (min. 0-1-8)
Max Horiz 5=59 (LC 9)
Max Uplift 4=-35 (LC 24), 5=-146 (LC 8)
Max Grav 4=42 (LC 8), 5=992 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 1-5=-275/123, 2-5=-769/339, 2-4=-184/282

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 146 lb uplift at joint 5 and 35 lb uplift at joint 4.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC8	Common	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:40 Page: 1
ID:lwEfWwPs2LTBDHXDvbv9W6zcZEO-HzGq3P8WKR66Sr2lQ59hzSCqEIEcHN7f9A5gSTzUlfT



22-1-14 22-1-14



Scale = 1:46.5

Plate Offsets (X, Y): [2:0-3-0,0-1-8], [3:0-3-8,0-2-8], [6:0-3-8,0-2-0], [7:0-3-4,0-3-8], [8:0-3-8,Edge], [9:0-2-12,0-2-8], [11:0-3-8,0-2-8], [12:0-3-8,0-2-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.98	Vert(LL)	-0.61	10-11	>461	360	M18AHS	169/162
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.95	Vert(CT)	-0.72	10-11	>387	240	MT20	220/195
TCDL	12.0	Rep Stress Incr	YES	WB	0.85	Horz(CT)	0.12	8	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.11	10-11	>999	240		
BCDL	7.0										Weight: 137 lb	FT = 20%

LUMBER
TOP CHORD 2x6 DF No.2
BOT CHORD 2x4 DF 2100F 1.8E
WEBS 2x4 DF Stud *Except* W13,W6:2x4 DF No.2, W4,W12:2x4 DF 2100F 1.8E

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 8=1135/ Mechanical, 13=1358/0-5-8, (min. 0-3-8)
Max Horiz 13=53 (LC 9)
Max Uplift 8=-147 (LC 9), 13=-236 (LC 8)
Max Grav 8=2758 (LC 2), 13=3298 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 7-8=-2683/424, 5-6=-8276/1255, 6-7=-6371/986, 2-3=-5297/772, 3-4=-7987/1198, 4-15=-8271/1255, 15-16=-8263/1255, 5-16=-8260/1256
BOT CHORD 11-12=-710/5284, 10-11=-1130/7975, 9-10=-921/6357, 8-9=-25/274
WEBS 2-13=-3217/530, 5-10=-708/141, 4-10=-854/1221, 3-12=-2028/351, 2-12=-865/5611, 3-11=-455/2912, 4-11=-1059/198, 6-10=-279/2212, 6-9=-1918/333, 7-9=-957/6386


NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 12-1-12, Exterior (2) 12-1-12 to 13-7-1, Corner (3) 13-7-1 to 25-7-1 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) All plates are MT20 plates unless otherwise indicated.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Refer to girder(s) for truss to truss connections.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 147 lb uplift at joint 8 and 236 lb uplift at joint 13.
10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC9	Common	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:40 Page: 1
ID:DwNJQi1UoK0oTHWDyWrLd3zcZDa-HzGq3P8WKR66Sr2lQ59hzSCwjIESHLpf9A5gSTzUlfT





Scale = 1:42.7

Plate Offsets (X, Y): [3:0-3-7,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.63	Vert(LL)	-0.29	10	>759	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.90	Vert(CT)	-0.35	10	>638	240		
TCDL	12.0	Rep Stress Incr	YES	WB	1.00	Horz(CT)	0.09	8	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.06	10	>999	240		
BCDL	7.0										Weight: 100 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2 *Except* T1:2x4 DF 2100F 1.8E
BOT CHORD 2x4 DF No.2 *Except* B2:2x4 DF 2100F 1.8E
WEBS 2x4 DF Stud
OTHERS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 3-13

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 8=896/ Mechanical, 13=1124/0-5-8, (min. 0-2-15)
Max Horiz 13=61 (LC 9)
Max Uplift 8=-93 (LC 9), 13=-219 (LC 8)
Max Grav 8=2177 (LC 2), 13=2729 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 7-8=-318/69, 5-6=-4259/760, 3-4=-3837/652, 4-5=-5263/929
BOT CHORD 12-13=-584/3826, 11-12=-584/3826, 10-11=-855/5251, 9-10=-701/4326, 8-9=-449/2742
WEBS 2-13=-899/192, 5-9=-1023/205, 3-13=-4220/761, 3-11=-87/666, 4-11=-1565/298, 4-10=-554/166, 5-10=-243/1420, 6-9=-292/1859, 6-8=-3217/572

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 93 lb uplift at joint 8 and 219 lb uplift at joint 13.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC10	Common	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:40 Page: 1
ID:tVdHWdOgzEghRkEn86s8IBzcZD7-HzGq3P8WKR66Sr2lQ59hzSCvGIJAHMCf9A5gSTzUlfT



Scale = 1:40

Plate Offsets (X, Y): [2:0-3-8,0-2-8], [10:0-3-8,0-2-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.66	Vert(LL)	-0.13	9-10	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.59	Vert(CT)	-0.16	9-10	>999	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.91	Horz(CT)	0.03	7	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.03	9-10	>999	240		
BCDL	7.0										Weight: 79 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W4:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 7=656/ Mechanical, 12=891/0-5-8, (min. 0-2-5)
Max Horiz 12=66 (LC 9)
Max Uplift 7=-97 (LC 12), 12=-193 (LC 8)
Max Grav 7=1593 (LC 2), 12=2164 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-2559/499, 3-4=-2789/575, 4-5=-803/191
BOT CHORD 9-10=-440/2549, 8-9=-510/2779, 7-8=-120/793
WEBS 5-7=-1816/358, 2-12=-2000/453, 5-8=-154/924, 4-8=-2195/428, 3-10=-1050/264, 2-10=-604/2845, 3-9=-76/251

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 97 lb uplift at joint 7 and 193 lb uplift at joint 12.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC11	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:40 Page: 1
ID:PabKt5aiC9hQMBSs4T9vxZzcZCt-HzGq3P8WKR66Sr2lQ59hzSCu4IMqHQkf9A5gSTzUlfT



22-1-14 22-1-14



Scale = 1:34.1

0-2-12

Plate Offsets (X, Y): [4:Edge,0-3-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.74	Vert(LL)	-0.12	5-6	>909	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.42	Vert(CT)	-0.20	5-6	>536	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.68	Horz(CT)	0.02	5	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.00	5-6	>999	240		
BCDL	7.0										Weight: 52 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 5=411/ Mechanical, 6=663/0-5-8, (min. 0-1-11)
Max Horiz 6=64 (LC 9)
Max Uplift 5=-62 (LC 8), 6=-158 (LC 8)
Max Grav 5=998 (LC 2), 6=1610 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 4-5=-449/127
BOT CHORD 5-6=-283/1306
WEBS 2-6=-855/246, 3-5=-1270/328, 3-6=-1500/468

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 158 lb uplift at joint 6 and 62 lb uplift at joint 5.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC12	Jack-Closed	1	1	Job Reference (optional)



Scale = 1:29.9

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.66	Vert(LL)	-0.01	4-5	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.09	Vert(CT)	-0.01	4-5	>999	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.22	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.00	4-5	>999	240		
BCDL	7.0										Weight: 32 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=146/ Mechanical, 5=455/0-5-8, (min. 0-1-8)
Max Horiz 5=60 (LC 9)
Max Uplift 4=-17 (LC 12), 5=-133 (LC 8)
Max Grav 4=354 (LC 2), 5=1105 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-369/128
WEBS 2-5=-972/372


NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 133 lb uplift at joint 5 and 17 lb uplift at joint 4.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC13	Common	1	2	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:41 Page: 1
ID:EH0SGm3onRkl9LWYQttHZ_zcZCF-lAqCHl985lEz4?dy_ogwWfl7DiaA0rKoOqqE?vzUlfS





Scale = 1:56.2

Plate Offsets (X, Y): [2:0-3-8,0-2-8], [3:0-3-8,0-2-0], [7:0-3-8,0-2-0], [9:0-3-8,0-3-8], [13:0-3-8,0-3-8], [14:0-3-8,0-2-0], [17:0-3-8,0-2-0], [18:0-3-8,0-2-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.45	Vert(LL)	-0.49	14-16	>664	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.93	Vert(CT)	-0.58	14-16	>558	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.79	Horz(CT)	0.07	12	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.08	14-16	>999	240		
BCDL	7.0										Weight: 391 lb	FT = 20%

LUMBER
TOP CHORD 2x6 DF No.2
BOT CHORD 2x6 DF No.2
WEBS 2x4 DF Stud *Except* W4,W14:2x4 DF No.2
OTHERS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

REACTIONS (lb/size) 12=1614/0-7-12, (min. 0-2-1), 20=1514/0-5-8, (min. 0-1-15)
Max Horiz 20=-46 (LC 8)
Max Uplift 12=-287 (LC 9), 20=-245 (LC 8)
Max Grav 12=3919 (LC 2), 20=3676 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-251/22, 2-22=-6460/725, 3-22=-6449/726, 3-4=-10260/1189, 4-5=-11101/1292, 5-6=-11105/1292, 6-7=-10593/1229, 7-8=-6818/768, 8-23=-6821/768, 9-23=-6831/767
BOT CHORD 19-20=-37/251, 18-19=-37/251, 17-18=-665/6447, 16-17=-1124/10246, 15-16=-1164/10580, 14-15=-1164/10580, 13-14=-708/6816
WEBS 1-20=-16/340, 5-16=-495/90, 9-12=-3612/469, 2-20=-3504/457, 3-18=-2378/323, 2-18=-790/6612, 3-17=-487/4033, 4-17=-1322/191, 4-16=-643/1728, 9-13=-846/7158, 6-14=-1269/189, 6-16=-899/1536, 7-14=-484/3991, 7-13=-2334/318


NOTES
1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc, 2x6 - 2 rows staggered at 0-9-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Unbalanced roof live loads have been considered for this design.
4) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 28-0-11, Corner (3) 28-0-11 to 32-0-11 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
5) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
6) Provide adequate drainage to prevent water ponding.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 245 lb uplift at joint 20 and 287 lb uplift at joint 12.
10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC14	Common	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:41 Page: 1
ID:JW2FFzGXEAKZ9i9mHtgkd4zcZAh-IAqCHl985lEz4?dy_ogwWfl0xif?0pMoOqqE?vzUlfS





Scale = 1:59.2

Plate Offsets (X, Y): [2:0-2-4,0-1-8], [6:0-3-8,0-2-8], [7:0-3-8,Edge], [15:0-2-4,0-1-8], [17:0-3-4,0-1-12], [19:0-1-12,0-1-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.92	Vert(LL)	-0.37	17-18	>684	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.62	Vert(CT)	-0.44	17-18	>574	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.92	Horz(CT)	0.03	14	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.06	17-18	>999	240		
BCDL	7.0										Weight: 158 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2 *Except* T2:2x4 DF 2100F 1.8E
BOT CHORD 2x4 DF No.2 *Except* B2:2x4 DF 2100F 1.8E
WEBS 2x4 DF Stud *Except* W11:2x4 DF 2100F 1.8E, W10,W4:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 8-14

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 13=314/0-7-12, (min. 0-1-8), 14=1897/0-7-12, (min. 0-4-15), 21=1112/0-5-8, (min. 0-2-14)
Max Horiz 21=-51 (LC 8)
Max Uplift 13=-336 (LC 30), 14=-229 (LC 13), 21=-215 (LC 8)
Max Grav 13=1221 (LC 31), 14=4608 (LC 2), 21=2700 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-23=-3782/411, 3-23=-3772/411, 3-4=-5127/593, 4-5=-4181/500, 5-6=-4181/500, 6-7=-1454/203, 7-8=-399/3724, 8-9=-105/476, 9-24=-105/467, 10-24=-106/461, 10-11=-109/475
BOT CHORD 18-19=-344/3771, 17-18=-522/5116, 16-17=-132/1443, 15-16=-132/1443, 14-15=-3712/464, 13-14=-1168/179
WEBS 2-21=-2535/338, 11-13=-577/177, 10-13=-778/119, 8-13=-212/1177, 5-17=-743/117, 7-14=-3380/424, 8-14=-2767/310, 7-15=-650/5620, 6-15=-2224/281, 6-17=-322/2996, 4-17=-1543/341, 3-19=-1554/224, 2-19=-502/4146, 3-18=-194/1466, 4-18=-525/101


NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 30-0-11, Corner (3) 30-0-11 to 34-0-11 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 215 lb uplift at joint 21, 336 lb uplift at joint 13 and 229 lb uplift at joint 14.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC15	Common	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:41 Page: 1
ID:YWd4jrar69csHi8mpK7qgZzcZAH-lAqCHl985lEz4?dy_ogwWfl2yibU0oKoOqqE?vzUlfS





Scale = 1:56.8

Plate Offsets (X, Y): [2:0-3-8,0-2-0], [18:0-1-12,0-2-4]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.79	Vert(LL)	-0.25	17	>914	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.85	Vert(CT)	-0.30	17-18	>769	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.98	Horz(CT)	0.04	14	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.04	17	>999	240		
BCDL	7.0										Weight: 150 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2 *Except* T2:2x4 DF 2100F 1.8E
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W10,W4:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 6-14, 8-14

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 12=264/ Mechanical, 14=1898/0-7-12, (min. 0-4-15), 20=1004/0-5-8, (min. 0-2-10)
Max Horiz 20=-51 (LC 8)
Max Uplift 12=-210 (LC 30), 14=-234 (LC 9), 20=-207 (LC 8)
Max Grav 12=952 (LC 31), 14=4611 (LC 2), 20=2437 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-22=-3183/350, 3-22=-3173/351, 3-4=-3986/474, 4-5=-2520/311, 5-6=-2517/311, 6-7=-390/3612, 7-8=-394/3616, 8-23=-761/1055, 9-23=-762/1053, 11-12=-377/61
BOT CHORD 17-18=-284/3173, 16-17=-403/3975, 13-14=-1392/439, 12-13=-576/1219
WEBS 2-20=-2274/316, 7-14=-888/132, 5-16=-726/114, 6-16=-295/2822, 6-14=-4313/519, 3-18=-1306/200, 2-18=-438/3509, 3-17=-130/874, 4-17=-291/72, 4-16=-1800/183, 8-13=-79/885, 8-14=-3112/386, 9-13=-1071/163, 9-12=-1227/655

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 28-5-7, Corner (3) 28-5-7 to 32-5-7 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) All plates are 3x4 (=) MT20 unless otherwise indicated.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Refer to girder(s) for truss to truss connections.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 210 lb uplift at joint 12, 207 lb uplift at joint 20 and 234 lb uplift at joint 14.
10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC16	Common	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:42 Page: 1
ID:hjBG7Qod0Nfvkqdx1Gwkb9zcZ7Q-DMOaU5Ams2Mqh9B8YVB92tHDZ6_GlGJycUanXMzUlfR



Scale = 1:50.8

Plate Offsets (X, Y): [5:0-2-4,0-1-8], [14:0-2-0,0-2-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.80	Vert(LL)	-0.19	15-16	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.68	Vert(CT)	-0.23	15-16	>898	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.93	Horz(CT)	0.05	9	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.03	15-16	>999	240		
BCDL	7.0										Weight: 131 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2 *Except* T2:2x4 DF 2100F 1.8E
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W8:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 2-17

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 9=336/ Mechanical, 12=1696/0-7-12, (min. 0-4-6), 17=697/ Mechanical
Max Horiz 17=-54 (LC 8)
Max Uplift 9=-116 (LC 30), 12=-199 (LC 9), 17=-122 (LC 8)
Max Grav 9=1061 (LC 31), 12=4119 (LC 2), 17=1693 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-17=-435/75, 2-3=-3143/461, 3-18=-1426/222, 4-18=-1409/222, 4-19=-1416/222, 5-19=-1428/221, 5-6=-309/2482, 6-7=-854/989, 8-9=-379/68
BOT CHORD 16-17=-338/2843, 15-16=-338/2843, 14-15=-390/3132, 13-14=-2471/379, 12-13=-2471/379, 11-12=-988/845, 10-11=-351/1422, 9-10=-351/1422
WEBS 5-12=-2799/416, 4-14=-794/135, 5-14=-571/4230, 2-17=-2951/439, 2-15=-56/313, 3-14=-2007/272, 6-12=-2632/379, 7-9=-1463/397, 6-11=-46/521, 7-11=-1165/165

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 12-1-12, Exterior (2) 12-1-12 to 15-11-15, Corner (3) 15-11-15 to 27-11-15 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 122 lb uplift at joint 17, 116 lb uplift at joint 9 and 199 lb uplift at joint 12.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC17	Common	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:42 Page: 1
ID:tNPHZpLsPCKWdkaaADDIvezcZ6j-DMOaU5Ams2Mqh9B8YVB92tHCj6?tlG0ycUanXMzUlfR



Scale = 1:47.8

Plate Offsets (X, Y): [15:0-3-8,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.85	Vert(LL)	-0.13	15-16	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.58	Vert(CT)	-0.16	15-16	>999	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.95	Horz(CT)	0.03	9	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.02	15-16	>999	240		
BCDL	7.0										Weight: 124 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W8:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 9=369/ Mechanical, 12=1558/0-7-12, (min. 0-4-1), 17=606/ Mechanical
Max Horiz 17=-54 (LC 8)
Max Uplift 9=-79 (LC 13), 12=-168 (LC 9), 17=-112 (LC 8)
Max Grav 9=1112 (LC 31), 12=3783 (LC 2), 17=1523 (LC 30)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-17=-421/77, 2-3=-2428/355, 3-18=-2480/366, 4-18=-2461/366, 4-19=-371/306, 5-19=-372/295, 5-6=-267/2096, 6-7=-1056/795, 8-9=-382/72
BOT CHORD 16-17=-284/2418, 15-16=-290/2469, 14-15=-302/372, 13-14=-302/372, 12-13=-2087/340, 11-12=-794/1047, 10-11=-260/1487, 9-10=-260/1487
WEBS 4-13=-1682/267, 5-12=-2478/384, 5-13=-392/2736, 6-12=-2598/393, 7-9=-1541/300, 6-11=-35/438, 7-11=-938/140, 2-17=-2511/382, 3-15=-1011/183, 4-15=-359/2440

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 12-1-12, Exterior (2) 12-1-12 to 13-11-15, Corner (3) 13-11-15 to 25-11-15 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 112 lb uplift at joint 17, 79 lb uplift at joint 9 and 168 lb uplift at joint 12.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC18	Common	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:42 Page: 1
ID:S4FaVbWe6W5XJueH_9TaUbzcZ6V-DMOaU5Ams2Mqh9B8YVB92tHAl61GlGsycUanXMzUlfR



Scale = 1:44.9

Plate Offsets (X, Y): [1:0-3-4,0-2-8], [3:0-3-12,0-5-4], [7:0-3-8,0-1-8], [10:0-6-0,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.98	Vert(LL)	-0.12	10	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.49	Vert(CT)	-0.15	10	>999	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.90	Horz(CT)	0.01	6	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.02	10	>999	240		
BCDL	7.0										Weight: 125 lb	FT = 20%

LUMBER
TOP CHORD 2x6 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W1,W4:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 4-8

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 6=410/ Mechanical, 8=1404/0-7-12, (min. 0-3-10), 11=523/ Mechanical
Max Horiz 11=52 (LC 9)
Max Uplift 6=-82 (LC 9), 8=-137 (LC 12), 11=-99 (LC 8)
Max Grav 6=1154 (LC 31), 8=3413 (LC 2), 11=1354 (LC 30)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-11=-1289/223, 1-2=-2550/364, 2-3=-2317/326, 3-4=-223/1529, 4-5=-1788/337, 5-6=-1092/171
BOT CHORD 10-11=-34/270, 9-10=-930/190, 8-9=-930/190, 7-8=-335/1776
WEBS 1-10=-352/2338, 2-10=-1488/290, 3-10=-468/3064, 3-8=-2377/419, 4-8=-2924/486, 4-7=-430/172, 5-7=-381/1645


NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) All plates are MT20 plates unless otherwise indicated.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Refer to girder(s) for truss to truss connections.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 99 lb uplift at joint 11, 82 lb uplift at joint 6 and 137 lb uplift at joint 8.
10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC19	Common	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:42 Page: 1
ID:M?iVuTCS8Xkg6PLBBZ_P97zcZ4J-DMOaU5Ams2Mqh9B8YVB92tHBo61elFbycUanXMzUlfR





Scale = 1:41.9

Plate Offsets (X, Y): [3:0-3-7,0-2-0], [8:0-3-8,0-1-8], [11:0-3-8,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.91	Vert(LL)	-0.08	11	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.47	Vert(CT)	-0.09	11	>999	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.98	Horz(CT)	0.01	7	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.01	11	>999	240		
BCDL	7.0										Weight: 117 lb	FT = 20%

LUMBER
TOP CHORD 2x6 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W4:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 7=429/ Mechanical, 9=1288/0-7-12, (min. 0-3-5), 12=425/ Mechanical
Max Horiz 12=54 (LC 9)
Max Uplift 7=-80 (LC 13), 9=-138 (LC 12), 12=-87 (LC 8)
Max Grav 7=1128 (LC 31), 9=3126 (LC 2), 12=1146 (LC 30)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-12=-586/117, 2-3=-1743/262, 3-4=-140/1131, 4-5=-1621/278, 6-7=-595/122
BOT CHORD 11-12=-192/1731, 10-11=-1135/214, 9-10=-1135/214, 8-9=-462/85, 7-8=-206/1610
WEBS 4-9=-1419/232, 4-8=-309/1874, 5-8=-795/180, 5-7=-1509/221, 3-9=-1958/358, 2-11=-861/188, 2-12=-1622/257, 3-11=-431/2671

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 87 lb uplift at joint 12, 80 lb uplift at joint 7 and 138 lb uplift at joint 9.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC20	Common	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:43 Page: 1
ID:kPFE2V7Zx3eF3hQYRkpSZRzcZ1r-hYyyiRAOdMUhJJmK6DjOb4qQIVOkUlW5r8JL3ozUlfQ






Plate Offsets (X, Y): [9:0-3-0,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.67	Vert(LL)	-0.07	8-9	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.41	Vert(CT)	-0.12	8-9	>999	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.81	Horz(CT)	0.02	8	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.01	8-9	>999	240		
BCDL	7.0										Weight: 96 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 8=454/ Mechanical, 10=1158/0-7-12, (min. 0-3-0), 14=335/ Mechanical
Max Horiz 14=59 (LC 9)
Max Uplift 8=-76 (LC 13), 10=-145 (LC 12), 14=-69 (LC 8)
Max Grav 8=1102 (LC 2), 10=2815 (LC 2), 14=902 (LC 30)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-14=-306/64, 2-3=-682/218, 3-4=-137/975, 4-5=-879/181, 5-6=-880/181, 7-8=-381/83
BOT CHORD 13-14=-87/978, 12-13=-87/978, 11-12=-87/978, 10-11=-218/674, 9-10=-967/206, 8-9=-235/1381
WEBS 4-10=-1867/354, 4-9=-358/2105, 5-9=-704/155, 6-9=-646/145, 6-8=-1437/294, 2-14=-1069/183, 3-10=-1608/268, 2-11=-520/79, 3-11=-16/287

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 69 lb uplift at joint 14, 76 lb uplift at joint 8 and 145 lb uplift at joint 10.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FCGR	Common Girder	1	4	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:43 Page: 1
ID:y?3IdF96n2EtGtVP5tXk2wzcY57-hYyyiRAOdMUhJJmK6DjOb4qMVVIbUjC5r8JL3ozUlfQ



Scale = 1:53.9

Plate Offsets (X, Y): [2:0-2-0,0-2-0], [3:0-3-8,0-2-0], [10:0-3-8,0-2-0], [12:0-3-0,0-1-8], [16:0-3-8,0-2-8], [17:0-1-12,0-2-0], [21:0-3-8,0-2-0], [22:0-3-8,0-2-0], [23:0-2-0,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.92	Vert(LL)	-0.77	18-20	>429	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.80	Vert(CT)	-0.90	18-20	>367	240	M18AHS	132/127
TCDL	12.0	Rep Stress Incr	NO	WB	0.96	Horz(CT)	0.09	15	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH		Wind(LL)	0.12	18-20	>999	240		
BCDL	7.0										Weight: 877 lb	FT = 20%

LUMBER

TOP CHORD	2x6 DF 1950F 1.5E or 2x6 DF SS *Except* T4,T1:2x6 DF No.2
BOT CHORD	2.0 RigidLam DF LVL 1-1/2 x 7-1/4 *Except* B1:2x8 DF 2250F 1.6E or 2x8 DF SS
WEBS	2x4 DF Stud *Except* W14,W4,W6,W8:2x4 DF No.2, W15:2x4 DF 2100F 1.8E

BRACING

TOP CHORD	Structural wood sheathing directly applied or 3-10-14 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 25-26,14-15.

REACTIONS (lb/size) 15=5379/0-5-15, (min. 0-2-15), 25=3316/0-5-15, (min. 0-2-3)
Max Horiz 25=-43 (LC 8)
Max Uplift 15=-837 (LC 7), 25=-620 (LC 6)
Max Grav 15=13331 (LC 2), 25=8312 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-26=-758/61, 1-2=-1240/99, 2-3=-14862/1009, 3-4=-27481/1785, 4-5=-35836/2246, 5-6=-35826/2247, 6-7=-39949/2391, 7-8=-41056/2457, 8-9=-35893/2128, 9-10=-35896/2125, 10-11=-22819/1351, 11-12=-22832/1350, 12-13=-2363/148, 13-14=-1512/95

BOT CHORD 24-25=-115/1243, 24-27=-115/1243, 23-27=-115/1243, 23-28=-985/14846, 22-28=-985/14846, 22-29=-1759/27469, 29-30=-1759/27469, 21-30=-1759/27469, 21-31=-2218/35823, 20-31=-2218/35823, 20-32=-2398/39937, 19-32=-2398/39937, 18-19=-2398/39937, 18-33=-2464/41045, 17-33=-2464/41045, 17-34=-1365/22813, 16-34=-1365/22813, 16-35=-148/2367, 15-35=-148/2367

WEBS 1-25=-110/1512, 13-15=-169/2880, 2-25=-7510/537, 12-15=-11150/693, 7-20=-552/591, 7-18=-1078/2549, 8-18=-177/2182, 8-17=-5758/414, 9-17=-739/84, 10-17=-849/14251, 10-16=-6402/415, 12-16=-1337/22474, 3-23=-6561/433, 2-23=-1009/14858, 3-22=-857/13890, 4-22=-4937/310, 4-21=-564/9260, 6-21=-2772/163, 6-20=-317/5498

NOTES

1) 4-ply truss to be connected together with 10d (0.131"x3") nails as follows:
   Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc, 2x6 - 2 rows staggered at 0-6-0 oc.
   Bottom chords connected as follows: 2x8 - 4 rows staggered at 0-4-0 oc.
   Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
   Attach TC w/ 1/2" diam. bolts (ASTM A-307) in the center of the member w/washers at 4-0-0 oc.
   Attach BC w/ 1/2" diam. bolts (ASTM A-307) in the center of the member w/washers at 4-0-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Unbalanced roof live loads have been considered for this design.
4) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
5) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
6) Provide adequate drainage to prevent water ponding.
7) All plates are MT20 plates unless otherwise indicated.


Continued on page 2

8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 620 lb uplift at joint 25 and 837 lb uplift at joint 15.
11) Use Simpson Strong-Tie TJC37 (4 nail, 22-30) or equivalent at 4-10-13 from the left end to connect truss(es) FC7 (1 ply 2x4 DF) to front face of bottom chord, skewed 67.5 deg.to the left, sloping 0.0 deg. down.
12) Use Simpson Strong-Tie THASL29 (23 to 74 Skewed Left) or equivalent at 10-1-8 from the left end to connect truss(es) FC6 (1 ply 2x4 DF) to front face of bottom chord, skewed 67.5 deg.to the left, sloping 0.0 deg. down.
13) Use Simpson Strong-Tie THASL29 (46 to 85 Skewed Left Screws) or equivalent at 15-4-4 from the left end to connect truss(es) FC5 (1 ply 2x4 DF) to front face of bottom chord, skewed 67.5 deg.to the left, sloping 0.0 deg. down.
14) Use Simpson Strong-Tie TJC37 (6 nail, 150-157) or equivalent at 7-1-5 from the left end to connect truss(es) FC12 (1 ply 2x4 DF) to back face of bottom chord, skewed 67.5 deg.to the right, sloping 0.0 deg. down.
15) Use Simpson Strong-Tie THASR29 (23 to 74 Skewed Right) or equivalent at 12-4-1 from the left end to connect truss(es) FC11 (1 ply 2x4 DF) to back face of bottom chord, skewed 67.5 deg.to the right, sloping 0.0 deg. down.
16) Use Simpson Strong-Tie THASR29 (46 to 85 Skewed Right Screws) or equivalent at 17-6-12 from the left end to connect truss(es) FC10 (1 ply 2x4 DF) to back face of bottom chord, skewed 67.5 deg.to the right, sloping 0.0 deg. down.
17) Fill all nail holes where hanger is in contact with lumber.
18) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 1894 lb down and 101 lb up at 20-6-15, 2141 lb down and 109 lb up at 22-9-8, and 2476 lb down and 141 lb up at 25-9-11, and 2721 lb down and 162 lb up at 28-0-3 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard

1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
   Uniform Loads (lb/ft)
   Vert: 1-13=-84, 14-26=-14
   Concentrated Loads (lb)
   Vert: 17=-860 (B), 27=40 (F), 28=-109 (B), 29=-267 (F), 30=-374 (B), 31=-516 (F), 32=-619 (B), 33=-758 (F), 34=-998 (F), 35=-1099 (B)

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD1	Half Hip	2	**2**	Job Reference (optional)






Plate Offsets (X, Y): [3:0-2-8,0-3-4], [5:0-0-8,0-1-8], [8:0-4-0,0-3-4], [9:0-3-8,0-2-8]

Loading	(psf)	**Spacing**	2-0-0	**CSI**		**DEFL**	in	(loc)	l/defl	L/d	**PLATES**	**GRIP**
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.69	Vert(LL)	-0.37	8-9	>630	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.93	Vert(CT)	-0.44	8-9	>529	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.79	Horz(CT)	0.07	6	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.08	8	>999	240		
BCDL	7.0										Weight: 172 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W2:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.


REACTIONS (lb/size) 6=944/ Mechanical, 10=944/ Mechanical
Max Horiz 10=54 (LC 9)
Max Uplift 6=-162 (LC 12), 10=-164 (LC 8)
Max Grav 6=2292 (LC 2), 10=2292 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-10=-2200/424, 1-2=-6388/1168, 2-3=-7938/1463, 3-4=-5656/1054, 4-5=-273/74, 5-6=-510/112
BOT CHORD 9-10=-45/427, 8-9=-1130/6375, 7-8=-1420/7927, 6-7=-1005/5643
WEBS 1-9=-1134/6138, 2-9=-1520/324, 2-8=-301/1614, 3-8=-365/108, 3-7=-2373/432, 4-7=-77/669, 4-6=-5646/1035

NOTES
1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Unbalanced roof live loads have been considered for this design.
4) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
5) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
6) Provide adequate drainage to prevent water ponding.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Refer to girder(s) for truss to truss connections.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 164 lb uplift at joint 10 and 162 lb uplift at joint 6.
11) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD2	Half Hip	2	**2**	Job Reference (optional)





Scale = 1:38

Plate Offsets (X, Y): [4:0-2-0,Edge], [10:0-3-8,0-2-0]

Loading	(psf)	**Spacing**	2-0-0	**CSI**		**DEFL**	in	(loc)	l/defl	L/d	**PLATES**	**GRIP**
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.55	Vert(LL)	-0.34	10-11	>686	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.94	Vert(CT)	-0.40	10-11	>576	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.79	Horz(CT)	0.08	8	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.07	10-11	>999	240		
BCDL	7.0										Weight: 176 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 6-7.
BOT CHORD Rigid ceiling directly applied.


REACTIONS (lb/size) 8=944/ Mechanical, 14=944/ Mechanical
Max Horiz 14=52 (LC 9)
Max Uplift 8=-162 (LC 8), 14=-164 (LC 8)
Max Grav 8=2292 (LC 2), 14=2292 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-14=-423/91, 1-2=-301/43, 2-3=-5572/1022, 3-4=-7913/1463, 4-5=-7903/1463, 5-6=-6682/1246
BOT CHORD 13-14=-979/5560, 12-13=-1414/7901, 11-12=-1414/7901, 10-11=-1192/6670, 9-10=-487/2814, 8-9=-485/2819
WEBS 6-8=-3473/632, 2-14=-5562/1028, 2-13=-89/695, 3-13=-2442/454, 3-11=-366/104, 5-11=-235/1304, 5-10=-1379/291, 6-10=-752/4110

NOTES
1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Unbalanced roof live loads have been considered for this design.
4) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
5) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
6) Provide adequate drainage to prevent water ponding.
7) All plates are MT20 plates unless otherwise indicated.
8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
10) Refer to girder(s) for truss to truss connections.
11) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 164 lb uplift at joint 14 and 162 lb uplift at joint 8.
12) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
13) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD3	Half Hip	2	**2**	Job Reference (optional)





Scale = 1:38

Plate Offsets (X, Y): [7:0-3-4,0-2-0], [10:0-1-12,0-2-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.80	Vert(LL)	-0.36	8-10	>640	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.82	Vert(CT)	-0.43	8-10	>534	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.93	Horz(CT)	0.05	6	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.08	8-10	>999	240		
BCDL	7.0										Weight: 172 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W2:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (5-7-14 max.): 4-5.
BOT CHORD Rigid ceiling directly applied.

REACTIONS (lb/size) 6=944/ Mechanical, 11=944/ Mechanical
Max Horiz 11=51 (LC 9)
Max Uplift 6=-162 (LC 8), 11=-164 (LC 8)
Max Grav 6=2292 (LC 2), 11=2292 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-11=-2206/424, 1-2=-6480/1184, 2-3=-7967/1475, 3-4=-7725/1428, 4-12=-4735/890, 5-12=-4735/890, 5-6=-2225/422
BOT CHORD 10-11=-43/399, 9-10=-1144/6461, 8-9=-1144/6461, 7-8=-868/4900
WEBS 4-7=-1757/357, 5-7=-882/4854, 4-8=-534/2960, 1-10=-1156/6263, 2-10=-1530/331, 2-8=-293/1531, 3-8=-1221/271

NOTES
1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Unbalanced roof live loads have been considered for this design.
4) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
5) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
6) Provide adequate drainage to prevent water ponding.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Refer to girder(s) for truss to truss connections.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 164 lb uplift at joint 11 and 162 lb uplift at joint 6.
11) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
12) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD4	Half Hip	2	2	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:44 Page: 1
ID:2bAohcKpKxuEevWL0C6b5NzhUb4-9lWKvnB0OgcYxTLXfwEd7INZ3vcoDCGF4o3ubEzUlfP



22-1-14 22-1-14



Scale = 1:38

Plate Offsets (X, Y): [4:0-6-4,0-3-4], [5:0-3-8,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.80	Vert(LL)	-0.38	7-8	>604	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.93	Vert(CT)	-0.46	7-8	>507	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.78	Horz(CT)	0.09	6	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.08	7-8	>999	240		
BCDL	7.0										Weight: 171 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W9:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 4-5.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 4-6


REACTIONS (lb/size) 6=944/ Mechanical, 11=944/ Mechanical
Max Horiz 11=49 (LC 11)
Max Uplift 6=-162 (LC 8), 11=-164 (LC 8)
Max Grav 6=2292 (LC 2), 11=2292 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-11=-517/111, 1-2=-402/61, 2-3=-6065/1115, 3-4=-7908/1464, 4-12=-522/124, 5-12=-522/124, 5-6=-721/158
BOT CHORD 10-11=-1068/6053, 9-10=-1413/7897, 8-9=-1413/7897, 7-8=-1157/6489, 6-7=-1153/6489
WEBS 4-6=-6147/1115, 4-8=-485/1492, 2-10=-64/564, 2-11=-5905/1092, 3-10=-1935/361, 3-8=-391/244

NOTES
1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Unbalanced roof live loads have been considered for this design.
4) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
5) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
6) Provide adequate drainage to prevent water ponding.
7) All plates are MT20 plates unless otherwise indicated.
8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
10) Refer to girder(s) for truss to truss connections.
11) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 164 lb uplift at joint 11 and 162 lb uplift at joint 6.
12) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
13) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD5	Half Hip	2	**2**	Job Reference (optional)



22-1-14 22-1-14

Scale = 1:38

Plate Offsets (X, Y): [3:0-5-4,0-3-0], [8:0-4-0,0-3-0], [9:0-2-0,0-2-4]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.93	Vert(LL)	-0.38	8-9	>616	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.89	Vert(CT)	-0.45	8-9	>513	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.74	Horz(CT)	0.07	6	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.08	8-9	>999	240		
BCDL	7.0										Weight: 171 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W2:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (5-5-7 max.): 3-5.
BOT CHORD Rigid ceiling directly applied.

REACTIONS (lb/size) 6=944/ Mechanical, 10=944/ Mechanical
Max Horiz 10=48 (LC 9)
Max Uplift 6=-162 (LC 8), 10=-164 (LC 8)
Max Grav 6=2292 (LC 2), 10=2292 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-10=-2193/426, 1-2=-7111/1304, 2-3=-7542/1393, 3-4=-5047/949, 5-6=-443/97
BOT CHORD 9-10=-47/534, 8-9=-1260/7090, 7-8=-1344/7527, 6-7=-897/5047
WEBS 4-6=-5124/937, 4-7=-122/871, 3-7=-2631/474, 2-8=-90/1351, 2-9=-1421/316, 1-9=-1243/6714


NOTES
1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Unbalanced roof live loads have been considered for this design.
4) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
5) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
6) Provide adequate drainage to prevent water ponding.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Refer to girder(s) for truss to truss connections.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 164 lb uplift at joint 10 and 162 lb uplift at joint 6.
11) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
12) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD6	Half Hip	2	**2**	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:45 Page: 1
ID:T3YwHKpLbQGwHfro9pIC15zhUZA-dx4i66Ce9zkPYcwjDelsgVvlsJy_ye8OISoR8hzUlfO





Scale = 1:38

Plate Offsets (X, Y): [3:0-5-8,0-3-4], [5:Edge,0-1-8], [10:0-3-8,0-2-8]

Loading	(psf)	**Spacing**	2-0-0	**CSI**		**DEFL**	in	(loc)	l/defl	L/d	**PLATES**	**GRIP**
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.73	Vert(LL)	-0.38	7-8	>615	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.94	Vert(CT)	-0.45	7-8	>517	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.87	Horz(CT)	0.07	6	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.08	8	>999	240		
BCDL	7.0										Weight: 171 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W2:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (3-8-11 max.): 3-5.
BOT CHORD Rigid ceiling directly applied.

REACTIONS (lb/size) 6=944/ Mechanical, 11=944/ Mechanical
Max Horiz 11=47 (LC 9)
Max Uplift 6=-162 (LC 8), 11=-164 (LC 8)
Max Grav 6=2292 (LC 2), 11=2292 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-11=-2201/424, 1-2=-6275/1149, 2-3=-7959/1469, 3-4=-6186/1156, 4-5=-349/89, 5-6=-538/117
BOT CHORD 10-11=-42/402, 9-10=-1106/6263, 8-9=-1106/6263, 7-8=-1409/7907, 6-7=-1106/6186
WEBS 3-8=-494/112, 2-8=-327/2104, 4-6=-6069/1110, 4-7=-39/482, 3-7=-1786/315, 2-10=-1546/329, 1-10=-1121/6059

NOTES
1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Unbalanced roof live loads have been considered for this design.
4) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
5) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
6) Provide adequate drainage to prevent water ponding.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Refer to girder(s) for truss to truss connections.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 164 lb uplift at joint 11 and 162 lb uplift at joint 6.
11) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
12) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD7	Half Hip	2	**2**	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:45 Page: 1
ID:QGFyPSSb6ixO8oP_mSlehHzhUYL-dx4i66Ce9zkPYcwjDeIsgVvjVJyfyeGOISoR8hzUlfO



22-1-14 22-1-14



Scale = 1:38

Plate Offsets (X, Y): [4:0-2-4,0-2-0], [5:Edge,0-3-8], [8:0-2-8,0-3-4]

Loading	(psf)	**Spacing**	2-0-0	**CSI**		**DEFL**	in	(loc)	l/defl	L/d	**PLATES**	**GRIP**
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.88	Vert(LL)	-0.41	7-8	>570	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.96	Vert(CT)	-0.48	7-8	>477	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.86	Horz(CT)	0.09	6	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.09	7-8	>999	240		
BCDL	7.0										Weight: 168 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2 *Except* T2:2x4 DF 2100F 1.8E
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (4-5-7 max.): 3-5.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 4-6

REACTIONS (lb/size) 6=944/ Mechanical, 9=944/ Mechanical
Max Horiz 9=45 (LC 9)
Max Uplift 6=-162 (LC 8), 9=-164 (LC 8)
Max Grav 6=2292 (LC 2), 9=2292 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-9=-444/95, 1-2=-274/21, 2-3=-7704/1404, 3-4=-7225/1347, 4-5=-495/114, 5-6=-643/141
BOT CHORD 8-9=-932/5186, 7-8=-1356/7695, 6-7=-1298/7225
WEBS 4-6=-6907/1266, 3-8=-820/198, 3-7=-481/745, 2-8=-451/2727, 2-9=-5233/1014

NOTES
1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Unbalanced roof live loads have been considered for this design.
4) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
5) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
6) Provide adequate drainage to prevent water ponding.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Refer to girder(s) for truss to truss connections.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 164 lb uplift at joint 9 and 162 lb uplift at joint 6.
11) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
12) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD8	Half Hip Girder	2	3	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:45 Page: 1
ID:fLwU8bbYzbn3QFa2GBQgV5zhUWt-dx4i66Ce9zkPYcwjDelsgVvihJ?Zye0OISoR8hzUlfO



Scale = 1:38

Plate Offsets (X, Y): [2:0-10-0,0-5-8], [3:0-5-4,0-3-0], [5:0-3-8,0-2-8], [7:Edge,0-3-0], [9:0-4-4,0-3-4], [11:0-5-12,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.94	Vert(LL)	-0.50	10-11	>463	360	MT20	174/154
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.71	Vert(CT)	-0.59	10-11	>393	240	M18AHS	132/127
TCDL	12.0	Rep Stress Incr	NO	WB	0.87	Horz(CT)	0.06	8	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MSH		Wind(LL)	0.09	10-11	>999	240		
BCDL	7.0										Weight: 382 lb	FT = 20%

LUMBER

TOP CHORD	2x6 DF No.2
BOT CHORD	2.0 RigidLam DF LVL 1-1/2 x 7-1/4
WEBS	2x4 DF Stud *Except* W3:2x8 DF 2250F 1.6E or 2x8 DF SS, W7:2x4 DF 2100F 1.8E

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (3-8-11 max.): 3-7.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 8=2819/ Mechanical, 14=2583/ Mechanical
Max Horiz 14=38 (LC 7)
Max Uplift 8=-529 (LC 7), 14=-486 (LC 6)
Max Grav 8=6942 (LC 2), 14=6365 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	1-14=-680/59, 1-2=-1079/92, 2-3=-12325/947, 3-4=-25591/1955, 4-5=-23892/1829, 5-6=-15103/1159, 6-7=-15103/1159, 7-8=-5091/398
BOT CHORD	14-15=-961/12288, 13-15=-961/12288, 13-16=-1657/21441, 12-16=-1657/21441, 12-17=-1675/21696, 11-17=-1675/21696, 11-18=-1973/25599, 18-19=-1973/25599, 10-19=-1973/25599, 10-20=-1838/23892, 20-21=-1838/23892, 9-21=-1838/23892, 9-22=-86/1015, 8-22=-86/1015
WEBS	3-12=-131/1926, 3-11=-314/4080, 4-10=-1790/160, 5-10=-141/2004, 5-9=-9213/706, 6-9=-552/111, 2-14=-12093/925, 2-13=-303/4187, 3-13=-9902/759, 7-9=-1130/14767

NOTES

1) 3-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc, 2x6 - 2 rows staggered at 0-9-0 oc.
Bottom chords connected as follows: 2x8 - 2 rows staggered at 0-4-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc, 2x8 - 2 rows staggered at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Unbalanced roof live loads have been considered for this design.
4) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
5) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
6) Provide adequate drainage to prevent water ponding.
7) All plates are MT20 plates unless otherwise indicated.
8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
10) Refer to girder(s) for truss to truss connections.
11) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 486 lb uplift at joint 14 and 529 lb uplift at joint 8.
12) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.


Continued on page 2

13) Use Simpson Strong-Tie LUS26 (4-SD9112 Girder, 4-SD9212 Truss, Single Ply Girder) or equivalent spaced at 2-0-0 oc max. starting at 1-4-12 from the left end to 19-4-12 to connect truss(es) FD11 (1 ply 2x4 DF), FD10 (1 ply 2x4 DF), FD9 (1 ply 2x4 DF) to back face of bottom chord.
14) Fill all nail holes where hanger is in contact with lumber.

LOAD CASE(S) Standard

1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-7=-84, 8-14=-14
Concentrated Loads (lb)
Vert: 8=-358 (B), 12=-351 (B), 15=-351 (B), 16=-351 (B), 17=-351 (B), 18=-351 (B), 19=-351 (B), 20=-351 (B), 21=-351 (B), 22=-351 (B)

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD9	Jack-Closed	8	1	Job Reference (optional)



Scale = 1:32.9

Plate Offsets (X, Y): [1:0-5-12,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.85	Vert(LL)	-0.04	5	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.38	Vert(CT)	-0.05	4-5	>999	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.54	Horz(CT)	0.01	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.01	5	>999	240		
BCDL	7.0										Weight: 36 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud
OTHERS 2x10 DF SS

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

REACTIONS (lb/size) 4=365/ Mechanical, 9=319/0-6-0, (min. 0-1-8)
Max Horiz 9=38 (LC 11)
Max Uplift 4=-63 (LC 8), 9=-53 (LC 8)
Max Grav 4=886 (LC 2), 9=769 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-1507/436, 3-4=-364/117
BOT CHORD 5-6=-111/447, 4-5=-398/1500
WEBS 2-4=-1577/443, 2-5=-376/146, 1-5=-308/1128, 1-9=-1139/317

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) All plates are MT20 plates unless otherwise indicated.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Refer to girder(s) for truss to truss connections.
9) Bearing at joint(s) 9 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 63 lb uplift at joint 4 and 53 lb uplift at joint 9.
11) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD10	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:46 Page: 1
ID:4f4BCoQmGH02k5WMSFAOw8zhUX5-57e5KSDGwHsGAmVvnLG5DjSsfjQ0hEhXX6Y?g7zUlfN



Scale = 1:32.8

Plate Offsets (X, Y): [1:0-4-12,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.99	Vert(LL)	-0.02	6-7	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.37	Vert(CT)	-0.04	6-7	>999	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.27	Horz(CT)	0.01	5	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP		Wind(LL)	0.01	6-7	>999	240		
BCDL	7.0										Weight: 36 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W1:2x10 DF SS

BRACING
TOP CHORD Structural wood sheathing directly applied or 5-8-7 oc purlins, except end verticals, and 2-0-0 oc purlins: 3-4.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 5=365/ Mechanical, 10=319/0-6-0, (min. 0-1-8)
Max Horiz 10=36 (LC 11)
Max Uplift 5=-63 (LC 8), 10=-53 (LC 8)
Max Grav 5=886 (LC 2), 10=769 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 7-10=-124/497, 1-10=-124/497, 1-11=-430/143, 2-11=-420/143, 2-3=-988/278
BOT CHORD 6-7=-374/1341, 5-6=-230/955
WEBS 3-5=-1164/308, 2-6=-403/157, 2-7=-1025/303, 1-10=-1113/310

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) All plates are MT20 plates unless otherwise indicated.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Refer to girder(s) for truss to truss connections.
9) Bearing at joint(s) 10 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 63 lb uplift at joint 5 and 53 lb uplift at joint 10.
11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD11	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:46 Page: 1
ID:rBZDtXWoOl0viK7uwxKGFqzhUWz-57e5KSDGwHsGAmVvnLG5DjSxqjQehBMXX6Y?g7zUlfN



Scale = 1:32.7

Plate Offsets (X, Y): [1:0-3-4,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.65	Vert(LL)	-0.04	4-5	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.33	Vert(CT)	-0.04	4-5	>999	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.48	Horz(CT)	0.01	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.01	5	>999	240		
BCDL	7.0										Weight: 36 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2 *Except* T2:2x4 DF 2100F 1.8E
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W1:2x4 DF No.2
OTHERS 2x10 DF SS

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins: 2-3.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=365/ Mechanical, 9=319/0-6-0, (min. 0-1-8)
Max Horiz 9=35 (LC 11)
Max Uplift 4=-63 (LC 8), 9=-53 (LC 8)
Max Grav 4=886 (LC 2), 9=769 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 6-9=-73/338, 1-9=-73/338, 1-10=-555/183, 2-10=-546/183, 3-4=-432/140
BOT CHORD 5-6=-327/1299, 4-5=-331/1295
WEBS 2-4=-1361/371, 2-6=-812/201, 1-9=-1249/353

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) All plates are MT20 plates unless otherwise indicated.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Refer to girder(s) for truss to truss connections.
9) Bearing at joint(s) 9 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 63 lb uplift at joint 4 and 53 lb uplift at joint 9.
11) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
12) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD12	Jack-Closed	8	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:46 Page: 1
ID:a1oWX_b2kAkYR8FMVt0xvUzhU1t-57e5KSDGwHsGAmVvnLG5DjS16jRFhCJXX6Y?g7zUlfN




22-11-8 22-1-14

2-2-6

1-11-12

1-6-4



0-2-10

0-5-8

Scale = 1:36.9

0-2-10

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.32	Vert(LL)	-0.05	5-6	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.30	Vert(CT)	-0.09	5-6	>802	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.42	Horz(CT)	0.01	5	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.00	7	>999	240		
BCDL	7.0										Weight: 37 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud
OTHERS 2x8 DF 2250F 1.6E or 2x8 DF SS

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 5=278/ Mechanical, 11=471/0-5-4, (min. 0-1-8)
Max Horiz 11=44 (LC 9)
Max Uplift 5=-45 (LC 8), 11=-111 (LC 8)
Max Grav 5=676 (LC 2), 11=1152 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 4-5=-260/84
BOT CHORD 5-6=-239/837
WEBS 3-5=-918/288, 3-6=-799/263, 6-11=-90/370, 2-11=-90/370

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) All plates are MT20 plates unless otherwise indicated.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Refer to girder(s) for truss to truss connections.
9) Bearing at joint(s) 11 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 45 lb uplift at joint 5 and 111 lb uplift at joint 11.
11) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD13	Jack-Closed	1	1	Job Reference (optional)




22-11-8 22-1-14

2-2-6

1-11-12

1-6-4



0-2-10

0-5-8

Scale = 1:37.5

0-2-10

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.88	Vert(LL)	-0.05	5-6	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.29	Vert(CT)	-0.09	5-6	>803	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.27	Horz(CT)	0.01	5	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.00	7	>999	240		
BCDL	7.0										Weight: 37 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud
OTHERS 2x8 DF 2250F 1.6E or 2x8 DF SS

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins: 3-4.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 5=278/ Mechanical, 11=471/0-5-4, (min. 0-1-8)
Max Horiz 11=44 (LC 9)
Max Uplift 5=-48 (LC 9), 11=-111 (LC 8)
Max Grav 5=676 (LC 2), 11=1152 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
BOT CHORD 5-6=-170/616
WEBS 3-6=-635/220, 3-5=-751/236

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) All plates are MT20 plates unless otherwise indicated.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Refer to girder(s) for truss to truss connections.
9) Bearing at joint(s) 11 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 48 lb uplift at joint 5 and 111 lb uplift at joint 11.
11) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
12) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD14	Jack-Closed	1	1	Job Reference (optional)




22-11-8 22-1-14

2-2-6

1-11-12

1-6-4



0-2-10

0-5-8

Scale = 1:37.5

0-2-10

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.65	Vert(LL)	-0.05	5-6	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.29	Vert(CT)	-0.09	5-6	>802	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.27	Horz(CT)	0.00	5	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.00	7	>999	240		
BCDL	7.0										Weight: 37 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2 *Except* T2:2x4 DF 2100F 1.8E
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud
OTHERS 2x8 DF 2250F 1.6E or 2x8 DF SS

REACTIONS (lb/size) 5=278/ Mechanical, 11=471/0-5-4, (min. 0-1-8)
Max Horiz 11=42 (LC 9)
Max Uplift 5=-48 (LC 9), 11=-111 (LC 8)
Max Grav 5=676 (LC 2), 11=1152 (LC 2)

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins: 3-4.
BOT CHORD Rigid ceiling directly applied.


MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 4-5=-432/140
BOT CHORD 5-6=-168/632
WEBS 3-6=-751/252, 3-5=-665/200, 6-11=-125/471, 2-11=-125/471

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) All plates are MT20 plates unless otherwise indicated.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Refer to girder(s) for truss to truss connections.
9) Bearing at joint(s) 11 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 48 lb uplift at joint 5 and 111 lb uplift at joint 11.
11) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
12) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD15	Half Hip	1	1	Job Reference (optional)





Scale = 1:48.5

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.31	Vert(LL)	-0.02	6-7	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.25	Vert(CT)	-0.03	6-7	>999	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.28	Horz(CT)	0.00	6	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.00	6-7	>999	240		
BCDL	7.0										Weight: 38 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud
OTHERS 2x8 DF 2250F 1.6E or 2x8 DF SS

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 3-5.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 6=278/ Mechanical, 13=471/0-5-4, (min. 0-1-8)
Max Horiz 13=41 (LC 9)
Max Uplift 6=-48 (LC 9), 13=-111 (LC 8)
Max Grav 6=676 (LC 2), 13=1152 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-321/70
BOT CHORD 7-8=-20/279, 6-7=-234/874
WEBS 3-7=-51/350, 3-8=-687/156, 4-7=-619/232, 4-6=-968/283, 8-13=-173/616, 2-13=-173/616

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) All plates are MT20 plates unless otherwise indicated.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Refer to girder(s) for truss to truss connections.
9) Bearing at joint(s) 13 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 48 lb uplift at joint 6 and 111 lb uplift at joint 13.
11) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
12) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD16	Flat	1	1	Job Reference (optional)



Scale = 1:23.4

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.22	Vert(LL)	n/a	-	n/a	999	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.04	Vert(CT)	n/a	-	n/a	999		
TCDL	12.0	Rep Stress Incr	YES	WB	0.17	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 11 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD 2-0-0 oc purlins: 1-2, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 2=0/ Mechanical, 3=188/ Mechanical
Max Horiz 2=374 (LC 2), 3=-374 (LC 2)
Max Uplift 3=-64 (LC 8)
Max Grav 3=456 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-443/179
BOT CHORD 3-4=-374/151
WEBS 2-4=-192/438

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Refer to girder(s) for truss to truss connections.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 64 lb uplift at joint 3.
10) Non Standard bearing condition. Review required.
11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
12) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD17	Monopitch	22	1	Job Reference (optional)



Scale = 1:23.5

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.29	Vert(LL)	n/a	-	n/a	999	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.03	Vert(CT)	n/a	-	n/a	999		
TCDL	12.0	Rep Stress Incr	YES	WB	0.10	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 11 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

REACTIONS (lb/size) 2=0/ Mechanical, 3=188/ Mechanical
Max Horiz 2=361 (LC 2), 3=-361 (LC 2)
Max Uplift 3=-64 (LC 8)
Max Grav 3=456 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-170/365
WEBS 1-3=-423/185

BRACING
TOP CHORD Structural wood sheathing directly applied or 2-2-8 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.


MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Refer to girder(s) for truss to truss connections.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 64 lb uplift at joint 3.
10) Non Standard bearing condition. Review required.
11) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD18	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:47 Page: 1
ID:3FKmhBAHj1XHOV3uzIkYM0zhUQy-ZKBTXoEvhb_6ow46K3nKlw?7W7rCQi2hmmHYCZzUlfM



Scale = 1:31.4

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.59	Vert(LL)	n/a	-	n/a	999	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.06	Vert(CT)	n/a	-	n/a	999		
TCDL	12.0	Rep Stress Incr	YES	WB	0.20	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 14 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 3-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 2=0/ Mechanical, 3=265/ Mechanical
Max Horiz 2=721 (LC 2), 3=-721 (LC 2)
Max Uplift 3=-91 (LC 8)
Max Grav 3=644 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-328/725, 2-3=-314/116
WEBS 1-3=-786/344

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Refer to girder(s) for truss to truss connections.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 91 lb uplift at joint 3.
10) Non Standard bearing condition. Review required.
11) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD19	Common	5	2	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:47 Page: 1
ID:Fj73q0LV6XdfvFOLbSS3FGzhUPS-ZKBTXoEvhb_6ow46K3nKlw?3u7i6QY3hmmHYCZzUlfM



Scale = 1:64.9

Plate Offsets (X, Y): [3:0-2-4,0-2-0], [5:0-3-8,0-2-8], [9:0-5-8,0-3-0], [11:0-3-8,0-1-8], [13:0-5-12,0-2-0], [15:0-2-4,0-2-0], [17:0-2-8,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.89	Vert(LL)	-0.26	16-17	>795	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.64	Vert(CT)	-0.30	16-17	>677	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.84	Horz(CT)	0.03	15	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.04	16-17	>999	240		
BCDL	7.0										Weight: 307 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2 *Except* T2:2x4 DF 2100F 1.8E
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W8:2x4 DF No.2
OTHERS 2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 3-15

REACTIONS (lb/size) 15=2103/0-5-8, (min. 0-2-12), 18=644/ Mechanical, 20=646/0-2-8, (min. 0-1-8)
Max Horiz 18=34 (LC 9)
Max Uplift 15=-268 (LC 12), 18=-122 (LC 8), 20=-121 (LC 13)
Max Grav 15=5106 (LC 2), 18=1705 (LC 30), 20=1706 (LC 31)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-18=-1619/196, 1-21=-4829/483, 2-21=-4810/484, 2-3=-2993/849, 3-4=-528/4709, 4-5=-527/4723, 5-6=-1779/979, 6-7=-1789/973, 7-8=-4402/434, 8-9=-3969/426
BOT CHORD 17-18=-28/545, 16-17=-464/4855, 15-16=-847/2981, 14-15=-4708/563, 13-14=-4708/563, 12-13=-397/4391, 11-12=-393/3959, 10-11=-56/658
WEBS 6-13=-811/123, 9-11=-359/3480, 7-13=-3095/362, 8-12=-379/456, 8-11=-1109/149, 5-15=-3264/416, 5-13=-653/5702, 1-17=-439/4356, 2-17=-841/131, 2-16=-2461/284, 3-16=-26/593, 3-15=-6753/774, 9-20=-2167/240

NOTES
1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Unbalanced roof live loads have been considered for this design.
4) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 30-9-2, Corner (3) 30-9-2 to 34-9-2 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
5) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
6) Provide adequate drainage to prevent water ponding.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Refer to girder(s) for truss to truss connections.
10) Bearing at joint(s) 20 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
11) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 20.
12) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 122 lb uplift at joint 18, 268 lb uplift at joint 15 and 121 lb uplift at joint 20.

Continued on page 2


Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD19	Common	5	**2**	Job Reference (optional)

13) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD20	Half Hip	3	2	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:48 Page: 1
ID:7lz?Jh6CeOxOKBFItz2Eu3zhUKa-2WIrl8EXSu7zP4flumlZI8XlpW1m9_0q?Q15k?zUlfL



Scale = 1:35.7

Plate Offsets (X, Y): [10:0-3-8,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.62	Vert(LL)	-0.24	8-10	>905	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.68	Vert(CT)	-0.28	8-10	>757	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.92	Horz(CT)	0.03	6	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.05	8-10	>999	240		
BCDL	7.0										Weight: 162 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W1:2x4 DF No.2
OTHERS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 4-5.
BOT CHORD Rigid ceiling directly applied.

REACTIONS (lb/size) 6=874/0-5-8, (min. 0-1-8), 13=842/0-2-8, (min. 0-1-8)
Max Horiz 13=52 (LC 11)
Max Uplift 6=-152 (LC 8), 13=-145 (LC 8)
Max Grav 6=2122 (LC 2), 13=2045 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-5469/1076, 2-3=-6164/1211, 3-4=-3404/677, 5-6=-353/68
BOT CHORD 10-11=-156/852, 9-10=-1032/5457, 8-9=-1032/5457, 7-8=-1161/6152, 6-7=-607/3305
WEBS 4-6=-3675/709, 4-7=-155/975, 3-7=-2915/571, 2-10=-1311/293, 1-10=-911/4787, 2-8=-135/726, 1-13=-2604/504

NOTES
1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Unbalanced roof live loads have been considered for this design.
4) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
5) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
6) Provide adequate drainage to prevent water ponding.
7) All plates are MT20 plates unless otherwise indicated.
8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
10) Bearing at joint(s) 13 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
11) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 13.
12) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 152 lb uplift at joint 6 and 145 lb uplift at joint 13.
13) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
14) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.


Continued on page 2


Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD20	Half Hip	3	**2**	Job Reference (optional)

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD21	Monopitch	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:48 Page: 1
ID:uqWu72dZlIDRNeSNLoo4bwzhUJw-2Wlrl8EXSu7zP4flumlZI8XDIW?Q9?Nq?Q15k?zUlfL





Scale = 1:44.4

Plate Offsets (X, Y): [4:0-5-0,0-1-8], [7:0-3-8,0-1-8], [8:0-3-7,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.91	Vert(LL)	-0.26	10-11	>703	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.83	Vert(CT)	-0.32	10-11	>581	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.83	Horz(CT)	0.03	9	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.05	10-11	>999	240		
BCDL	7.0										Weight: 109 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2 *Except* T1:2x4 DF 2100F 1.8E
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W13:2x4 DF No.2, W8:2x4 DF 2100F 1.8E
OTHERS 2x6 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 7-9

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 9=654/0-5-8, (min. 0-1-11), 13=1383/0-5-8, (min. 0-3-9), 17=343/0-4-0, (min. 0-1-8)
Max Horiz 17=56 (LC 9)
Max Uplift 9=-114 (LC 8), 13=-238 (LC 12), 17=-89 (LC 8)
Max Grav 9=1588 (LC 2), 13=3357 (LC 2), 17=851 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-307/2055, 4-22=-2877/486, 22-23=-2864/486, 5-23=-2862/487, 5-6=-3449/571, 6-7=-3438/572, 7-8=-257/66, 8-9=-536/103
BOT CHORD 12-13=-2042/346, 11-12=-2042/346, 10-11=-441/2864, 9-10=-520/3437
WEBS 4-13=-2518/439, 3-13=-2055/363, 7-9=-3342/536, 5-11=-1278/239, 5-10=-83/596, 4-11=-814/5078, 2-17=-96/454


NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 12-1-12, Exterior (2) 12-1-12 to 12-6-8, Corner (3) 12-6-8 to 24-6-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) All plates are MT20 plates unless otherwise indicated.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Bearing at joint(s) 17 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 114 lb uplift at joint 9, 238 lb uplift at joint 13 and 89 lb uplift at joint 17.
10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD22	Monopitch	4	2	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:48 Page: 1
ID:nyOXpUiNneRpYKmU2_vyihzhUIX-2Wlrl8EXSu7zP4flumlZI8XEvWzw9?Sq?Q15k?zUlfL





Scale = 1:44.4

Plate Offsets (X, Y): [6:0-1-12,Edge], [7:0-3-8,0-1-8], [12:0-4-4,Edge], [13:0-3-8,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.87	Vert(LL)	-0.56	11-12	>491	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.92	Vert(CT)	-0.67	11-12	>411	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.89	Horz(CT)	0.05	9	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.11	11-12	>999	240		
BCDL	7.0										Weight: 222 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2 *Except* B3:2x4 DF 2100F 1.8E
WEBS 2x4 DF Stud *Except* W4:2x4 DF No.2
OTHERS 2x6 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

REACTIONS (lb/size) 9=1111/0-5-8, (min. 0-1-8), 18=1269/0-4-0, (min. 0-1-8)
Max Horiz 18=32 (LC 9)
Max Uplift 9=-193 (LC 12), 18=-246 (LC 8)
Max Grav 9=2699 (LC 2), 18=3097 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-577/57, 3-4=-7875/1214, 4-5=-10472/1622, 5-23=-9822/1527, 23-24=-9815/1527, 6-24=-9811/1528, 6-7=-6311/987
BOT CHORD 14-15=-734/4723, 13-14=-734/4723, 12-13=-1236/7871, 11-12=-1686/10691, 10-11=-1535/9732, 9-10=-994/6301
WEBS 8-9=-423/82, 7-9=-6683/1054, 4-13=-1687/295, 4-12=-423/2718, 5-12=-828/169, 5-11=-925/154, 6-11=-20/356, 6-10=-3647/576, 7-10=-162/1288, 3-13=-575/3609, 3-15=-4758/747, 2-18=-1002/164, 15-18=-365/2376, 2-18=-365/2376

NOTES
1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-6-0 oc.
Bottom chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Web connected as follows: 2x4 - 2 rows staggered at 0-5-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Unbalanced roof live loads have been considered for this design.
4) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 12-1-12, Exterior (2) 12-1-12 to 12-6-8, Corner (3) 12-6-8 to 24-6-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
5) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
6) Provide adequate drainage to prevent water ponding.
7) All plates are MT20 plates unless otherwise indicated.
8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
10) Bearing at joint(s) 18 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
11) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 193 lb uplift at joint 9 and 246 lb uplift at joint 18.
12) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD23	Half Hip	4	2	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:48 Page: 1
ID:r4c_9_q8bmE6sBG591q4p2zhXT4-2Wlrl8EXSu7zP4flumIZI8XEkW1i9?Vq?Q15k?zUlfL



Scale = 1:43.9

Plate Offsets (X, Y): [2:0-3-4,0-3-0], [8:0-8-12,0-3-0], [9:Edge,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.88	Vert(LL)	-0.57	12-13	>477	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.68	Vert(CT)	-0.68	12-13	>400	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.89	Horz(CT)	0.05	10	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.11	12-13	>999	240		
BCDL	7.0										Weight: 231 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2 *Except* T3:2x6 DF No.2
BOT CHORD 2x4 DF 2100F 1.8E *Except* B1:2x4 DF No.2
WEBS 2x4 DF Stud *Except* W4:2x4 DF No.2
OTHERS 2x6 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 8-9.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 8-10

REACTIONS (lb/size) 10=1111/0-5-8, (min. 0-1-8), 20=1269/0-4-0, (min. 0-1-8)
Max Horiz 20=55 (LC 9)
Max Uplift 10=-192 (LC 8), 20=-246 (LC 8)
Max Grav 10=2699 (LC 2), 20=3097 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-539/96, 3-4=-7561/1199, 4-5=-7569/1203, 5-6=-10477/1664, 6-25=-10467/1664, 7-25=-10467/1664, 7-8=-10303/1644, 8-9=-421/91, 9-10=-698/134
BOT CHORD 16-17=-686/4562, 15-16=-686/4562, 14-15=-1616/10465, 13-14=-1616/10465, 12-13=-1591/10291, 11-12=-1143/7447, 10-11=-1138/7446
WEBS 8-10=-7282/1143, 8-12=-480/3047, 4-15=-783/153, 5-15=-3061/481, 7-13=-335/184, 7-12=-999/189, 3-15=-555/3511, 3-17=-4666/727, 2-20=-1406/225, 17-20=-367/2410, 2-20=-367/2410


NOTES
1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-6-0 oc, 2x6 - 2 rows staggered at 0-9-0 oc.
Bottom chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-2-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Unbalanced roof live loads have been considered for this design.
4) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 12-1-12, Exterior (2) 12-1-12 to 12-6-8, Corner (3) 12-6-8 to 24-6-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
5) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
6) Provide adequate drainage to prevent water ponding.
7) All plates are MT20 plates unless otherwise indicated.
8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
10) Bearing at joint(s) 20 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
11) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 192 lb uplift at joint 10 and 246 lb uplift at joint 20.
12) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

Continued on page 2

13) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD24	Monopitch	2	1	Job Reference (optional)




22-11-8 23-1-14

2-2-6

1-11-12

1-6-6

1-6-4 9-3-2



0-2-10 0-3-8

0-0-2

0-5-6

0-2-10

Scale = 1:42.3

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.67	Vert(LL)	-0.06	5-6	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.37	Vert(CT)	-0.11	5-6	>842	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.50	Horz(CT)	0.01	17	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.00	5	>999	240		
BCDL	7.0										Weight: 41 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W7:2x4 DF No.2
OTHERS 2x8 DF 2250F 1.6E or 2x8 DF SS *Except* BL2:2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 12=530/0-5-4, (min. 0-1-8), 17=314/0-2-8, (min. 0-1-8)
Max Horiz 12=37 (LC 9)
Max Uplift 12=-120 (LC 8), 17=-55 (LC 12)
Max Grav 12=1296 (LC 2), 17=762 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-411/93, 5-17=-59/308, 4-17=-59/308
BOT CHORD 5-6=-335/1233
WEBS 3-6=-1278/379, 3-5=-869/281, 6-12=-156/628, 2-12=-156/628, 4-17=-1048/280

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) All plates are MT20 plates unless otherwise indicated.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Bearing at joint(s) 12, 17 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
9) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 17.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 120 lb uplift at joint 12 and 55 lb uplift at joint 17.
11) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD25	Monopitch	6	1	Job Reference (optional)





Scale = 1:28.9

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.80	Vert(LL)	-0.05	4-5	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.37	Vert(CT)	-0.08	4-5	>999	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.54	Horz(CT)	0.02	8	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.00	4	>999	240		
BCDL	7.0										Weight: 40 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W5:2x4 DF No.2
OTHERS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 5=535/0-5-8, (min. 0-1-8), 8=315/0-2-8, (min. 0-1-8)
Max Horiz 5=37 (LC 9)
Max Uplift 5=-123 (LC 8), 8=-54 (LC 12)
Max Grav 5=1299 (LC 2), 8=766 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-185/415, 2-3=-372/85, 4-8=-70/355, 3-8=-70/355
BOT CHORD 4-5=-355/1368
WEBS 1-5=-762/307, 2-5=-1932/608, 2-4=-1051/311, 3-8=-1030/270

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Bearing at joint(s) 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
8) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 8.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 123 lb uplift at joint 5 and 54 lb uplift at joint 8.
10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD26	Monopitch	8	1	Job Reference (optional)



23-1-6 22-9-12

1-11-12 9-3-7



Scale = 1:29.1

0-5-8 0-3-8

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.55	Vert(LL)	-0.03	6-7	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.38	Vert(CT)	-0.04	6-7	>999	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.68	Horz(CT)	0.01	16	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.01	6	>999	240		
BCDL	7.0										Weight: 43 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud
OTHERS 2x6 DF No.2 *Except* BL2:2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 10=526/0-4-0, (min. 0-1-8), 16=316/0-3-0, (min. 0-1-8)
Max Horiz 10=32 (LC 9)
Max Uplift 10=-119 (LC 8), 16=-56 (LC 12)
Max Grav 10=1293 (LC 2), 16=768 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-333/87, 5-16=-93/414, 4-16=-93/414
BOT CHORD 6-7=-315/1270, 5-6=-315/1270
WEBS 3-7=-1188/308, 3-5=-1011/261, 7-10=-106/458, 2-10=-106/458, 4-16=-853/225

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Bearing at joint(s) 10, 16 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
8) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 16.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 119 lb uplift at joint 10 and 56 lb uplift at joint 16.
10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FJ1	Half Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:49 Page: 1
ID:4ZVN2ccaz8zQjKQJp1cKvYzcYWx-WiJDyUF9DCFq1EEUSUpoqL4P_wWkucz_D4mfHSzUlfK



Scale = 1:26.3

0-2-12

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.85	Vert(LL)	-0.01	4-5	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.12	Vert(CT)	-0.02	4-5	>999	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.24	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.00	4-5	>999	240		
BCDL	7.0										Weight: 39 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2 *Except* T2:2x4 DF 2100F 1.8E
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

REACTIONS (lb/size) 4=238/ Mechanical, 6=518/0-5-8, (min. 0-1-8)
Max Horiz 6=59 (LC 9)
Max Uplift 4=-51 (LC 9), 6=-139 (LC 8)
Max Grav 4=578 (LC 2), 6=1257 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-178/450, 3-4=-488/158
WEBS 1-6=-575/208, 2-6=-1023/305

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins: 2-3.
BOT CHORD Rigid ceiling directly applied.


MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 139 lb uplift at joint 6 and 51 lb uplift at joint 4.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard


Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FJ2	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:49 Page: 1
ID:4ZVN2ccaz8zQjKQJp1cKvYzcYWx-WiJDyUF9DCFq1EEUSUpoqL4S4wVbudF_D4mfHSzUlfK



22-1-14 22-1-14

2-2-12



Scale = 1:30.4

0-2-12

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.65	Vert(LL)	-0.03	5-6	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.19	Vert(CT)	-0.05	5-6	>999	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.15	Horz(CT)	0.00	5	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.00	5-6	>999	240		
BCDL	7.0										Weight: 39 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2 *Except* T2:2x4 DF 2100F 1.8E
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

REACTIONS (lb/size) 5=238/ Mechanical, 6=518/0-5-8, (min. 0-1-8)
Max Horiz 6=60 (LC 9)
Max Uplift 5=-51 (LC 9), 6=-139 (LC 8)
Max Grav 5=578 (LC 2), 6=1257 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 4-5=-432/140
WEBS 1-6=-265/131, 3-5=-271/48, 2-6=-551/181, 3-6=-641/244

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins: 3-4.
BOT CHORD Rigid ceiling directly applied.


MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 51 lb uplift at joint 5 and 139 lb uplift at joint 6.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FJ3	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:50 Page: 1
ID:4ZVN2ccaz8zQjKQJp1cKvYzcYWx-_vtbAqGn_WNhfOpg0BL1NYddtKrpd3r7SkWCpuzUlfJ



Scale = 1:30.5

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.59	Vert(LL)	-0.03	5-6	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.19	Vert(CT)	-0.05	5-6	>999	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.20	Horz(CT)	0.00	5	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.00	5-6	>999	240		
BCDL	7.0										Weight: 39 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins: 3-4.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 5=238/ Mechanical, 6=518/0-5-8, (min. 0-1-8)
Max Horiz 6=62 (LC 9)
Max Uplift 5=-51 (LC 9), 6=-138 (LC 8)
Max Grav 5=578 (LC 2), 6=1257 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
BOT CHORD 5-6=-57/342
WEBS 3-5=-481/121, 2-6=-879/287, 3-6=-490/217

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 51 lb uplift at joint 5 and 138 lb uplift at joint 6.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FJ4	Jack-Closed	12	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:50 Page: 1
ID:4ZVN2ccaz8zQjKQJp1cKvYzcYWx-_vtbAqGn_WNhfOpg0BL1NYdhXKqnd3W7SkWCpuzUlfJ



Scale = 1:29.9

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.35	Vert(LL)	-0.03	5-6	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.19	Vert(CT)	-0.05	5-6	>999	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.22	Horz(CT)	0.00	5	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.00	5-6	>999	240		
BCDL	7.0										Weight: 39 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 5=238/ Mechanical, 6=518/0-5-8, (min. 0-1-8)
Max Horiz 6=61 (LC 9)
Max Uplift 5=-27 (LC 8), 6=-138 (LC 8)
Max Grav 5=578 (LC 2), 6=1257 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 4-5=-254/82
BOT CHORD 5-6=-77/453
WEBS 2-6=-605/197, 3-5=-539/132, 3-6=-764/294

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 138 lb uplift at joint 6 and 27 lb uplift at joint 5.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FJ5	Jack-Closed	2	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:50 Page: 1
ID:4ZVN2ccaz8zQjKQJp1cKvYzcYWx-_vtbAqGn_WNhfOpg0BL1NYdeqKskd3m7SkWCpuzUIfJ



Scale = 1:29.9

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.53	Vert(LL)	0.00	4-5	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.07	Vert(CT)	-0.01	4-5	>999	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.20	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.00	4-5	>999	240		
BCDL	7.0										Weight: 30 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 4=113/ Mechanical, 5=438/0-5-8, (min. 0-1-8)
Max Horiz 5=60 (LC 9)
Max Uplift 4=-18 (LC 9), 5=-133 (LC 8)
Max Grav 4=275 (LC 2), 5=1063 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-321/114
WEBS 2-5=-899/357

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 133 lb uplift at joint 5 and 18 lb uplift at joint 4.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FJ6	Jack-Closed	2	1	Job Reference (optional)



Scale = 1:29.9

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.25	Vert(LL)	0.00	4-5	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.05	Vert(CT)	0.00	4-5	>999	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.17	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP		Wind(LL)	0.00	4-5	>999	240		
BCDL	7.0										Weight: 22 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 3-10-15 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=-63/ Mechanical, 5=418/0-5-8, (min. 0-1-8)
Max Horiz 5=59 (LC 9)
Max Uplift 4=-153 (LC 2), 5=-160 (LC 8)
Max Grav 4=64 (LC 8), 5=1015 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 1-5=-286/125, 2-5=-782/359, 2-4=-214/335

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 160 lb uplift at joint 5 and 153 lb uplift at joint 4.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FJ7	Jack-Closed	2	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:50 Page: 1
ID:4ZVN2ccaz8zQjKQJp1cKvYzcYWx-_vtbAqGn_WNhfOpg0BL1NYdkBKtVd6y7SkWCpuzUlfJ



Scale = 1:24.5

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.18	Vert(LL)	n/a	-	n/a	999	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.02	Vert(CT)	n/a	-	n/a	999		
TCDL	12.0	Rep Stress Incr	YES	WB	0.06	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 12 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 1-10-15 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 2=0/ Mechanical, 3=159/ Mechanical
Max Horiz 2=179 (LC 2), 3=-179 (LC 2)
Max Uplift 3=-54 (LC 8)
Max Grav 3=386 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 1-3=-260/114

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Refer to girder(s) for truss to truss connections.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 54 lb uplift at joint 3.
10) Non Standard bearing condition. Review required.
11) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FJ8	Diagonal Hip Girder	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:38:51 Page: 1
ID:4ZVN2ccaz8zQjKQJp1cKvYzcYWx-S5R_NAHPlpVYGXNtZusGwm9mIk1HLOnHhOFmLKzUlfI



Scale = 1:35

Plate Offsets (X, Y): [2:0-3-8,0-1-8], [4:0-0-8,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.74	Vert(LL)	-0.09	5-6	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.82	Vert(CT)	-0.10	5-6	>927	240		
TCDL	12.0	Rep Stress Incr	NO	WB	0.73	Horz(CT)	0.00	5	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MSH		Wind(LL)	-0.02	6-7	>999	240		
BCDL	7.0										Weight: 53 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF 2100F 1.8E
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 4-11-9 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 5=441/ Mechanical, 7=1020/0-7-12, (min. 0-2-13)
Max Horiz 7=54 (LC 7)
Max Uplift 5=-104 (LC 10), 7=-376 (LC 6)
Max Grav 5=1143 (LC 2), 7=2621 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-91/455, 2-3=-1309/198, 4-5=-411/24
BOT CHORD 7-10=-449/115, 6-10=-449/115, 6-11=-176/1302, 5-11=-176/1302
WEBS 1-7=-552/99, 2-7=-1641/198, 2-6=-254/1892, 3-6=-690/151, 3-5=-1273/199

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 376 lb uplift at joint 7 and 104 lb uplift at joint 5.
9) Use Simpson Strong-Tie SUL24 (4-10dx1 1/2 Girder, 4-10dx1 1/2 Truss, Single Ply Girder) or equivalent spaced at 5-7-14 oc max. starting at 2-9-8 from the left end to 8-5-6 to connect truss(es) FJ7 (1 ply 2x4 DF), FJ5 (1 ply 2x4 DF) to front face of bottom chord.
10) Use Simpson Strong-Tie SUR24 (4-10dx1 1/2 Girder, 4-10dx1 1/2 Truss, Single Ply Girder) or equivalent at 2-9-8 from the left end to connect truss(es) FJ7 (1 ply 2x4 DF) to back face of bottom chord, skewed 45.0 deg.to the right, sloping 0.0 deg. down.
11) Use Simpson Strong-Tie SUR24 (4-10dx1 1/2 Girder, 4-10dx1 1/2 Truss, Single Ply Girder) or equivalent at 8-5-6 from the left end to connect truss(es) FJ5 (1 ply 2x4 DF) to back face of bottom chord, skewed 45.0 deg.to the right, sloping 0.0 deg. down.
12) Fill all nail holes where hanger is in contact with lumber.
13) "NAILED" indicates Girder: 3-10d (0.148" x 3") toe-nails per NDS guidelines.
14) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).


LOAD CASE(S) Standard
1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-4=-84, 5-8=-14

Continued on page 2

Concentrated Loads (lb)

Vert: 7=-278 (F=-139, B=-139), 10=72 (F=36, B=36), 11=-187 (F=-93, B=-93)

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FJ9	Monopitch	19	1	Job Reference (optional)



Scale = 1:25.2

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.21	Vert(LL)	n/a	-	n/a	999	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.02	Vert(CT)	n/a	-	n/a	999		
TCDL	12.0	Rep Stress Incr	YES	WB	0.07	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 12 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 2-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 2=0/ Mechanical, 3=167/ Mechanical
Max Horiz 2=198 (LC 2), 3=-198 (LC 2)
Max Uplift 3=-57 (LC 8)
Max Grav 3=406 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 1-3=-281/123

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Refer to girder(s) for truss to truss connections.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 57 lb uplift at joint 3.
10) Non Standard bearing condition. Review required.
11) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.

LOAD CASE(S) Standard