

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FA1	Floor	2	1	Job Reference (optional)





Scale = 1:44.4

Plate Offsets (X, Y): [1:Edge,0-1-8], [6:0-1-8,Edge], [14:0-1-8,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.73	Vert(LL)	-0.20	14-15	>999	360	MT20	220/195
TCDL	11.0	Lumber DOL	1.00	BC	0.81	Vert(CT)	-0.26	14-15	>787	240		
BCLL	0.0	Rep Stress Incr	YES	WB	0.42	Horz(CT)	0.04	11	n/a	n/a		
BCDL	7.0	Code	IRC2021/TPI2014	Matrix-AS							Weight: 90 lb	FT = 20%F, 11%E

LUMBER
TOP CHORD 2x4 DF No.2(flat)
BOT CHORD 2x4 DF No.2(flat)
WEBS 2x4 DF Stud(flat)

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

REACTIONS (lb/size) 11=1008/0-5-8, (min. 0-1-8), 17=1008/ Mechanical


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1942/0, 3-4=-1942/0, 4-5=-2294/0, 5-6=-2294/0, 6-7=-1769/0, 7-8=-1769/0, 8-9=-1769/0
BOT CHORD 16-17=0/1171, 15-16=0/1171, 14-15=0/2289, 13-14=0/2294, 12-13=0/2294, 11-12=0/910
WEBS 2-17=-1464/0, 2-15=0/972, 4-15=-438/0, 4-14=-232/356, 6-12=-782/0, 7-12=-284/31, 9-12=0/1083, 9-11=-1289/0

NOTES
1) Unbalanced floor live loads have been considered for this design.
2) Refer to girder(s) for truss to truss connections.
3) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
4) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FA2	Floor	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:22 Page: 1
ID:DO0SOwskBCShUJeoNzrXFDzhXzI-0wkfaIcKcQ6N3z2CONbwcJ7EGuWKEjQeboBqQYzcW1t



Scale = 1:65

Plate Offsets (X, Y): [6:0-1-8,Edge], [14:Edge,0-1-8], [17:0-1-8,Edge], [20:0-1-8,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.75	Vert(LL)	-0.20	20-22	>999	360	MT20	220/195
TCDL	11.0	Lumber DOL	1.00	BC	0.84	Vert(CT)	-0.27	20-22	>756	240		
BCLL	0.0	Rep Stress Incr	YES	WB	0.43	Horz(CT)	0.04	17	n/a	n/a		
BCDL	7.0	Code	IRC2021/TPI2014	Matrix-AS							Weight: 106 lb	FT = 20%F, 11%E

LUMBER
TOP CHORD 2x4 DF No.2(flat)
BOT CHORD 2x4 DF No.2(flat)
WEBS 2x4 DF Stud(flat)
OTHERS 2x4 DF Stud(flat)

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

REACTIONS All bearings 3-2-4. except 23= Mechanical
(lb) - Max Uplift All uplift 100 (lb) or less at joint(s) 14
Max Grav All reactions 250 (lb) or less at joint(s) 14, 15, 16 except
17=1107 (LC 1), 23=985 (LC 1)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1882/0, 3-4=-1882/0, 4-5=-2178/0, 5-6=-2178/0, 6-7=-1602/0, 7-8=-1602/0
BOT CHORD 22-23=0/1141, 21-22=0/2198, 20-21=0/2198, 19-20=0/2178, 18-19=0/2178, 17-18=0/726
WEBS 2-23=-1427/0, 2-22=0/935, 4-22=-398/0, 4-20=-258/314, 6-18=-823/0, 7-18=-286/34, 8-18=0/1105, 8-17=-1146/0


NOTES
1) Unbalanced floor live loads have been considered for this design.
2) All plates are 1.5x4 (||) MT20 unless otherwise indicated.
3) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
4) Gable studs spaced at 1-4-0 oc.
5) Refer to girder(s) for truss to truss connections.
6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 14.
7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
8) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
9) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FA3	Floor	5	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:23 Page: 1
ID:DO0SOwskBCShUJeoNzrXFDzhXzI-U6I1necyNkEEg7dPy5699WgN?Irsz9yoqSxNy?zcW1s





Scale = 1:50.9

Plate Offsets (X, Y): [6:0-1-8,Edge], [10:0-1-8,Edge], [13:0-1-8,Edge], [16:0-1-8,Edge], [20:0-1-8,0-0-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.88	Vert(LL)	-0.24	14-15	>999	360	M18AHS	169/162
TCDL	11.0	Lumber DOL	1.00	BC	0.95	Vert(CT)	-0.32	14-15	>754	240	MT20	220/195
BCLL	0.0	Rep Stress Incr	YES	WB	0.47	Horz(CT)	0.06	12	n/a	n/a		
BCDL	7.0	Code	IRC2021/TPI2014	Matrix-AS							Weight: 106 lb	FT = 20%F, 11%E

LUMBER

TOP CHORD	2x4 DF No.2(flat)
BOT CHORD	2x4 DF No.2(flat)
WEBS	2x4 DF Stud(flat)
OTHERS	2x4 DF Stud(flat)

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.

REACTIONS (lb/size) 12=1156/0-5-8, (min. 0-1-8), 19=1162/ Mechanical

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


TOP CHORD	2-3=-2344/0, 3-4=-2344/0, 4-5=-3080/0, 5-6=-3080/0, 6-7=-2864/0, 7-8=-2864/0, 8-9=-1203/0, 9-10=-1203/0
BOT CHORD	18-19=0/1373, 17-18=0/2907, 16-17=0/2907, 15-16=0/3080, 14-15=0/3080, 13-14=0/2188, 12-13=0/1203
WEBS	5-16=-419/14, 6-14=-578/83, 7-14=-331/0, 8-14=0/852, 8-13=-1243/0, 10-13=0/814, 10-12=-1609/0, 2-19=-1716/0, 2-18=0/1226, 3-18=-253/0, 4-18=-710/0, 4-16=-50/650


NOTES

1) Unbalanced floor live loads have been considered for this design.
2) All plates are MT20 plates unless otherwise indicated.
3) Refer to girder(s) for truss to truss connections.
4) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
5) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
6) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FA4	Floor	3	1	Job Reference (optional)





Scale = 1:50.9

Plate Offsets (X, Y): [1:Edge,0-1-8], [6:0-1-8,Edge], [10:0-1-8,Edge], [13:0-1-8,Edge], [16:0-1-8,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.90	Vert(LL)	-0.24	14-15	>999	360	M18AHS	169/162
TCDL	11.0	Lumber DOL	1.00	BC	0.96	Vert(CT)	-0.32	14-15	>744	240	MT20	220/195
BCLL	0.0	Rep Stress Incr	YES	WB	0.47	Horz(CT)	0.06	12	n/a	n/a		
BCDL	7.0	Code	IRC2021/TPI2014	Matrix-AS							Weight: 104 lb	FT = 20%F, 11%E

LUMBER

TOP CHORD	2x4 DF No.2(flat)
BOT CHORD	2x4 DF No.2(flat)
WEBS	2x4 DF Stud(flat)

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.

REACTIONS (lb/size) 12=1166/0-5-8, (min. 0-1-8), 19=1166/ Mechanical

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


TOP CHORD	2-3=-2354/0, 3-4=-2354/0, 4-5=-3099/0, 5-6=-3099/0, 6-7=-2889/0, 7-8=-2889/0, 8-9=-1239/0, 9-10=-1239/0
BOT CHORD	18-19=0/1378, 17-18=0/2921, 16-17=0/2921, 15-16=0/3099, 14-15=0/3099, 13-14=0/2218, 12-13=0/1239
WEBS	5-16=-423/11, 6-14=-574/92, 7-14=-333/0, 8-14=0/847, 8-13=-1234/0, 10-13=0/809, 10-12=-1640/0, 2-19=-1722/0, 2-18=0/1231, 3-18=-253/0, 4-18=-716/0, 4-16=-46/657

NOTES

1) Unbalanced floor live loads have been considered for this design.
2) All plates are MT20 plates unless otherwise indicated.
3) Refer to girder(s) for truss to truss connections.
4) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
5) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FA5	Floor	7	1	Job Reference (optional)



Scale = 1:48.3

Plate Offsets (X, Y): [1:0-5-0,Edge], [6:0-1-8,Edge], [10:0-1-8,Edge], [13:0-4-0,Edge], [14:Edge,0-0-12], [16:0-1-8,Edge], [17:0-1-8,Edge], [22:Edge,0-0-12], [23:0-4-8,0-2-0], [25:0-3-12,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.77	Vert(LL)	-0.19	16-17	>999	360	MT20	220/195
TCDL	11.0	Lumber DOL	1.00	BC	0.91	Vert(CT)	-0.27	16-17	>841	240	M18AHS	169/162
BCLL	0.0	Rep Stress Incr	YES	WB	0.64	Horz(CT)	0.03	26	n/a	n/a		
BCDL	7.0	Code	IRC2021/TPI2014	Matrix-AS							Weight: 115 lb	FT = 20%F, 11%E

LUMBER

TOP CHORD	2x4 DF No.2(flat)
BOT CHORD	2x4 DF No.2(flat)
WEBS	2x4 DF Stud(flat)
OTHERS	2x4 DF Stud(flat)

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.

REACTIONS (lb/size) 25=1076/0-6-1, (min. 0-1-8), 26=1080/0-3-8, (min. 0-1-8)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-1417/0, 2-3=-1414/0, 3-4=-1414/0, 4-5=-2716/0, 5-6=-2716/0, 6-7=-2781/0, 7-8=-2781/0, 8-9=-1630/0, 9-10=-1630/0, 10-11=-1395/0, 11-12=-1395/0, 12-13=-1396/0

BOT CHORD 20-21=0/2236, 19-20=0/2236, 18-19=0/2781, 17-18=0/2781, 16-17=0/2372, 15-16=0/1630


WEBS 7-17=-278/0, 1-21=0/1578, 4-21=-1037/0, 4-19=0/606, 5-19=-293/95, 6-19=-523/250, 8-17=0/700, 8-16=-936/0, 10-16=0/630, 10-15=-798/0, 13-15=0/1661, 1-25=-1102/0, 13-26=-1110/0

NOTES

1) Unbalanced floor live loads have been considered for this design.
2) All plates are MT20 plates unless otherwise indicated.
3) All plates are 3x4 (=) MT20 unless otherwise indicated.
4) Bearing at joint(s) 25, 26 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
5) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
6) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FA6	Floor Supported Gable	1	1	Job Reference (optional)



Scale = 1:49.3

Plate Offsets (X, Y): [20:Edge,0-0-12], [36:Edge,0-0-12], [37:0-4-8,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.06	Vert(LL)	n/a	-	n/a	999	MT20	220/195
TCDL	11.0	Lumber DOL	1.00	BC	0.01	Vert(CT)	n/a	-	n/a	999		
BCLL	0.0	Rep Stress Incr	YES	WB	0.03	Horz(CT)	0.00	39	n/a	n/a		
BCDL	7.0	Code	IRC2021/TPI2014	Matrix-AS							Weight: 105 lb	FT = 20%F, 11%E

LUMBER

TOP CHORD	2x4 DF No.2(flat)
BOT CHORD	2x4 DF No.2(flat)
WEBS	2x4 DF Stud(flat)
OTHERS	2x4 DF Stud(flat)

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.

REACTIONS All bearings 19-5-1. except 39=0-3-8
(lb) - Max Uplift All uplift 100 (lb) or less at joint(s) 39
Max Grav All reactions 250 (lb) or less at joint(s) 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 34, 35, 36, 39

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


NOTES


1) All plates are 1.5x4 (||) MT20 unless otherwise indicated.
2) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
3) Gable studs spaced at 1-4-0 oc.
4) Bearing at joint(s) 39 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 39.
6) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
7) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FA7	Floor	7	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:24 Page: 1
ID:haarbGtMyWaX6SD_whMmnQzhXzH-zIsP?_da82M5lHCbVoeOhkChYiIjicNx26gxVRzcW1r





Scale = 1:41

Plate Offsets (X, Y): [8:0-1-8,Edge], [10:0-4-8,0-0-0], [12:0-1-8,Edge], [17:0-4-8,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.26	Vert(LL)	-0.06	13-14	>999	360	MT20	220/195
TCDL	11.0	Lumber DOL	1.00	BC	0.47	Vert(CT)	-0.11	13-14	>999	240		
BCLL	0.0	Rep Stress Incr	YES	WB	0.46	Horz(CT)	0.02	17	n/a	n/a		
BCDL	7.0	Code	IRC2021/TPI2014	Matrix-AS							Weight: 90 lb	FT = 20%F, 11%E

LUMBER

TOP CHORD	2x4 DF No.2(flat)
BOT CHORD	2x4 DF No.2(flat)
WEBS	2x4 DF Stud(flat)
OTHERS	2x4 DF Stud(flat)

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.

REACTIONS (lb/size) 15=956/0-5-8, (min. 0-1-8), 17=862/0-6-1, (min. 0-1-8)
Max Grav 15=956 (LC 1), 17=863 (LC 4)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	10-17=-847/0, 3-4=-1549/0, 4-5=-1549/0, 5-6=-1586/0, 6-7=-1586/0, 7-8=-1586/0, 8-9=-1028/0, 9-10=-1032/0
BOT CHORD	14-15=0/955, 13-14=0/1729, 12-13=0/1028
WEBS	3-15=-1205/0, 3-14=0/757, 6-13=-258/0, 8-13=0/698, 8-12=-641/0, 10-12=0/1196

NOTES


1) Unbalanced floor live loads have been considered for this design.
2) Bearing at joint(s) 17 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
3) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
4) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
5) CAUTION, Do not erect truss backwards.


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FA8	Floor	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:24 Page: 1

ID:haarbGtMyWaX6SD_whMmnQzhXzH-zIsP?_da82M5IHCbVoeOhkCbWiJnicjx26gxVRzcW1r





Scale = 1:48.2

0-2-12

Plate Offsets (X, Y): [1:Edge,0-0-12], [12:0-1-8,Edge], [15:0-1-8,Edge], [22:0-1-8,0-0-12], [23:0-1-8,0-0-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.64	Vert(LL)	-0.07	16-17	>999	360	MT20	220/195
TCDL	11.0	Lumber DOL	1.00	BC	0.40	Vert(CT)	-0.10	16-17	>999	240	M18AHS	169/162
BCLL	0.0	Rep Stress Incr	YES	WB	0.50	Horz(CT)	0.02	14	n/a	n/a		
BCDL	7.0	Code	IRC2021/TPI2014	Matrix-AS							Weight: 130 lb	FT = 20%F, 11%E

LUMBER

TOP CHORD	2x4 DF No.2(flat)
BOT CHORD	2x4 DF No.2(flat)
WEBS	2x4 DF Stud(flat)
OTHERS	2x4 DF Stud(flat)

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.

REACTIONS (lb/size) 14=617/0-5-8, (min. 0-1-8), 19=2236/0-5-8, (min. 0-1-8)
Max Uplift 14=-9 (LC 3)
Max Grav 14=817 (LC 4), 19=2236 (LC 1)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


TOP CHORD	2-3=0/695, 3-4=0/695, 4-5=0/2420, 5-6=0/2420, 6-7=0/2420, 7-8=-1154/1157, 8-9=-1154/1157, 9-10=-1560/349, 10-11=-1560/349, 11-12=-490/1
BOT CHORD	19-20=-1636/0, 18-19=-1756/380, 17-18=-1756/380, 16-17=-718/1520, 15-16=-138/1191, 14-15=-1/490
WEBS	2-20=-667/0, 4-20=0/1189, 4-19=-1225/0, 7-19=-1721/0, 7-17=0/1305, 9-17=-790/0, 9-16=0/465, 11-16=-265/465, 11-15=-885/173, 12-15=-46/599, 12-14=-945/2

NOTES

1) Unbalanced floor live loads have been considered for this design.
2) All plates are MT20 plates unless otherwise indicated.
3) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 9 lb uplift at joint 14.
4) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
5) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
6) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FA9	Floor	1	1	Job Reference (optional)





Scale = 1:48.5

Plate Offsets (X, Y): [1:Edge,0-0-12], [3:0-1-8,Edge], [11:0-1-8,Edge], [14:0-1-8,Edge], [19:0-1-8,Edge], [21:0-1-8,0-0-12], [22:0-1-8,0-0-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.50	Vert(LL)	-0.07	15-16	>999	360	MT20	220/195
TCDL	11.0	Lumber DOL	1.00	BC	0.43	Vert(CT)	-0.10	15-16	>999	240		
BCLL	0.0	Rep Stress Incr	YES	WB	0.44	Horz(CT)	0.03	13	n/a	n/a		
BCDL	7.0	Code	IRC2021/TPI2014	Matrix-AS							Weight: 122 lb	FT = 20%F, 11%E

LUMBER

TOP CHORD	2x4 DF No.2(flat)
BOT CHORD	2x4 DF No.2(flat)
WEBS	2x4 DF Stud(flat)
OTHERS	2x4 DF Stud(flat)

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.

REACTIONS (lb/size) 13=718/0-5-8, (min. 0-1-8), 18=1936/0-5-8, (min. 0-1-8)
Max Grav 13=849 (LC 4), 18=1936 (LC 1)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 2-3=0/700, 3-4=0/1564, 4-5=0/1564, 5-6=-1337/569, 6-7=-1337/569, 7-8=-1337/569, 8-9=-1661/25, 9-10=-1661/25, 10-11=-509/0

BOT CHORD 18-19=-700/0, 17-18=-1040/603, 16-17=-1040/603, 15-16=-262/1662, 14-15=0/1251, 13-14=0/509


WEBS 4-18=-251/0, 2-19=-674/0, 3-19=0/469, 3-18=-1120/0, 5-18=-1547/0, 5-16=0/1143, 8-16=-623/0, 8-15=-1/299, 10-15=-99/517, 10-14=-937/8, 11-14=0/631, 11-13=-982/0

NOTES

1) Unbalanced floor live loads have been considered for this design.
2) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
3) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
4) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FA10	Floor	4	1	Job Reference (optional)





Scale = 1:48.5

Plate Offsets (X, Y): [1:Edge,0-0-12], [3:0-1-8,Edge], [11:0-1-8,Edge], [14:0-1-8,Edge], [19:0-1-8,Edge], [21:0-1-8,0-0-12], [22:0-1-8,0-0-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.40	Vert(LL)	-0.07	15-16	>999	360	MT20	220/195
TCDL	11.0	Lumber DOL	1.00	BC	0.44	Vert(CT)	-0.11	15-16	>999	240		
BCLL	0.0	Rep Stress Incr	YES	WB	0.40	Horz(CT)	0.03	13	n/a	n/a		
BCDL	7.0	Code	IRC2021/TPI2014	Matrix-AS							Weight: 118 lb	FT = 20%F, 11%E

LUMBER
TOP CHORD 2x4 DF No.2(flat)
BOT CHORD 2x4 DF No.2(flat)
WEBS 2x4 DF Stud(flat)
OTHERS 2x4 DF Stud(flat)

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

REACTIONS (lb/size) 13=775/0-5-8, (min. 0-1-8), 18=1742/0-5-8, (min. 0-1-8)
Max Grav 13=866 (LC 4), 18=1742 (LC 1)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=0/705, 3-4=0/1093, 4-5=0/1093, 5-6=-1440/238, 6-7=-1440/238, 7-8=-1718/0, 8-9=-1718/0, 9-10=-1718/0, 10-11=-520/0
BOT CHORD 18-19=-705/0, 17-18=-631/730, 16-17=-631/730, 15-16=-5/1742, 14-15=0/1285, 13-14=0/520
WEBS 2-19=-683/0, 3-19=0/472, 3-18=-765/0, 5-18=-1464/0, 5-16=0/1045, 7-16=-531/0, 10-15=-6/546, 10-14=-966/0, 11-14=0/648, 11-13=-1002/0

NOTES
1) Unbalanced floor live loads have been considered for this design.
2) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
3) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
4) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB1	Roof Special	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:25 Page: 1
ID:V1T2Q6Q3LLQiZLM2bLmn7pzgcrd-RVPoCKeCvLUywRnn3W9dExlj06ZCRxB4HmQU1tzcW1q



Scale = 1:65.6

Plate Offsets (X, Y): [2:0-3-8,0-2-8], [3:0-3-8,0-2-8], [6:0-3-7,0-2-0], [7:0-3-7,0-2-9], [9:0-4-0,0-4-12], [15:0-5-8,0-2-8], [16:0-3-8,0-2-8], [20:0-3-8,0-2-8], [21:0-3-8,0-2-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.85	Vert(LL)	-0.63	19-20	>490	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.77	Vert(CT)	-0.75	19-20	>411	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	1.00	Horz(CT)	0.12	15	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.09	19	>999	240		
BCDL	7.0										Weight: 225 lb	FT = 20%

LUMBER
TOP CHORD 2x6 DF No.2 *Except* T2:2x6 DF 1950F 1.5E or 2x6 DF SS
BOT CHORD 2x6 DF 1950F 1.5E or 2x6 DF SS *Except* B1:2x6 DF No.2
WEBS 2x4 DF Stud *Except* W12,W11,W6:2x4 DF No.2, W4:2x4 DF 2100F 1.8E

REACTIONS (lb/size) 15=2283/(0-5-8 + bearing block), (req. 0-5-15), 23=1308/0-5-8, (min. 0-3-6)
Max Horiz 23=-46 (LC 8)
Max Uplift 15=-525 (LC 9), 23=-239 (LC 8)
Max Grav 15=5544 (LC 2), 23=3176 (LC 2)

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 9-11.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 6-16
WEBS 2 Rows at 1/3 pts 7-15

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-25=-5171/442, 3-25=-5159/443, 3-4=-7726/656, 4-5=-7709/581, 5-6=-6050/298, 6-7=-1770/140, 7-8=-1190/5304, 8-9=-1194/5307, 9-26=-696/3415, 10-26=-696/3415, 11-12=-326/50
BOT CHORD 20-21=-383/5158, 19-20=-592/7714, 18-19=-513/7692, 17-18=-247/6038, 16-17=-247/6038, 15-16=-110/1769, 14-15=-3415/751, 13-14=-3415/751, 12-13=-775/243
WEBS 9-15=-2296/606, 9-13=-329/1063, 8-15=-1173/177, 10-13=-2900/557, 10-12=-263/881, 5-19=-242/367, 7-15=-7260/924, 6-18=-100/802, 5-18=-1804/308, 6-16=-4862/671, 7-16=-204/1721, 2-23=-3007/334, 4-19=-770/755, 3-21=-1923/217, 2-21=-503/5321, 3-20=-224/2747, 4-20=-946/106

NOTES
1) 2x6 DF 1950F 1.5E or 2x6 DF SS bearing block 12" long at jt. 15 attached to front face with 3 rows of 10d (0.131"x3") nails spaced 3" o.c. 12 Total fasteners. Bearing is assumed to be DF 1950F 1.5E or SS.
2) Unbalanced roof live loads have been considered for this design.
3) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 32-9-7, Corner (3) 32-9-7 to 36-9-7 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
4) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
5) Provide adequate drainage to prevent water ponding.
6) All plates are MT20 plates unless otherwise indicated.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 239 lb uplift at joint 23 and 525 lb uplift at joint 15.
10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB2	Roof Special	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:25 Page: 1
ID:hElv?7OclcNVYUuEkRgIqTzgcqO-RVPoCKeCvLUywRnn3W9dExljs6XYRzX4HmQU1tzcW1q



Scale = 1:65.6

Plate Offsets (X, Y): [3:0-3-7,0-2-1], [8:0-5-8,0-4-8], [14:0-3-8,0-2-0], [16:0-3-8,0-2-12], [19:0-3-8,0-2-8], [20:0-3-8,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.86	Vert(LL)	-0.67	20-21	>462	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.94	Vert(CT)	-0.79	20-21	>388	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.85	Horz(CT)	0.16	16	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.10	20-21	>999	240		
BCDL	7.0										Weight: 200 lb	FT = 20%

LUMBER
TOP CHORD 2x6 DF No.2 *Except* T2:2x6 DF 1950F 1.5E or 2x6 DF SS
BOT CHORD 2x4 DF 2100F 1.8E *Except* B3,B4:2x4 DF No.2
WEBS 2x4 DF Stud *Except* W11,W12:2x4 DF 2100F 1.8E, W4,W13:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (10-0-0 max.): 8-10.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 7-16, 3-24, 4-22

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 16=2276/(0-5-8 + bearing block), (req. 0-5-14), 24=1315/0-5-8, (min. 0-3-7)
Max Horiz 24=49 (LC 11)
Max Uplift 16=-522 (LC 9), 24=-239 (LC 8)
Max Grav 16=5526 (LC 2), 24=3194 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-5057/441, 4-5=-7536/649, 5-6=-7501/570, 6-7=-5909/298, 7-8=-1161/5294, 8-9=-394/1923, 9-27=-46/265, 10-27=-46/265
BOT CHORD 23-24=-374/5046, 22-23=-374/5046, 21-22=-578/7526, 20-21=-510/7536, 19-20=-235/5898, 18-19=-104/1692, 17-18=-104/1692, 16-17=-104/1692, 15-16=-5068/1180, 14-15=-5068/1180, 13-14=-1923/454
WEBS 2-24=-1076/149, 5-20=-635/143, 8-16=-2503/489, 6-20=-291/1734, 6-19=-1704/264, 7-19=-633/4650, 7-16=-7431/942, 3-24=-5379/517, 3-22=-55/1080, 4-22=-2698/222, 4-21=-269/399, 5-21=-795/782, 9-14=-1517/280, 8-14=-806/3498, 9-13=-411/1857, 10-13=-620/85, 11-13=-280/70

NOTES
1) 2x4 DF No.2 bearing block 12" long at jt. 16 attached to front face with 2 rows of 10d (0.131"x3") nails spaced 3" o.c. 8 Total fasteners. Bearing is assumed to be DF No.2.
2) Unbalanced roof live loads have been considered for this design.
3) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 32-9-7, Corner (3) 32-9-7 to 36-9-7 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
4) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
5) Provide adequate drainage to prevent water ponding.
6) All plates are MT20 plates unless otherwise indicated.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 239 lb uplift at joint 24 and 522 lb uplift at joint 16.
10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB3	Roof Special	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:26 Page: 1
ID:pH4gsCy5g3lqgi_G_p0KENzgcpf-vhzAQgfqgfcpXaM_dDgsm9It9VuZAQJEWQ91ZJzcW1p



Scale = 1:65.6

Plate Offsets (X, Y): [2:0-3-8,0-2-8], [3:0-3-8,0-2-0], [7:0-3-8,0-2-0], [8:0-8-12,0-3-0], [10:0-4-0,0-4-12], [17:0-3-8,Edge], [19:0-3-8,0-2-0], [21:0-3-8,0-2-0], [22:0-3-8,0-2-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.89	Vert(LL)	-0.58	20-21	>525	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.89	Vert(CT)	-0.70	20-21	>440	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.88	Horz(CT)	0.09	14	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.09	20-21	>999	240		
BCDL	7.0										Weight: 200 lb	FT = 20%

LUMBER
TOP CHORD 2x6 DF No.2 *Except* T3:2x6 DF 1950F 1.5E or 2x6 DF SS
BOT CHORD 2x4 DF No.2 *Except* B2:2x4 DF 2100F 1.8E
WEBS 2x4 DF Stud *Except* W12,W17,W6:2x4 DF No.2, W14,W4:2x4 DF 2100F 1.8E

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (2-2-0 max.): 8-10.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 10-14

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 14=2283/(0-5-8 + bearing block), (req. 0-5-15), 24=1308/0-5-8, (min. 0-3-6)
Max Horiz 24=-49 (LC 8)
Max Uplift 14=-525 (LC 9), 24=-239 (LC 8)
Max Grav 14=5544 (LC 2), 24=3176 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-26=-5010/378, 3-26=-4998/379, 3-4=-7450/538, 4-5=-7435/426, 5-6=-7471/433, 6-7=-6360/293, 7-8=-2920/172, 8-9=-1355/5071, 9-10=-1355/5071, 10-11=-149/915
BOT CHORD 21-22=-316/4997, 20-21=-471/7438, 19-20=-260/6347, 18-19=-141/2911, 17-18=-141/2911, 16-17=-2888/1149, 15-16=-2902/1164, 14-15=-2902/1164, 13-14=-930/218
WEBS 5-20=-544/101, 10-13=-169/426, 9-14=-1296/375, 8-14=-3871/352, 6-19=-1410/253, 6-20=-274/1437, 7-17=-2447/380, 7-19=-588/3725, 8-17=-811/5742, 11-13=-1042/209, 10-14=-4365/1263, 2-24=-3095/322, 4-20=-722/708, 3-22=-1915/197, 2-22=-453/5316, 3-21=-168/2642, 4-21=-956/89

NOTES
1) 2x4 DF No.2 bearing block 12" long at jt. 14 attached to front face with 2 rows of 10d (0.131"x3") nails spaced 3" o.c. 8 Total fasteners. Bearing is assumed to be DF No.2.
2) Unbalanced roof live loads have been considered for this design.
3) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 32-9-7, Corner (3) 32-9-7 to 36-9-7 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
4) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
5) Provide adequate drainage to prevent water ponding.
6) All plates are MT20 plates unless otherwise indicated.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 239 lb uplift at joint 24 and 525 lb uplift at joint 14.
10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB4	Roof Special	1	1	Job Reference (optional)



Scale = 1:50.2

Plate Offsets (X, Y): [1:0-3-12,0-5-0], [2:0-3-8,0-2-8], [6:0-5-4,0-5-4], [8:0-4-0,0-3-7], [11:0-3-8,0-2-0], [14:0-7-0,Edge], [17:0-1-12,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.93	Vert(LL)	-0.67	13-14	>432	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	1.00	Vert(CT)	-0.80	13-14	>362	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.88	Horz(CT)	0.07	10	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.13	13-14	>999	240		
BCDL	7.0										Weight: 150 lb	FT = 20%

LUMBER
TOP CHORD 2x6 DF No.2 *Except* T4:2x4 DF No.2
BOT CHORD 2x6 DF 1950F 1.5E or 2x6 DF SS
WEBS 2x4 DF Stud *Except* W1:2x8 DF 2250F 1.6E or 2x8 DF SS, W14,W4,W2:2x4 DF No.2
OTHERS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (2-0-7 max.): 6-8.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 8-10, 7-11

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 10=1179/ Mechanical, 20=1133/0-2-12, (min. 0-2-1)
Max Horiz 20=-48 (LC 8)
Max Uplift 10=-196 (LC 13), 20=-139 (LC 9)
Max Grav 10=2864 (LC 2), 20=2752 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-3578/623, 2-3=-5861/987, 3-4=-5864/986, 4-5=-8266/1368, 5-6=-9699/1592, 6-7=-8449/1389, 7-8=-4944/822, 9-10=-391/77
BOT CHORD 17-18=-149/994, 16-17=-556/3570, 15-16=-1303/8259, 14-15=-1530/9675, 13-14=-1569/9922, 12-13=-1567/9923, 11-12=-1329/8449, 10-11=-740/4798
WEBS 3-16=-413/84, 8-11=-239/1657, 8-10=-5189/833, 7-11=-3877/629, 7-12=-99/787, 6-12=-1660/268, 4-16=-2944/449, 4-15=-105/884, 5-15=-1780/261, 5-14=-11/275, 6-14=-421/115, 2-16=-475/3004, 2-17=-2311/381, 1-17=-529/3342, 1-20=-3540/566


NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) All plates are MT20 plates unless otherwise indicated.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Refer to girder(s) for truss to truss connections.
9) Bearing at joint(s) 20 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
10) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 20.
11) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 196 lb uplift at joint 10 and 139 lb uplift at joint 20.
12) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
13) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.


Continued on page 2

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB4	Roof Special	1	1	Job Reference (optional)

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB5	Roof Special	1	1	Job Reference (optional)





Scale = 1:49.4

Plate Offsets (X, Y): [1:0-3-12,0-5-0], [2:0-1-12,0-1-8], [5:0-5-4,0-4-12], [11:0-3-0,0-2-8], [14:0-6-12,0-5-4], [16:0-1-12,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.76	Vert(LL)	-0.64	13	>446	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.99	Vert(CT)	-0.77	12-13	>375	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	1.00	Horz(CT)	0.06	10	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.12	13	>999	240		
BCDL	7.0										Weight: 152 lb	FT = 20%

LUMBER

TOP CHORD	2x6 DF No.2 *Except* T3:2x6 DF 1950F 1.5E or 2x6 DF SS
BOT CHORD	2x6 DF 1950F 1.5E or 2x6 DF SS
WEBS	2x4 DF Stud *Except* W1:2x8 DF 2250F 1.6E or 2x8 DF SS, W13:2x6 DF No.2, W11,W4,W2:2x4 DF No.2
OTHERS	2x4 DF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (2-3-8 max.): 5-7.
BOT CHORD	Rigid ceiling directly applied.
WEBS	1 Row at midpt 8-10

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 10=1175/ Mechanical, 19=1129/0-2-12, (min. 0-1-8)
Max Horiz 19=-49 (LC 8)
Max Uplift 10=-195 (LC 13), 19=-139 (LC 9)
Max Grav 10=2854 (LC 2), 19=2742 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


TOP CHORD	1-2=-3559/675, 2-3=-5869/1024, 3-4=-5873/1025, 4-5=-8610/1366, 5-6=-9177/1386, 6-7=-6935/1041, 7-20=-6985/1049, 8-20=-6990/1048, 8-9=-279/65, 9-10=-428/78
BOT CHORD	16-17=-161/992, 15-16=-610/3551, 14-15=-1296/8549, 13-14=-1445/9840, 12-13=-1443/9842, 11-12=-1322/9177, 10-11=-569/3966
WEBS	3-15=-496/133, 7-11=-588/103, 4-15=-3173/382, 4-14=-49/721, 5-14=-1554/162, 6-11=-2521/387, 6-12=-43/366, 5-12=-742/134, 8-11=-483/3492, 8-10=-4369/666, 2-15=-454/3041, 2-16=-2304/418, 1-16=-582/3320, 1-19=-3533/613

NOTES

1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-7-2 to 4-7-2, Exterior (2) 4-7-2 to 20-1-4, Corner (3) 20-1-4 to 24-1-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) All plates are MT20 plates unless otherwise indicated.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Refer to girder(s) for truss to truss connections.
9) Bearing at joint(s) 19 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
10) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 19.
11) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 195 lb uplift at joint 10 and 139 lb uplift at joint 19.
12) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
13) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB6	Roof Special	1	1	Job Reference (optional)



Scale = 1:50.4

Plate Offsets (X, Y): [1:0-3-12,0-5-0], [2:0-1-12,0-1-8], [4:0-5-4,0-3-8], [7:0-3-8,0-2-8], [9:Edge,0-3-8], [10:0-3-8,0-2-8], [11:0-2-0,0-2-0], [12:0-7-0,0-5-4], [15:0-1-12,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.78	Vert(LL)	-0.67	12-13	>429	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.98	Vert(CT)	-0.80	12-13	>360	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.92	Horz(CT)	0.05	9	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.13	12-13	>999	240		
BCDL	7.0										Weight: 151 lb	FT = 20%

LUMBER

TOP CHORD	2x6 DF No.2 *Except* T3:2x6 DF 1950F 1.5E or 2x6 DF SS
BOT CHORD	2x6 DF 1950F 1.5E or 2x6 DF SS
WEBS	2x4 DF Stud *Except* W1:2x8 DF 2250F 1.6E or 2x8 DF SS, W12,W9,W2,W4:2x4 DF No.2, W11:2x4 DF 2100F 1.8E
OTHERS	2x4 DF Stud

REACTIONS (lb/size) 9=1179/ Mechanical, 18=1133/0-2-12, (min. 0-2-1)
Max Horiz 18=-49 (LC 8)
Max Uplift 9=-196 (LC 13), 18=-139 (LC 9)
Max Grav 9=2864 (LC 2), 18=2752 (LC 2)

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (2-2-8 max.): 4-6.
BOT CHORD	Rigid ceiling directly applied.
WEBS	1 Row at midpt 4-14

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


TOP CHORD	1-2=-3546/620, 2-3=-6054/1017, 3-4=-6063/1016, 4-5=-9622/1583, 5-6=-8341/1372, 6-7=-8402/1381, 7-8=-5392/895, 8-9=-2743/455
BOT CHORD	15-16=-149/1002, 14-15=-551/3538, 13-14=-1473/9322, 12-13=-1470/9318, 11-12=-1520/9628, 10-11=-835/5382, 9-10=-29/256
WEBS	6-11=-615/124, 7-11=-527/3293, 7-10=-2208/386, 8-10=-892/5565, 5-11=-1455/242, 2-15=-2340/378, 1-15=-521/3290, 2-14=-520/3303, 3-14=-801/160, 4-14=-3674/558, 4-12=-150/543, 1-18=-3541/567

NOTES

1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) All plates are MT20 plates unless otherwise indicated.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Refer to girder(s) for truss to truss connections.
9) Bearing at joint(s) 18 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
10) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 18.
11) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 196 lb uplift at joint 9 and 139 lb uplift at joint 18.
12) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
13) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB7	Roof Special	1	1	Job Reference (optional)



Scale = 1:49.4

Plate Offsets (X, Y): [1:0-3-12,0-5-0], [2:0-3-8,0-2-8], [7:0-3-8,0-1-8], [8:0-3-8,0-2-8], [10:Edge,0-5-8], [11:0-3-8,0-2-8], [12:0-3-8,0-2-8], [13:0-5-8,Edge], [16:0-1-12,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	1.00	Vert(LL)	-0.60	13-14	>481	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.96	Vert(CT)	-0.72	13-14	>400	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.86	Horz(CT)	0.05	10	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.12	13-14	>999	240		
BCDL	7.0										Weight: 152 lb	FT = 20%

LUMBER

TOP CHORD	2x6 DF No.2
BOT CHORD	2x6 DF 1950F 1.5E or 2x6 DF SS
WEBS	2x4 DF Stud *Except* W1:2x8 DF 2250F 1.6E or 2x8 DF SS, W14:2x6 DF No.2, W11,W4,W2:2x4 DF No.2, W13:2x4 DF 2100F 1.8E
OTHERS	2x4 DF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins: 4-6.
BOT CHORD	Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 10=1175/ Mechanical, 19=1129/0-2-12, (min. 0-1-8)
Max Horiz 19=-49 (LC 8)
Max Uplift 10=-195 (LC 13), 19=-139 (LC 9)
Max Grav 10=2854 (LC 2), 19=2742 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	1-2=-3565/622, 2-3=-5828/985, 3-4=-5830/984, 4-5=-8296/1365, 5-6=-8982/1469, 6-7=-8989/1468, 7-8=-7575/1251, 8-9=-4685/780, 9-10=-2708/447
BOT CHORD	16-17=-148/991, 15-16=-553/3558, 14-15=-1292/8246, 13-14=-1494/9367, 12-13=-1188/7567, 11-12=-721/4674, 10-11=-35/346
WEBS	3-15=-407/82, 4-15=-2967/440, 4-14=-64/709, 6-13=-553/113, 5-14=-1409/223, 5-13=-434/104, 7-13=-247/1636, 7-12=-1505/258, 8-12=-529/3278, 8-11=-2231/386, 9-11=-774/4835, 2-15=-473/2976, 2-16=-2293/380, 1-16=-526/3331, 1-19=-3533/565

NOTES


1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) All plates are MT20 plates unless otherwise indicated.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Refer to girder(s) for truss to truss connections.
9) Bearing at joint(s) 19 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
10) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 19.
11) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 195 lb uplift at joint 10 and 139 lb uplift at joint 19.
12) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
13) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

Continued on page 2

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB7	Roof Special	1	1	Job Reference (optional)

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB8	Roof Special	1	1	Job Reference (optional)



Scale = 1:45.2

Plate Offsets (X, Y): [1:0-3-12,0-5-4], [4:0-5-8,0-4-4], [8:0-3-8,0-2-8], [9:0-5-4,0-2-0], [10:Edge,0-5-8], [11:0-3-8,0-2-8], [12:0-3-8,0-2-8], [15:0-3-8,0-2-0], [17:0-4-8,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.82	Vert(LL)	-0.61	13	>476	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.87	Vert(CT)	-0.72	13-15	>400	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.92	Horz(CT)	0.03	10	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.12	13	>999	240		
BCDL	7.0										Weight: 153 lb	FT = 20%

LUMBER

TOP CHORD	2x6 DF No.2 *Except* T3:2x6 DF 1950F 1.5E or 2x6 DF SS
BOT CHORD	2x6 DF 1950F 1.5E or 2x6 DF SS
WEBS	2x4 DF Stud *Except* W1:2x8 DF 2250F 1.6E or 2x8 DF SS, W13:2x6 DF No.2, W10,W2:2x4 DF No.2, W12:2x4 DF 2100F 1.8E
OTHERS	2x4 DF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (2-3-12 max.): 4-6.
BOT CHORD	Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 10=1175/ Mechanical, 20=1129/0-2-12, (min. 0-1-8)
Max Horiz 20=-49 (LC 8)
Max Uplift 10=-195 (LC 13), 20=-139 (LC 9)
Max Grav 10=2854 (LC 2), 20=2742 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	1-2=-3584/623, 2-3=-3582/625, 3-4=-6761/1133, 4-5=-8695/1441, 5-6=-9188/1513, 6-7=-9245/1522, 7-8=-8393/1382, 8-9=-5455/905, 9-10=-2707/450
BOT CHORD	17-18=-144/962, 16-17=-911/5788, 15-16=-1061/6757, 14-15=-1371/8695, 13-14=-1371/8695, 12-13=-1317/8384, 11-12=-844/5443, 10-11=-40/413
WEBS	4-16=-1790/288, 6-13=-619/124, 7-13=-150/939, 7-12=-1240/230, 8-12=-517/3216, 8-11=-2145/377, 9-11=-871/5440, 5-13=-95/751, 5-15=-1143/196, 4-15=-352/2392, 2-17=-463/81, 1-17=-533/3394, 3-17=-2933/473, 3-16=-317/2154, 1-20=-3527/564

NOTES

1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) All plates are MT20 plates unless otherwise indicated.
6) The Fabrication Tolerance at joint 1 = 16%, joint 1 = 16%
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Refer to girder(s) for truss to truss connections.
10) Bearing at joint(s) 20 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
11) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 20.
12) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 195 lb uplift at joint 10 and 139 lb uplift at joint 20.
13) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
14) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.


Continued on page 2


Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB8	Roof Special	1	1	Job Reference (optional)

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB9	Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:28 Page: 1
ID:C1JPte_g8hEx3y1EBgoxnJzgd4P-NtXYd0fSRzkg9kxABxB5JMq1zvEovtBNk4vb5mzcW1o





Scale = 1:43.6

Plate Offsets (X, Y): [1:0-3-12,0-5-4], [2:0-3-8,0-2-8], [7:0-3-8,0-2-8], [9:Edge,0-3-8], [10:0-2-8,0-3-0], [11:0-3-8,0-2-8], [14:0-5-0,0-2-8], [15:0-1-12,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.95	Vert(LL)	-0.61	11-12	>473	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.89	Vert(CT)	-0.73	11-12	>397	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.84	Horz(CT)	0.03	9	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.12	11-12	>999	240		
BCDL	7.0										Weight: 150 lb	FT = 20%

LUMBER

TOP CHORD	2x6 DF No.2
BOT CHORD	2x6 DF 1950F 1.5E or 2x6 DF SS
WEBS	2x4 DF Stud *Except* W1:2x8 DF 2250F 1.6E or 2x8 DF SS, W14,W11,W4,W2:2x4 DF No.2, W13:2x4 DF 2100F 1.8E
OTHERS	2x4 DF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (2-2-0 max.): 3-5.
BOT CHORD	Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 9=1179/ Mechanical, 18=1133/0-2-12, (min. 0-1-8)
Max Horiz 18=-48 (LC 8)
Max Uplift 9=-203 (LC 9), 18=-197 (LC 9)
Max Grav 9=2864 (LC 2), 18=2752 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	1-2=-4186/722, 2-3=-6713/1121, 3-4=-6672/1115, 4-5=-9026/1489, 5-6=-9039/1487, 6-7=-8989/1479, 7-8=-6151/1016, 8-9=-2737/456
BOT CHORD	15-16=-151/1010, 14-15=-653/4177, 13-14=-1284/8113, 12-13=-1284/8113, 11-12=-1413/8976, 10-11=-956/6138, 9-10=-34/319
WEBS	3-14=-461/91, 5-12=-636/129, 4-14=-1852/310, 4-12=-221/1147, 6-12=-77/1079, 6-11=-1024/201, 7-11=-489/3034, 7-10=-2113/378, 8-10=-990/6180, 2-14=-474/3027, 2-15=-2241/374, 1-15=-604/3812, 1-18=-3549/568

NOTES

1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) All plates are MT20 plates unless otherwise indicated.
6) The Fabrication Tolerance at joint 1 = 0%, joint 1 = 0%
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Refer to girder(s) for truss to truss connections.
10) Bearing at joint(s) 18 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
11) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 18.
12) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 203 lb uplift at joint 9 and 197 lb uplift at joint 18.
13) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
14) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.


Continued on page 2

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB9	Hip	1	1	Job Reference (optional)

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB10	Hip	2	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:28 Page: 1
ID:Jp7lAvLU4v0ggZK?xzKz?ezgd3x-r45wrMg5CGsXnuWMkeiKsaNEkJYYeIEXzke8eCzcW1n



Scale = 1:46

Plate Offsets (X, Y): [1:0-3-12,0-5-4], [2:0-3-8,0-2-8], [7:0-5-8,0-3-8], [11:0-3-8,0-2-8], [12:0-5-12,Edge], [13:0-2-12,0-1-8], [14:0-3-8,0-2-8], [15:0-2-0,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.82	Vert(LL)	-0.65	11-12	>444	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.92	Vert(CT)	-0.77	11-12	>373	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.98	Horz(CT)	0.06	9	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.13	11	>999	240		
BCDL	7.0										Weight: 152 lb	FT = 20%

LUMBER
TOP CHORD 2x6 DF No.2 *Except* T3:2x6 DF 1950F 1.5E or 2x6 DF SS
BOT CHORD 2x6 DF 1950F 1.5E or 2x6 DF SS
WEBS 2x4 DF Stud *Except* W1:2x8 DF 2250F 1.6E or 2x8 DF SS, W14,W11,W13,W2,W4:2x4 DF No.2
OTHERS 2x4 DF No.2

REACTIONS (lb/size) 9=1179/ Mechanical, 18=1133/0-2-12, (min. 0-1-8)
Max Horiz 18=-48 (LC 8)
Max Uplift 9=-203 (LC 9), 18=-197 (LC 9)
Max Grav 9=2864 (LC 2), 18=2752 (LC 2)

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (2-4-13 max.): 4-5.
BOT CHORD Rigid ceiling directly applied.
WEBS 2 Rows at 1/3 pts 7-9

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-3946/683, 2-3=-6261/1053, 3-4=-7639/1272, 4-19=-7628/1272, 5-19=-7628/1272, 5-6=-8419/1391, 6-7=-9322/1533, 7-8=-419/96, 8-9=-607/116
BOT CHORD 15-16=-149/999, 14-15=-614/3938, 13-14=-982/6255, 12-13=-1312/8336, 11-12=-1466/9308, 10-11=-1052/6725, 9-10=-1052/6725
WEBS 4-13=-288/69, 5-13=-1441/234, 5-12=-144/458, 6-12=-961/585, 6-11=-809/172, 7-11=-437/2724, 7-9=-6663/1071, 1-15=-575/3635, 3-13=-280/1785, 2-15=-2285/381, 2-14=-460/2897, 3-14=-1674/286, 1-18=-3547/567

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) All plates are MT20 plates unless otherwise indicated.
6) The Fabrication Tolerance at joint 1 = 8%, joint 1 = 8%
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Refer to girder(s) for truss to truss connections.
10) Bearing at joint(s) 18 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
11) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 18.
12) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 203 lb uplift at joint 9 and 197 lb uplift at joint 18.
13) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
14) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.


Continued on page 2


Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB10	Hip	2	1	Job Reference (optional)

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB11	Common	2	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:28 Page: 1
ID:4d8CPSeABaA7APkpvjHqWwzgd3Y-r45wrMg5CGsXnuWMkeiKsaNDeJYieKRXzke8eCzcW1n





Scale = 1:45.8

Plate Offsets (X, Y): [1:0-3-12,0-5-4], [7:0-3-0,Edge], [10:Edge,0-3-4], [12:0-3-8,0-2-8], [17:0-4-8,0-2-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.89	Vert(LL)	-0.61	12-13	>477	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.91	Vert(CT)	-0.72	12-13	>401	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.84	Horz(CT)	0.06	10	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.11	13	>999	240		
BCDL	7.0										Weight: 152 lb	FT = 20%

LUMBER
TOP CHORD 2x6 DF No.2
BOT CHORD 2x6 DF 1950F 1.5E or 2x6 DF SS
WEBS 2x4 DF Stud *Except* W1:2x8 DF 2250F 1.6E or 2x8 DF SS, W14,W12,W2:2x4 DF No.2
OTHERS 2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 8-10

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 10=1179/ Mechanical, 20=1133/0-2-12, (min. 0-1-8)
Max Horiz 20=-48 (LC 8)
Max Uplift 10=-182 (LC 13), 20=-116 (LC 12)
Max Grav 10=2864 (LC 2), 20=2752 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-4137/635, 2-21=-4135/638, 3-21=-4130/638, 3-4=-6496/960, 4-5=-8021/1158, 5-6=-9252/1321, 6-7=-8630/1232, 7-8=-8640/1231, 8-9=-277/70, 9-10=-480/91
BOT CHORD 17-18=-132/988, 16-17=-887/6491, 15-16=-1086/8012, 14-15=-1252/9243, 13-14=-1252/9243, 12-13=-1167/8629, 11-12=-761/5601, 10-11=-761/5601
WEBS 4-15=-90/895, 5-15=-1915/343, 8-10=-5791/815, 5-13=-269/69, 6-13=-93/676, 6-12=-1164/187, 8-12=-439/3272, 1-17=-527/3805, 2-17=-551/106, 3-17=-2920/395, 3-16=-134/1246, 4-16=-2051/248, 1-20=-3545/508

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-7-2 to 4-7-2, Exterior (2) 4-7-2 to 20-2-4, Corner (3) 20-2-4 to 24-2-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) All plates are MT20 plates unless otherwise indicated.
6) The Fabrication Tolerance at joint 1 = 0%, joint 1 = 0%
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Refer to girder(s) for truss to truss connections.
10) Bearing at joint(s) 20 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
11) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 20.
12) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 182 lb uplift at joint 10 and 116 lb uplift at joint 20.
13) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB12	Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:28 Page: 1
ID:v21vEJwbmf3sQx?El2BEymzgd3B-r45wrMg5CGsXnuWMkeiKsaNFzJc?eM8Xzke8eCzcW1n



Scale = 1:43.6

Plate Offsets (X, Y): [1:0-2-0,0-4-0], [3:0-3-0,0-3-4]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.74	Vert(LL)	-0.18	11-12	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.70	Vert(CT)	-0.22	11-12	>945	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.73	Horz(CT)	0.04	10	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.04	11-12	>999	240		
BCDL	7.0										Weight: 137 lb	FT = 20%

LUMBER
TOP CHORD 2x6 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W1:2x8 DF 2250F 1.6E or 2x8 DF SS, W9:2x4 DF No.2
OTHERS 2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 3-6.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 7-13, 8-10

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 10=698/ Mechanical, 15=1677/0-5-8, (min. 0-4-6), 20=-63/0-2-12, (min. 0-1-8)
Max Horiz 20=-51 (LC 8)
Max Uplift 10=-121 (LC 13), 15=-289 (LC 9), 20=-153 (LC 2)
Max Grav 10=1695 (LC 2), 15=4074 (LC 2), 20=427 (LC 30)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-321/619, 2-3=-272/1996, 3-4=-413/2846, 4-5=-413/2846, 5-6=-945/193, 6-7=-896/180, 7-8=-3196/548, 9-10=-499/97
BOT CHORD 16-17=-612/315, 15-16=-2065/358, 14-15=-1487/265, 13-14=-1487/265, 12-13=-480/3185, 11-12=-451/2999, 10-11=-451/2999
WEBS 6-13=-807/157, 7-13=-2497/406, 8-10=-3055/492, 5-13=-478/3039, 2-17=-84/457, 1-17=-726/189, 2-16=-1736/287, 3-16=-160/1028, 3-15=-1524/256, 4-15=-610/104, 5-15=-2454/406, 1-20=-556/191


NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) All plates are MT20 plates unless otherwise indicated.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Refer to girder(s) for truss to truss connections.
9) Bearing at joint(s) 20 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
10) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 20.
11) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 121 lb uplift at joint 10, 289 lb uplift at joint 15 and 153 lb uplift at joint 20.
12) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
13) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB13	Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:29 Page: 1
ID:_0XHfhwfD9W5uirA6_AhpGzgd1u-JGfl2ihjza_OO25ZILDZOnwNcjxRNm7gCOOiAezcW1m





Scale = 1:59.6

Plate Offsets (X, Y): [2:0-3-8,0-2-0], [5:0-3-0,0-3-12], [13:0-3-8,0-2-8], [21:0-3-8,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.94	Vert(LL)	-0.19	14-15	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.75	Vert(CT)	-0.22	14-15	>954	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.94	Horz(CT)	0.05	12	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.03	14	>999	240		
BCDL	7.0										Weight: 188 lb	FT = 20%

LUMBER
TOP CHORD 2x6 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W16:2x4 DF No.2

REACTIONS (lb/size) 12=668/ Mechanical, 18=1932/0-5-8, (min. 0-5-0), 23=751/0-5-8, (min. 0-2-2)
Max Horiz 23=51 (LC 9)
Max Uplift 12=-125 (LC 13), 18=-251 (LC 9), 23=-182 (LC 8)
Max Grav 12=1746 (LC 31), 18=4693 (LC 2), 23=1988 (LC 30)

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (2-2-0 max.): 5-8.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 5-18, 8-17

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-25=-2070/171, 3-25=-2059/172, 3-4=-2225/585, 4-5=-440/1255, 5-6=-365/3487, 6-7=-365/3487, 7-8=-182/1923, 8-9=-2425/234, 9-10=-3555/392, 10-11=-2873/339, 11-12=-1695/201
BOT CHORD 20-21=-155/2059, 19-20=-583/2216, 18-19=-1280/363, 17-18=-1923/253, 16-17=-183/2369, 15-16=-183/2369, 14-15=-326/3545, 13-14=-277/2864
WEBS 5-19=-83/1028, 8-15=-54/725, 2-23=-1857/240, 9-15=-1514/181, 9-14=-257/70, 10-14=-55/751, 10-13=-1187/157, 11-13=-319/2995, 4-19=-2324/252, 3-21=-871/125, 2-21=-242/2293, 3-20=-469/172, 4-20=-10/253, 6-18=-543/71, 7-18=-2783/326, 5-18=-3324/369, 7-17=-149/1524, 8-17=-3867/449


NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 30-4-0, Corner (3) 30-4-0 to 34-4-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 125 lb uplift at joint 12, 182 lb uplift at joint 23 and 251 lb uplift at joint 18.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB14	Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:29 Page: 1
ID:mKulcX4YeQ5Jczo5RaLnp_zcYYv-JGfl2ihjza_OO25ZILDZOnwRpjxRNorgCOOiAezcW1m





Scale = 1:59.6

Plate Offsets (X, Y): [2:0-3-8,0-2-0], [5:0-1-12,0-2-0], [6:0-3-8,0-2-0], [10:0-3-0,0-3-4], [12:0-3-8,0-2-0], [13:0-1-12,0-2-0], [15:0-3-8,0-2-0], [17:0-3-8,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.67	Vert(LL)	-0.19	11-12	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.75	Vert(CT)	-0.23	11-12	>895	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.83	Horz(CT)	0.05	10	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.03	11-12	>999	240		
BCDL	7.0										Weight: 184 lb	FT = 20%

LUMBER
TOP CHORD 2x6 DF No.2 *Except* T2:2x6 DF 1950F 1.5E or 2x6 DF SS
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W14:2x6 DF No.2, W11,W8,W10:2x4 DF No.2

REACTIONS (lb/size) 10=678/ Mechanical, 15=1897/0-5-8, (min. 0-4-15), 19=768/0-5-8, (min. 0-2-0)
Max Horiz 19=-52 (LC 8)
Max Uplift 10=-122 (LC 9), 15=-321 (LC 8), 19=-173 (LC 8)
Max Grav 10=1729 (LC 31), 15=4606 (LC 2), 19=1865 (LC 2)

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (4-6-4 max.): 4-7.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 4-15, 8-10

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-21=-2048/219, 3-21=-2036/220, 3-4=-974/283, 4-5=-307/3046, 5-22=-860/77, 6-22=-860/77, 6-7=-3125/356, 7-8=-3184/389, 8-23=-268/64, 9-23=-288/64, 9-10=-555/84
BOT CHORD 16-17=-165/2035, 15-16=-294/927, 14-15=-3046/376, 13-14=-3046/376, 12-13=-79/860, 11-12=-299/3198, 10-11=-321/3172
WEBS 4-16=-4/447, 7-12=-1031/153, 2-19=-1787/259, 3-16=-1146/107, 3-17=-641/122, 2-17=-276/2132, 6-12=-306/2691, 5-15=-3033/387, 4-15=-4227/461, 5-13=-437/3757, 6-13=-1785/233, 8-10=-3103/343


NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 30-3-0, Corner (3) 30-3-0 to 34-3-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 122 lb uplift at joint 10, 173 lb uplift at joint 19 and 321 lb uplift at joint 15.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB15	Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:29 Page: 1
ID:uemx1Psha59DHphOB0UnPTzcYXv-JGfl2ihjza_OO25ZILDZOnwQtjw_NmpgCOOiAezcW1m





Scale = 1:59.6

Plate Offsets (X, Y): [5:0-3-8,0-1-8], [8:0-3-8,0-2-8], [13:0-3-8,0-2-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.73	Vert(LL)	-0.19	14-15	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.78	Vert(CT)	-0.23	14-15	>880	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.96	Horz(CT)	0.06	12	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.03	14-15	>999	240		
BCDL	7.0										Weight: 186 lb	FT = 20%

LUMBER
TOP CHORD 2x6 DF No.2 *Except* T2:2x6 DF 1950F 1.5E or 2x6 DF SS
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W14:2x6 DF No.2, W13,W10:2x4 DF No.2

REACTIONS (lb/size) 12=677/ Mechanical, 17=1898/0-5-8, (min. 0-4-15), 22=767/0-5-8, (min. 0-2-0)
Max Horiz 22=53 (LC 9)
Max Uplift 12=-121 (LC 9), 17=-322 (LC 8), 22=-173 (LC 8)
Max Grav 12=1707 (LC 31), 17=4610 (LC 2), 22=1863 (LC 2)

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (4-8-15 max.): 4-9.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 8-17, 5-17

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-24=-1793/181, 3-24=-1783/181, 3-4=-1692/192, 4-5=-74/366, 5-6=-330/3157, 6-25=-330/3157, 7-25=-330/3157, 7-8=-330/3157, 8-9=-1863/207, 9-26=-3399/402, 10-26=-3407/401, 10-11=-2678/333, 11-12=-1655/204
BOT CHORD 19-20=-133/1783, 18-19=-161/1674, 17-18=-366/57, 16-17=-144/1863, 15-16=-144/1863, 14-15=-340/3422, 13-14=-271/2668
WEBS 9-14=-291/68, 2-22=-1721/244, 10-14=-76/815, 10-13=-1136/154, 11-13=-306/2731, 3-20=-772/130, 2-20=-254/2013, 6-17=-1208/171, 8-15=-39/682, 8-17=-4913/574, 9-15=-1846/214, 5-17=-3436/380, 5-18=-70/918, 4-18=-1984/209

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 30-3-0, Corner (3) 30-3-0 to 34-3-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 121 lb uplift at joint 12, 173 lb uplift at joint 22 and 322 lb uplift at joint 17.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB16	Hip Girder	1	2	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:30 Page: 1
ID:4ZVN2ccaz8zQjKQJp1cKvYzcYWx-nSDgF1iLku6F0Cfls3kox?Scu7EL6F5qR27Fi5zcW1I



Scale = 1:59.6

Plate Offsets (X, Y): [7:0-3-8,0-2-8], [8:0-3-8,0-2-8], [15:0-3-8,0-2-8], [17:0-4-8,0-2-8], [19:0-3-8,0-4-8], [24:0-3-4,0-4-8], [25:0-3-8,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.65	Vert(LL)	-0.17	16-17	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.90	Vert(CT)	-0.20	16-17	>999	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	NO	WB	0.83	Horz(CT)	0.03	14	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH		Wind(LL)	0.03	16-17	>999	240		
BCDL	7.0										Weight: 433 lb	FT = 20%

LUMBER
TOP CHORD 2x6 DF No.2 *Except* T2:2x6 DF 1950F 1.5E or 2x6 DF SS
BOT CHORD 2x6 DF No.2
WEBS 2x4 DF Stud *Except* W15,W12:2x4 DF No.2, W11:2x4 DF 2100F 1.8E

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 4-11.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
6-0-0 oc bracing: 21-22
5-1-10 oc bracing: 18-21.

REACTIONS (lb/size) 14=1642/ Mechanical, 21=4286/(0-5-8 + bearing block), (req. 0-5-11), 26=1197/0-5-8, (min. 0-1-9)
Max Horiz 26=53 (LC 33)
Max Uplift 14=-316 (LC 6), 21=-719 (LC 7), 26=-262 (LC 6)
Max Grav 14=4059 (LC 2), 21=10654 (LC 2), 26=2979 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-3340/264, 3-4=-5571/431, 4-5=-3803/330, 5-6=-130/1028, 6-7=-511/7237, 7-28=-1552/138, 8-28=-1552/138, 8-9=-6724/461, 9-10=-6724/461, 10-11=-6724/461, 11-12=-7049/504, 12-13=-4763/367, 13-14=-3192/244
BOT CHORD 24-25=-286/3330, 24-29=-450/5548, 23-29=-450/5548, 23-30=-301/3803, 22-30=-301/3803, 22-31=-1028/113, 21-31=-1028/113, 20-21=-7237/514, 20-32=-7237/514, 32-33=-7237/514, 19-33=-7237/514, 18-19=-7237/514, 18-34=-155/1552, 17-34=-155/1552, 17-35=-500/7083, 16-35=-500/7083, 16-36=-362/4754, 15-36=-362/4754
WEBS 4-24=-61/461, 11-16=-467/91, 2-26=-2637/234, 3-24=-227/2588, 3-25=-1874/167, 2-25=-287/3697, 12-16=-173/2727, 12-15=-2017/144, 13-15=-393/5325, 7-21=-5166/373, 6-21=-7114/502, 5-23=-125/2004, 4-23=-1999/172, 5-22=-5535/405, 6-22=-197/3088, 8-18=-2878/229, 7-18=-639/9586, 8-17=-391/5641, 10-17=-895/97, 11-17=-392/59

NOTES
1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc, 2x6 - 2 rows staggered at 0-9-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-4-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) 2x6 DF No.2 bearing block 12" long at jt. 21 attached to each face with 3 rows of 10d (0.131"x3") nails spaced 3" o.c. 12 Total fasteners per block. Bearing is assumed to be DF No.2.
4) Unbalanced roof live loads have been considered for this design.
5) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
6) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
7) Provide adequate drainage to prevent water ponding.
8) All plates are MT20 plates unless otherwise indicated.
9) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
10) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
11) Refer to girder(s) for truss to truss connections.


Continued on page 2


12) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 316 lb uplift at joint 14, 262 lb uplift at joint 26 and 719 lb uplift at joint 21.
13) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
14) Use Simpson Strong-Tie THJA26 (THJA26 on 2 ply, Left Hand Hip) or equivalent at 8-0-6 from the left end to connect truss(es) FJ4 (1 ply 2x4 DF), FJ8 (1 ply 2x4 DF) to front face of bottom chord.
15) Use Simpson Strong-Tie LUS24 (4-10d Girder, 2-10d Truss) or equivalent spaced at 2-0-0 oc max. starting at 10-0-12 from the left end to 32-10-7 to connect truss(es) FJ4 (1 ply 2x4 DF), FJ3 (1 ply 2x4 DF), FJ2 (1 ply 2x4 DF) to front face of bottom chord.
16) Fill all nail holes where hanger is in contact with lumber.
17) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 542 lb down and 51 lb up at 34-4-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard

1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
   Uniform Loads (lb/ft)
   Vert: 1-13=-84, 14-27=-14
   Concentrated Loads (lb)
   Vert: 14=-219, 24=-645, 16=-224, 22=-224, 18=-224, 17=-224, 29=-224, 30=-224, 31=-224, 32=-224, 33=-224, 34=-224, 35=-224, 36=-224, 37=-224

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FB17	Monopitch	11	1	Job Reference (optional)





Scale = 1:36.4

0-5-8 0-3-8

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	1.00	Vert(LL)	-0.09	5-6	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.36	Vert(CT)	-0.15	5-6	>629	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.48	Horz(CT)	0.02	15	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.00	5	>999	240		
BCDL	7.0										Weight: 50 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud
OTHERS 2x6 DF No.2 *Except* BL2:2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 10=598/0-4-0, (min. 0-1-8), 15=329/0-2-12, (min. 0-1-8)
Max Horiz 10=54 (LC 9)
Max Uplift 10=-140 (LC 8), 15=-58 (LC 12)
Max Grav 10=1466 (LC 2), 15=799 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 5-15=-94/445, 4-15=-94/445
BOT CHORD 5-6=-238/977
WEBS 3-5=-843/258, 3-6=-1052/298, 2-10=-142/409, 6-10=-117/519, 2-10=-117/519, 4-15=-956/241

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Bearing at joint(s) 10, 15 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
8) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 15.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 140 lb uplift at joint 10 and 58 lb uplift at joint 15.
10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC1	Common	20	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:31 Page: 1
ID:93eciZK2KcgmHsyUkrZyCxzgdNK-Ffn3TNjzVBE6eMExQmG1TC?i9WZTrhPzfitoEXzcW1k



Scale = 1:50.5

Plate Offsets (X, Y): [3:0-2-0,0-3-4], [4:0-3-7,0-3-8], [6:0-3-7,0-3-8], [7:0-2-0,0-3-4], [11:0-6-12,0-4-8], [12:0-3-8,0-3-8], [17:0-3-8,0-3-8], [18:0-3-4,0-4-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	1.00	Vert(LL)	-0.76	15	>406	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.97	Vert(CT)	-0.91	15	>341	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.89	Horz(CT)	0.16	11	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.12	15	>999	240		
BCDL	7.0										Weight: 200 lb	FT = 20%

LUMBER
TOP CHORD 2x6 DF No.2
BOT CHORD 2x8 DF 2250F 1.6E or 2x8 DF SS
WEBS 2x4 DF Stud *Except* W4:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 7-11, 6-12, 3-18, 4-17

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 11=1456/0-5-8, (min. 0-3-12), 18=1456/0-5-8, (min. 0-3-12)
Max Horiz 18=43 (LC 11)
Max Uplift 11=-238 (LC 9), 18=-238 (LC 8)
Max Grav 11=3535 (LC 2), 18=3535 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 9-10=-383/29, 5-6=-9935/1222, 6-7=-6449/792, 7-20=-644/80, 8-20=-657/79, 8-9=-528/57, 1-2=-528/27, 2-21=-657/41, 3-21=-645/42, 3-4=-6448/766, 4-5=-9934/1210, 1-19=-383/26
BOT CHORD 17-18=-704/6433, 16-17=-1143/9922, 15-16=-1255/10775, 14-15=-1255/10775, 13-14=-1255/10775, 12-13=-1155/9923, 11-12=-729/6433
WEBS 2-18=-1120/180, 1-18=-48/699, 9-11=-43/699, 8-11=-1120/174, 7-11=-6160/753, 6-13=-220/708, 5-13=-1689/619, 6-12=-3750/458, 7-12=-103/1144, 5-16=-1690/618, 3-17=-108/1145, 3-18=-6160/766, 4-17=-3750/472, 4-16=-220/708


NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 25-10-4, Corner (3) 25-10-4 to 29-10-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) All plates are MT20 plates unless otherwise indicated.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 238 lb uplift at joint 18 and 238 lb uplift at joint 11.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC2	Common	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:31 Page: 1
ID:4eiRlt?2vCOQriqzIlrUy8zcZHV-Ffn3TNjzVBE6eMExQmG1TC?n9WZJrgTzfitoEXzcW1k





Scale = 1:49.9

Plate Offsets (X, Y): [3:0-3-7,0-2-1], [11:0-3-8,0-2-0], [16:0-3-0,0-2-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.68	Vert(LL)	-0.85	12	>363	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.98	Vert(CT)	-1.01	12	>305	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.95	Horz(CT)	0.20	9	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.15	12	>999	240		
BCDL	7.0										Weight: 169 lb	FT = 20%

LUMBER
TOP CHORD 2x6 DF 1950F 1.5E or 2x6 DF SS
BOT CHORD 2x6 DF 1950F 1.5E or 2x6 DF SS
WEBS 2x4 DF Stud *Except* W13,W12,W11,W4:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 7-9, 3-16, 4-15

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 9=1247/0-5-8, (min. 0-3-4), 16=1468/0-5-8, (min. 0-3-13)
Max Horiz 16=48 (LC 11)
Max Uplift 9=-170 (LC 9), 16=-242 (LC 8)
Max Grav 9=3029 (LC 2), 16=3565 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-6001/818, 4-18=-10342/1446, 5-18=-10334/1447, 5-19=-10328/1447, 6-19=-10342/1447, 6-7=-9720/1382, 7-8=-349/78, 8-9=-526/92
BOT CHORD 15-16=-754/5989, 14-15=-1262/9523, 13-14=-1262/9523, 12-13=-1262/9523, 11-12=-1317/9707, 10-11=-866/6381, 9-10=-866/6381
WEBS 1-16=-13/309, 2-16=-1060/184, 5-12=-525/98, 7-9=-6489/910, 6-12=-754/1543, 6-11=-1216/199, 7-11=-483/3564, 3-16=-6231/893, 3-15=-158/1357, 4-15=-3811/548, 4-12=-637/1656


NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 12-1-12, Exterior (2) 12-1-12 to 15-10-4, Corner (3) 15-10-4 to 27-10-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) All plates are MT20 plates unless otherwise indicated.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 170 lb uplift at joint 9 and 242 lb uplift at joint 16.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC3	Common	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:31 Page: 1
ID:1e?laRFHQ9VfKhmyq8it93zcZFt-Ffn3TNjzVBE6eMExQmG1TC?kLWczrhizfitoEXzcW1k





Scale = 1:43.5

Plate Offsets (X, Y): [2:0-3-8,0-2-8], [3:0-3-8,0-2-0], [6:0-3-7,0-2-0], [11:0-3-8,0-2-0], [13:0-3-8,0-2-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.86	Vert(LL)	-0.48	10-11	>537	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.81	Vert(CT)	-0.57	10-11	>450	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.87	Horz(CT)	0.12	8	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.09	10-11	>999	240		
BCDL	7.0										Weight: 111 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF 2100F 1.8E *Except* T2:2x4 DF No.2
BOT CHORD 2x4 DF 2100F 1.8E
WEBS 2x4 DF Stud *Except* W4:2x4 DF 2100F 1.8E, W11:2x4 DF No.2

REACTIONS (lb/size) 8=1034/ Mechanical, 14=1259/0-5-8, (min. 0-3-4)
Max Horiz 14=58 (LC 9)
Max Uplift 8=-125 (LC 9), 14=-230 (LC 8)
Max Grav 8=2512 (LC 2), 14=3057 (LC 2)

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 6-8

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-4602/717, 3-4=-6685/1079, 4-5=-6432/1053, 5-6=-4638/779, 7-8=-466/93
BOT CHORD 12-13=-653/4591, 11-12=-653/4591, 10-11=-1010/6674, 9-10=-979/6407, 8-9=-705/4626
WEBS 2-14=-2893/510, 5-10=-242/512, 4-10=-1051/731, 3-13=-1887/351, 2-13=-832/5021, 3-11=-389/2270, 4-11=-849/180, 6-9=-97/928, 5-9=-2024/305, 6-8=-4871/776

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) All plates are MT20 plates unless otherwise indicated.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Refer to girder(s) for truss to truss connections.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 125 lb uplift at joint 8 and 230 lb uplift at joint 14.
10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard


Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC4	Common	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:32 Page: 1
ID:V64YMbTZAhm6US9Quw15uszcZFb-krLRgjjbFVMzFVp7zUnG0QYyvwwKa9B6uMcMnzzcW1j



22-1-14 22-1-14

2-2-12



Scale = 1:36.3

0-2-12

Plate Offsets (X, Y): [2:0-3-8,0-2-0], [5:0-5-8,0-2-8], [9:0-3-8,0-1-8], [10:0-5-12,0-2-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.68	Vert(LL)	-0.21	9	>929	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.93	Vert(CT)	-0.25	9	>782	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.79	Horz(CT)	0.06	7	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.05	9-10	>999	240		
BCDL	7.0										Weight: 90 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF 2100F 1.8E *Except* T2:2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W4:2x4 DF No.2

REACTIONS (lb/size) 7=795/ Mechanical, 12=1025/0-5-8, (min. 0-2-10)
Max Horiz 12=63 (LC 9)
Max Uplift 7=-86 (LC 12), 12=-210 (LC 8)
Max Grav 7=1931 (LC 2), 12=2489 (LC 2)

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 5-7

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-3275/585, 3-4=-3273/590, 4-5=-4231/795, 6-7=-430/90
BOT CHORD 9-10=-723/4219, 8-9=-482/2855, 7-8=-484/2852
WEBS 5-7=-3122/567, 2-12=-2334/480, 3-10=-876/198, 4-10=-1064/222, 2-10=-691/3594, 4-9=-641/129, 5-9=-264/1735

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 86 lb uplift at joint 7 and 210 lb uplift at joint 12.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC5	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:32 Page: 1
ID:9Qp5tic5LNHPwI3jbSFvNOzcZFP-krLRgjjbFVMzFVp7zUnG0QYzKw1ga8F6uMcMnzzcW1j



22-1-14 22-1-14



Scale = 1:34.8

0-2-12

Plate Offsets (X, Y): [2:0-3-8,0-2-0], [5:0-0-8,0-1-8], [8:0-3-8,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.59	Vert(LL)	-0.08	7-8	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.46	Vert(CT)	-0.10	7-8	>999	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.85	Horz(CT)	0.02	6	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.02	7-8	>999	240		
BCDL	7.0										Weight: 68 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 6=553/ Mechanical, 9=794/0-5-8, (min. 0-2-1)
Max Horiz 9=66 (LC 9)
Max Uplift 6=-93 (LC 12), 9=-178 (LC 8)
Max Grav 6=1343 (LC 2), 9=1928 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1900/393, 3-4=-1932/429, 5-6=-399/104
BOT CHORD 7-8=-335/1891, 6-7=-366/1922
WEBS 2-9=-1743/426, 4-6=-2030/423, 3-8=-872/239, 2-8=-505/2198

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 93 lb uplift at joint 6 and 178 lb uplift at joint 9.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC6	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:32 Page: 1
ID:Gw5?b8nFINwZ_lZDsg_yP8zcZFC-krLRgjjbFVMzFVp7zUnG0QY?Ww57aGN6uMcMnzzcW1j



Scale = 1:30

0-2-12

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.45	Vert(LL)	-0.04	5-6	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.24	Vert(CT)	-0.07	5-6	>999	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.33	Horz(CT)	0.01	5	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.00	5-6	>999	240		
BCDL	7.0										Weight: 44 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 5=304/ Mechanical, 6=570/0-5-8, (min. 0-1-8)
Max Horiz 6=62 (LC 9)
Max Uplift 5=-41 (LC 8), 6=-145 (LC 8)
Max Grav 5=737 (LC 2), 6=1384 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 4-5=-344/106
BOT CHORD 5-6=-145/725
WEBS 2-6=-687/214, 3-5=-736/192, 3-6=-1002/346

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 145 lb uplift at joint 6 and 41 lb uplift at joint 5.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC7	Jack-Closed	1	1	Job Reference (optional)



Scale = 1:29.9

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.27	Vert(LL)	0.00	4-5	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.04	Vert(CT)	0.00	4-5	>999	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.17	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.00	4-5	>999	240		
BCDL	7.0										Weight: 24 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=-8/ Mechanical, 5=408/0-5-8, (min. 0-1-8)
Max Horiz 5=59 (LC 9)
Max Uplift 4=-35 (LC 24), 5=-146 (LC 8)
Max Grav 4=42 (LC 8), 5=992 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 1-5=-275/123, 2-5=-769/339, 2-4=-184/282


NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 146 lb uplift at joint 5 and 35 lb uplift at joint 4.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC8	Common	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:32 Page: 1
ID:lwEfWwPs2LTBDHXDvbv9W6zcZEO-krLRgjjbFVMzFVp7zUnG0QYtDww1a8F6uMcMnzzcW1j





Scale = 1:46.5

Plate Offsets (X, Y): [2:0-3-0,0-1-8], [3:0-3-8,0-2-8], [6:0-3-8,0-2-0], [7:0-3-4,0-3-8], [8:0-3-8,Edge], [9:0-2-12,0-2-8], [11:0-3-8,0-2-8], [12:0-3-8,0-2-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.98	Vert(LL)	-0.61	10-11	>461	360	M18AHS	169/162
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.95	Vert(CT)	-0.72	10-11	>387	240	MT20	220/195
TCDL	12.0	Rep Stress Incr	YES	WB	0.85	Horz(CT)	0.12	8	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.11	10	>999	240		
BCDL	7.0										Weight: 137 lb	FT = 20%

LUMBER
TOP CHORD 2x6 DF No.2
BOT CHORD 2x4 DF 2100F 1.8E
WEBS 2x4 DF Stud *Except* W13,W6:2x4 DF No.2, W4,W12:2x4 DF 2100F 1.8E

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 8=1135/ Mechanical, 13=1358/0-5-8, (min. 0-3-8)
Max Horiz 13=53 (LC 9)
Max Uplift 8=-147 (LC 9), 13=-236 (LC 8)
Max Grav 8=2758 (LC 2), 13=3298 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 7-8=-2683/424, 5-6=-8276/1255, 6-7=-6371/986, 2-3=-5297/772, 3-4=-7987/1198, 4-15=-8271/1255, 15-16=-8263/1255, 5-16=-8260/1256
BOT CHORD 11-12=-710/5284, 10-11=-1130/7975, 9-10=-921/6357, 8-9=-25/274
WEBS 2-13=-3217/530, 5-10=-708/141, 4-10=-854/1221, 3-12=-2028/351, 2-12=-865/5611, 3-11=-455/2912, 4-11=-1059/198, 6-10=-279/2212, 6-9=-1918/333, 7-9=-957/6386


NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 12-1-12, Exterior (2) 12-1-12 to 13-7-1, Corner (3) 13-7-1 to 25-7-1 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) All plates are MT20 plates unless otherwise indicated.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Refer to girder(s) for truss to truss connections.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 147 lb uplift at joint 8 and 236 lb uplift at joint 13.
10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC9	Common	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:33 Page: 1
ID:DwNJQi1UoK0oTHWDyWrLd3zcZDa-C1upu3kD0pVptfOKXBIVZd48SKG2JZ9G70MvJPzcW1i





Scale = 1:42.7

0-2-12

Plate Offsets (X, Y): [3:0-3-7,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.63	Vert(LL)	-0.29	10	>759	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.90	Vert(CT)	-0.35	10	>639	240		
TCDL	12.0	Rep Stress Incr	YES	WB	1.00	Horz(CT)	0.09	8	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.06	10	>999	240		
BCDL	7.0										Weight: 100 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2 *Except* T1:2x4 DF 2100F 1.8E
BOT CHORD 2x4 DF No.2 *Except* B2:2x4 DF 2100F 1.8E
WEBS 2x4 DF Stud
OTHERS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 3-13

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 8=896/ Mechanical, 13=1124/0-5-8, (min. 0-2-15)
Max Horiz 13=61 (LC 9)
Max Uplift 8=-93 (LC 9), 13=-219 (LC 8)
Max Grav 8=2177 (LC 2), 13=2729 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 7-8=-318/69, 5-6=-4259/760, 3-4=-3837/652, 4-5=-5263/929
BOT CHORD 12-13=-584/3826, 11-12=-584/3826, 10-11=-855/5251, 9-10=-701/4326, 8-9=-449/2742
WEBS 2-13=-899/192, 5-9=-1023/205, 3-13=-4220/761, 3-11=-87/666, 4-11=-1565/298, 4-10=-554/166, 5-10=-243/1420, 6-9=-292/1859, 6-8=-3217/572

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 93 lb uplift at joint 8 and 219 lb uplift at joint 13.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC10	Common	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:33 Page: 1
ID:tVdHWdOgzEghRkEn86s8IBzcZD7-C1upu3kD0pVptfOKXBIVZd47zKLuJaZG70MvJPzcW1i



Scale = 1:40

Plate Offsets (X, Y): [2:0-3-8,0-2-8], [10:0-3-8,0-2-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.66	Vert(LL)	-0.13	9-10	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.59	Vert(CT)	-0.16	9-10	>999	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.91	Horz(CT)	0.03	7	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.03	9-10	>999	240		
BCDL	7.0										Weight: 79 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W4:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 7=656/ Mechanical, 12=891/0-5-8, (min. 0-2-5)
Max Horiz 12=66 (LC 9)
Max Uplift 7=-97 (LC 12), 12=-193 (LC 8)
Max Grav 7=1593 (LC 2), 12=2164 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-2559/499, 3-4=-2789/575, 4-5=-803/191
BOT CHORD 9-10=-440/2549, 8-9=-510/2779, 7-8=-120/793
WEBS 5-7=-1816/358, 2-12=-2000/453, 5-8=-154/924, 4-8=-2195/428, 3-10=-1050/264, 2-10=-604/2845, 3-9=-76/251

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 97 lb uplift at joint 7 and 193 lb uplift at joint 12.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC11	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:33 Page: 1
ID:PabKt5aiC9hQMBSs4T9vxZzcZCt-C1upu3kD0pVptfOKXBIVZd46jKOYJe9G70MvJPzcW1i



22-1-14 22-1-14



Scale = 1:34.1

0-2-12

Plate Offsets (X, Y): [4:Edge,0-3-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.74	Vert(LL)	-0.12	5-6	>910	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.42	Vert(CT)	-0.20	5-6	>535	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.68	Horz(CT)	0.02	5	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.00	5-6	>999	240		
BCDL	7.0										Weight: 52 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 5=411/ Mechanical, 6=663/0-5-8, (min. 0-1-11)
Max Horiz 6=64 (LC 9)
Max Uplift 5=-62 (LC 8), 6=-158 (LC 8)
Max Grav 5=998 (LC 2), 6=1610 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 4-5=-449/127
BOT CHORD 5-6=-283/1306
WEBS 2-6=-855/246, 3-5=-1270/328, 3-6=-1500/468

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 158 lb uplift at joint 6 and 62 lb uplift at joint 5.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC12	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:33 Page: 1
ID:iwW_LUf5YIaQiGUC?RnYk1zcZCm-C1upu3kD0pVptfOKXBIVZd47zKThJIMG70MvJPzcW1i



Scale = 1:29.9

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.66	Vert(LL)	-0.01	4-5	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.09	Vert(CT)	-0.01	4-5	>999	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.22	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.00	4-5	>999	240		
BCDL	7.0										Weight: 32 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=146/ Mechanical, 5=455/0-5-8, (min. 0-1-8)
Max Horiz 5=60 (LC 9)
Max Uplift 4=-17 (LC 12), 5=-133 (LC 8)
Max Grav 4=354 (LC 2), 5=1105 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-369/128
WEBS 2-5=-972/372

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 133 lb uplift at joint 5 and 17 lb uplift at joint 4.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC13	Common	1	2	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:34 Page: 1
ID:EH0SGm3onRkl9LWYQttHZ_zcZCF-gESB5Plrn6dgVpzW5vpk5rdL0kbo23hPLf5SrszcW1h



Scale = 1:56.2

Plate Offsets (X, Y): [2:0-3-8,0-2-8], [3:0-3-8,0-2-0], [7:0-3-8,0-2-0], [9:0-3-8,0-3-8], [13:0-3-8,0-3-8], [14:0-3-8,0-2-0], [17:0-3-8,0-2-0], [18:0-3-8,0-2-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.45	Vert(LL)	-0.49	14-16	>665	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.93	Vert(CT)	-0.58	14-16	>558	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.79	Horz(CT)	0.07	12	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.08	16	>999	240		
BCDL	7.0										Weight: 391 lb	FT = 20%

LUMBER
TOP CHORD 2x6 DF No.2
BOT CHORD 2x6 DF No.2
WEBS 2x4 DF Stud *Except* W4,W14:2x4 DF No.2
OTHERS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

REACTIONS (lb/size) 12=1614/0-7-12, (min. 0-2-1), 20=1514/0-5-8, (min. 0-1-15)
Max Horiz 20=-46 (LC 10)
Max Uplift 12=-287 (LC 9), 20=-245 (LC 8)
Max Grav 12=3919 (LC 2), 20=3676 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-251/22, 2-22=-6460/725, 3-22=-6449/726, 3-4=-10260/1189, 4-5=-11101/1292, 5-6=-11105/1292, 6-7=-10593/1229, 7-8=-6818/768, 8-23=-6821/768, 9-23=-6831/767
BOT CHORD 19-20=-37/251, 18-19=-37/251, 17-18=-665/6447, 16-17=-1124/10246, 15-16=-1164/10580, 14-15=-1164/10580, 13-14=-708/6816
WEBS 1-20=-16/340, 5-16=-495/90, 9-12=-3612/469, 2-20=-3504/457, 3-18=-2378/323, 2-18=-790/6612, 3-17=-487/4033, 4-17=-1322/191, 4-16=-643/1728, 9-13=-846/7158, 6-14=-1269/189, 6-16=-899/1536, 7-14=-484/3991, 7-13=-2334/318


NOTES
1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc, 2x6 - 2 rows staggered at 0-9-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Unbalanced roof live loads have been considered for this design.
4) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 28-0-11, Corner (3) 28-0-11 to 32-0-11 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
5) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
6) Provide adequate drainage to prevent water ponding.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 245 lb uplift at joint 20 and 287 lb uplift at joint 12.
10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC14	Common	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:34 Page: 1
ID:JW2FFzGXEAKZ9i9mHtgkd4zcZAh-gESB5Plrn6dgVpzW5vpk5rdEfkge21fPLf5SrszcW1h





Scale = 1:59.2

Plate Offsets (X, Y): [2:0-2-4,0-1-8], [6:0-3-8,0-2-8], [7:0-3-8,Edge], [15:0-2-4,0-1-8], [17:0-3-4,0-1-12], [19:0-1-12,0-1-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.92	Vert(LL)	-0.37	17-18	>684	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.62	Vert(CT)	-0.44	17-18	>573	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.92	Horz(CT)	0.03	14	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.06	17-18	>999	240		
BCDL	7.0										Weight: 158 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2 *Except* T2:2x4 DF 2100F 1.8E
BOT CHORD 2x4 DF No.2 *Except* B2:2x4 DF 2100F 1.8E
WEBS 2x4 DF Stud *Except* W11:2x4 DF 2100F 1.8E, W10,W4:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 8-14

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 13=314/0-7-12, (min. 0-1-8), 14=1897/0-7-12, (min. 0-4-15), 21=1112/0-5-8, (min. 0-2-14)
Max Horiz 21=-51 (LC 8)
Max Uplift 13=-336 (LC 30), 14=-229 (LC 13), 21=-215 (LC 8)
Max Grav 13=1221 (LC 31), 14=4608 (LC 2), 21=2700 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-23=-3782/411, 3-23=-3772/411, 3-4=-5127/593, 4-5=-4181/500, 5-6=-4181/500, 6-7=-1454/203, 7-8=-399/3724, 8-9=-105/476, 9-24=-105/467, 10-24=-106/461, 10-11=-109/475
BOT CHORD 18-19=-344/3771, 17-18=-522/5116, 16-17=-132/1443, 15-16=-132/1443, 14-15=-3712/464, 13-14=-1168/179
WEBS 2-21=-2535/338, 11-13=-577/177, 10-13=-778/119, 8-13=-212/1177, 5-17=-743/117, 7-14=-3380/424, 8-14=-2767/310, 7-15=-650/5620, 6-15=-2224/281, 6-17=-322/2996, 4-17=-1543/341, 3-19=-1554/224, 2-19=-502/4146, 3-18=-194/1466, 4-18=-525/101


NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 30-0-11, Corner (3) 30-0-11 to 34-0-11 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 215 lb uplift at joint 21, 336 lb uplift at joint 13 and 229 lb uplift at joint 14.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC15	Common	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:34 Page: 1
ID:YWd4jrar69csHi8mpK7qgZzcZAH-gESB5Plrn6dgVpzW5vpk5rdGhkc220jPLf5SrszcW1h





Scale = 1:56.8

Plate Offsets (X, Y): [2:0-3-8,0-2-0], [18:0-1-12,0-2-4]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.79	Vert(LL)	-0.25	17	>914	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.85	Vert(CT)	-0.30	17	>768	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.98	Horz(CT)	0.04	14	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.04	17	>999	240		
BCDL	7.0										Weight: 150 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2 *Except* T2:2x4 DF 2100F 1.8E
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W10,W4:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 6-14, 8-14

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 12=264/ Mechanical, 14=1898/0-7-12, (min. 0-4-15), 20=1004/0-5-8, (min. 0-2-10)
Max Horiz 20=-51 (LC 8)
Max Uplift 12=-210 (LC 30), 14=-234 (LC 9), 20=-207 (LC 8)
Max Grav 12=952 (LC 31), 14=4611 (LC 2), 20=2437 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-22=-3183/350, 3-22=-3173/351, 3-4=-3986/474, 4-5=-2520/311, 5-6=-2517/311, 6-7=-390/3612, 7-8=-394/3616, 8-23=-761/1055, 9-23=-762/1053, 11-12=-377/61
BOT CHORD 17-18=-284/3173, 16-17=-403/3975, 13-14=-1392/439, 12-13=-576/1219
WEBS 2-20=-2274/316, 7-14=-888/132, 5-16=-726/114, 6-16=-295/2822, 6-14=-4313/519, 3-18=-1306/200, 2-18=-438/3509, 3-17=-130/874, 4-17=-291/72, 4-16=-1800/183, 8-13=-79/885, 8-14=-3112/386, 9-13=-1071/163, 9-12=-1227/655

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 28-5-7, Corner (3) 28-5-7 to 32-5-7 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) All plates are 3x4 (=) MT20 unless otherwise indicated.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Refer to girder(s) for truss to truss connections.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 210 lb uplift at joint 12, 207 lb uplift at joint 20 and 234 lb uplift at joint 14.
10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC16	Common	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:34 Page: 1
ID:hjBG7Qod0Nfvkqdx1Gwkb9zcZ7Q-gESB5Plrn6dgVpzW5vpk5rdGXkfi21VPLf5SrszcW1h



22-1-14 22-1-14 22-1-14

Scale = 1:50.8

Plate Offsets (X, Y): [5:0-2-4,0-1-8], [14:0-2-0,0-2-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.80	Vert(LL)	-0.19	15-16	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.68	Vert(CT)	-0.23	15-16	>897	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.93	Horz(CT)	0.05	9	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.03	15	>999	240		
BCDL	7.0										Weight: 131 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2 *Except* T2:2x4 DF 2100F 1.8E
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W8:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 2-17

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 9=336/ Mechanical, 12=1696/0-7-12, (min. 0-4-6), 17=697/ Mechanical
Max Horiz 17=-54 (LC 8)
Max Uplift 9=-116 (LC 30), 12=-199 (LC 9), 17=-122 (LC 8)
Max Grav 9=1061 (LC 31), 12=4119 (LC 2), 17=1693 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-17=-435/75, 2-3=-3143/461, 3-18=-1426/222, 4-18=-1409/222, 4-19=-1416/222, 5-19=-1428/221, 5-6=-309/2482, 6-7=-854/989, 8-9=-379/68
BOT CHORD 16-17=-338/2843, 15-16=-338/2843, 14-15=-390/3132, 13-14=-2471/379, 12-13=-2471/379, 11-12=-988/845, 10-11=-351/1422, 9-10=-351/1422
WEBS 5-12=-2799/416, 4-14=-794/135, 5-14=-571/4230, 2-17=-2951/439, 2-15=-56/313, 3-14=-2007/272, 6-12=-2632/379, 7-9=-1463/397, 6-11=-46/521, 7-11=-1165/165

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 12-1-12, Exterior (2) 12-1-12 to 15-11-15, Corner (3) 15-11-15 to 27-11-15 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 122 lb uplift at joint 17, 116 lb uplift at joint 9 and 199 lb uplift at joint 12.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC17	Common	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:35 Page: 1
ID:tNPHZpLsPCKWdkaaADDIvezcZ6j-8Q0ZJlmUYQlX6zYifcKze2AQU80WnUSZaJr0OlzcW1g



Scale = 1:47.8

Plate Offsets (X, Y): [15:0-3-8,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.85	Vert(LL)	-0.13	15-16	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.58	Vert(CT)	-0.16	15-16	>999	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.95	Horz(CT)	0.03	9	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.02	15-16	>999	240		
BCDL	7.0										Weight: 124 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W8:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 9=369/ Mechanical, 12=1558/0-7-12, (min. 0-4-1), 17=606/ Mechanical
Max Horiz 17=-54 (LC 8)
Max Uplift 9=-79 (LC 13), 12=-168 (LC 9), 17=-112 (LC 8)
Max Grav 9=1112 (LC 31), 12=3783 (LC 2), 17=1523 (LC 30)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-17=-421/77, 2-3=-2428/355, 3-18=-2480/366, 4-18=-2461/366, 4-19=-371/306, 5-19=-372/295, 5-6=-267/2096, 6-7=-1056/795, 8-9=-382/72
BOT CHORD 16-17=-284/2418, 15-16=-290/2469, 14-15=-302/372, 13-14=-302/372, 12-13=-2087/340, 11-12=-794/1047, 10-11=-260/1487, 9-10=-260/1487
WEBS 4-13=-1682/267, 5-12=-2478/384, 5-13=-392/2736, 6-12=-2598/393, 7-9=-1541/300, 6-11=-35/438, 7-11=-938/140, 2-17=-2511/382, 3-15=-1011/183, 4-15=-359/2440


NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 12-1-12, Exterior (2) 12-1-12 to 13-11-15, Corner (3) 13-11-15 to 25-11-15 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 112 lb uplift at joint 17, 79 lb uplift at joint 9 and 168 lb uplift at joint 12.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC18	Common	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:35 Page: 1
ID:S4FaVbWe6W5XJueH_9TaUbzcZ6V-8Q0ZJlmUYQlX6zYifcKze2AOS82vnUEZaJr0OlzcW1g





Scale = 1:44.9

Plate Offsets (X, Y): [1:0-3-4,0-2-8], [3:0-3-12,0-5-4], [7:0-3-8,0-1-8], [10:0-6-0,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.98	Vert(LL)	-0.12	10	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.49	Vert(CT)	-0.14	10	>999	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.90	Horz(CT)	0.01	6	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.02	10	>999	240		
BCDL	7.0										Weight: 125 lb	FT = 20%

LUMBER
TOP CHORD 2x6 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W1,W4:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 4-8

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 6=410/ Mechanical, 8=1404/0-7-12, (min. 0-3-10), 11=523/ Mechanical
Max Horiz 11=52 (LC 9)
Max Uplift 6=-82 (LC 9), 8=-137 (LC 12), 11=-99 (LC 8)
Max Grav 6=1154 (LC 31), 8=3413 (LC 2), 11=1354 (LC 30)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-11=-1289/223, 1-2=-2550/364, 2-3=-2317/326, 3-4=-223/1529, 4-5=-1788/337, 5-6=-1092/171
BOT CHORD 10-11=-34/270, 9-10=-930/190, 8-9=-930/190, 7-8=-335/1776
WEBS 1-10=-352/2338, 2-10=-1488/290, 3-10=-468/3064, 3-8=-2377/419, 4-8=-2924/486, 4-7=-430/172, 5-7=-381/1645


NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) All plates are MT20 plates unless otherwise indicated.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Refer to girder(s) for truss to truss connections.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 99 lb uplift at joint 11, 82 lb uplift at joint 6 and 137 lb uplift at joint 8.
10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC19	Common	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:35 Page: 1
ID:M?iVuTCS8Xkg6PLBBZ_P97zcZ4J-8Q0ZJlmUYQlX6zYifcKze2APY82EnTzZaJr0OlzcW1g





Scale = 1:41.9

Plate Offsets (X, Y): [3:0-3-7,0-2-0], [8:0-3-8,0-1-8], [11:0-3-8,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.91	Vert(LL)	-0.08	11	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.47	Vert(CT)	-0.09	11	>999	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.98	Horz(CT)	0.01	7	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.01	11	>999	240		
BCDL	7.0										Weight: 117 lb	FT = 20%

LUMBER
TOP CHORD 2x6 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W4:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 7=429/ Mechanical, 9=1288/0-7-12, (min. 0-3-5), 12=425/ Mechanical
Max Horiz 12=54 (LC 9)
Max Uplift 7=-80 (LC 13), 9=-138 (LC 12), 12=-87 (LC 8)
Max Grav 7=1128 (LC 31), 9=3126 (LC 2), 12=1146 (LC 30)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-12=-586/117, 2-3=-1743/262, 3-4=-140/1131, 4-5=-1621/278, 6-7=-595/122
BOT CHORD 11-12=-192/1731, 10-11=-1135/214, 9-10=-1135/214, 8-9=-462/85, 7-8=-206/1610
WEBS 4-9=-1419/232, 4-8=-309/1874, 5-8=-795/180, 5-7=-1509/221, 3-9=-1958/358, 2-11=-861/188, 2-12=-1622/257, 3-11=-431/2671

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 87 lb uplift at joint 12, 80 lb uplift at joint 7 and 138 lb uplift at joint 9.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FC20	Common	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:36 Page: 1
ID:kPFE2V7Zx3eF3hQYRkpSZRzcZ1r-8Q0ZJlmUYQlX6zYifcKze2ATI83AnWdZaJr0OIzcW1g






Plate Offsets (X, Y): [9:0-3-0,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.67	Vert(LL)	-0.07	8-9	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.41	Vert(CT)	-0.12	8-9	>999	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.81	Horz(CT)	0.02	8	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.01	8-9	>999	240		
BCDL	7.0										Weight: 96 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 8=454/ Mechanical, 10=1158/0-7-12, (min. 0-3-0), 14=335/ Mechanical
Max Horiz 14=59 (LC 9)
Max Uplift 8=-76 (LC 13), 10=-145 (LC 12), 14=-69 (LC 8)
Max Grav 8=1102 (LC 2), 10=2815 (LC 2), 14=902 (LC 30)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-14=-306/64, 2-3=-682/218, 3-4=-137/975, 4-5=-879/181, 5-6=-880/181, 7-8=-381/83
BOT CHORD 13-14=-87/978, 12-13=-87/978, 11-12=-87/978, 10-11=-218/674, 9-10=-967/206, 8-9=-235/1381
WEBS 4-10=-1867/354, 4-9=-358/2105, 5-9=-704/155, 6-9=-646/145, 6-8=-1437/294, 2-14=-1069/183, 3-10=-1608/268, 2-11=-520/79, 3-11=-16/287

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 69 lb uplift at joint 14, 76 lb uplift at joint 8 and 145 lb uplift at joint 10.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FCGR	Common Girder	1	4	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:36 Page: 1
ID:y?3IdF96n2EtGtVP5tXk2wzcY57-ccayW5m6JktOk77vCJrCAGia8XJlWxYipzaZwkzcW1f



Scale = 1:53.9

Plate Offsets (X, Y): [2:0-2-0,0-2-0], [3:0-3-8,0-2-0], [10:0-3-8,0-2-0], [12:0-3-0,0-1-8], [16:0-3-8,0-2-8], [17:0-1-12,0-2-0], [21:0-3-8,0-2-0], [22:0-3-8,0-2-0], [23:0-2-0,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.92	Vert(LL)	-0.77	18-20	>430	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.80	Vert(CT)	-0.90	18-20	>367	240	M18AHS	132/127
TCDL	12.0	Rep Stress Incr	NO	WB	0.96	Horz(CT)	0.09	15	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH		Wind(LL)	0.12	18-20	>999	240		
BCDL	7.0										Weight: 877 lb	FT = 20%

LUMBER

TOP CHORD	2x6 DF 1950F 1.5E or 2x6 DF SS *Except* T4,T1:2x6 DF No.2
BOT CHORD	2.0 RigidLam DF LVL 1-1/2 x 7-1/4 *Except* B1:2x8 DF 2250F 1.6E or 2x8 DF SS
WEBS	2x4 DF Stud *Except* W14,W4,W6,W8:2x4 DF No.2, W15:2x4 DF 2100F 1.8E

BRACING

TOP CHORD	Structural wood sheathing directly applied or 3-10-14 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 25-26,14-15.

REACTIONS (lb/size) 15=5379/0-5-15, (min. 0-2-15), 25=3316/0-5-15, (min. 0-2-3)
Max Horiz 25=-43 (LC 42)
Max Uplift 15=-837 (LC 7), 25=-620 (LC 6)
Max Grav 15=13331 (LC 2), 25=8312 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-26=-758/61, 1-2=-1240/99, 2-3=-14862/1009, 3-4=-27481/1785, 4-5=-35836/2246, 5-6=-35826/2247, 6-7=-39949/2391, 7-8=-41056/2457, 8-9=-35893/2128, 9-10=-35896/2125, 10-11=-22819/1351, 11-12=-22832/1350, 12-13=-2363/148, 13-14=-1512/95

BOT CHORD 24-25=-115/1243, 24-27=-115/1243, 23-27=-115/1243, 23-28=-985/14846, 22-28=-985/14846, 22-29=-1759/27469, 29-30=-1759/27469, 21-30=-1759/27469, 21-31=-2218/35823, 20-31=-2218/35823, 20-32=-2398/39937, 19-32=-2398/39937, 18-19=-2398/39937, 18-33=-2464/41045, 17-33=-2464/41045, 17-34=-1365/22813, 16-34=-1365/22813, 16-35=-148/2367, 15-35=-148/2367

WEBS 1-25=-110/1512, 13-15=-169/2880, 2-25=-7510/537, 12-15=-11150/693, 7-20=-552/591, 7-18=-1078/2549, 8-18=-177/2182, 8-17=-5758/414, 9-17=-739/84, 10-17=-849/14251, 10-16=-6402/415, 12-16=-1337/22474, 3-23=-6561/433, 2-23=-1009/14858, 3-22=-857/13890, 4-22=-4937/310, 4-21=-564/9260, 6-21=-2772/163, 6-20=-317/5498

NOTES

1) 4-ply truss to be connected together with 10d (0.131"x3") nails as follows:
   Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc, 2x6 - 2 rows staggered at 0-6-0 oc.
   Bottom chords connected as follows: 2x8 - 4 rows staggered at 0-4-0 oc.
   Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
   Attach TC w/ 1/2" diam. bolts (ASTM A-307) in the center of the member w/washers at 4-0-0 oc.
   Attach BC w/ 1/2" diam. bolts (ASTM A-307) in the center of the member w/washers at 4-0-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Unbalanced roof live loads have been considered for this design.
4) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
5) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
6) Provide adequate drainage to prevent water ponding.
7) All plates are MT20 plates unless otherwise indicated.

Continued on page 2


8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 620 lb uplift at joint 25 and 837 lb uplift at joint 15.
11) Use Simpson Strong-Tie TJC37 (4 nail, 22-30) or equivalent at 4-10-13 from the left end to connect truss(es) FC7 (1 ply 2x4 DF) to front face of bottom chord, skewed 67.5 deg.to the left, sloping 0.0 deg. down.
12) Use Simpson Strong-Tie THASL29 (23 to 74 Skewed Left) or equivalent at 10-1-8 from the left end to connect truss(es) FC6 (1 ply 2x4 DF) to front face of bottom chord, skewed 67.5 deg.to the left, sloping 0.0 deg. down.
13) Use Simpson Strong-Tie THASL29 (46 to 85 Skewed Left Screws) or equivalent at 15-4-4 from the left end to connect truss(es) FC5 (1 ply 2x4 DF) to front face of bottom chord, skewed 67.5 deg.to the left, sloping 0.0 deg. down.
14) Use Simpson Strong-Tie TJC37 (6 nail, 150-157) or equivalent at 7-1-5 from the left end to connect truss(es) FC12 (1 ply 2x4 DF) to back face of bottom chord, skewed 67.5 deg.to the right, sloping 0.0 deg. down.
15) Use Simpson Strong-Tie THASR29 (23 to 74 Skewed Right) or equivalent at 12-4-1 from the left end to connect truss(es) FC11 (1 ply 2x4 DF) to back face of bottom chord, skewed 67.5 deg.to the right, sloping 0.0 deg. down.
16) Use Simpson Strong-Tie THASR29 (46 to 85 Skewed Right Screws) or equivalent at 17-6-12 from the left end to connect truss(es) FC10 (1 ply 2x4 DF) to back face of bottom chord, skewed 67.5 deg.to the right, sloping 0.0 deg. down.
17) Fill all nail holes where hanger is in contact with lumber.
18) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 1894 lb down and 101 lb up at 20-6-15, 2141 lb down and 109 lb up at 22-9-8, and 2476 lb down and 141 lb up at 25-9-11, and 2721 lb down and 162 lb up at 28-0-3 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard

1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-13=-84, 14-26=-14
Concentrated Loads (lb)
Vert: 17=-860, 27=40, 28=-109, 29=-267, 30=-374, 31=-516, 32=-619, 33=-758, 34=-998, 35=-1099

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD1	Half Hip	2	**2**	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:36 Page: 1
ID:qaRXU0Ny5NVzCZIZPrP_J0zhUt6-ccayW5m6JktOk77vCJrCAGielXHGWzBipzaZwkzcW1f






Plate Offsets (X, Y): [3:0-2-8,0-3-4], [5:0-0-8,0-1-8], [8:0-4-0,0-3-4], [9:0-3-8,0-2-8]

Loading	(psf)	**Spacing**	2-0-0	**CSI**		**DEFL**	in	(loc)	l/defl	L/d	**PLATES**	**GRIP**
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.69	Vert(LL)	-0.37	8	>630	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.93	Vert(CT)	-0.44	8-9	>529	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.79	Horz(CT)	0.07	6	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.08	8	>999	240		
BCDL	7.0										Weight: 172 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W2:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.


REACTIONS (lb/size) 6=944/ Mechanical, 10=944/ Mechanical
Max Horiz 10=54 (LC 9)
Max Uplift 6=-162 (LC 12), 10=-164 (LC 8)
Max Grav 6=2292 (LC 2), 10=2292 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-10=-2200/424, 1-2=-6388/1168, 2-3=-7938/1463, 3-4=-5656/1054, 4-5=-273/74, 5-6=-510/112
BOT CHORD 9-10=-45/427, 8-9=-1130/6375, 7-8=-1420/7927, 6-7=-1005/5643
WEBS 1-9=-1134/6138, 2-9=-1520/324, 2-8=-301/1614, 3-8=-365/108, 3-7=-2373/432, 4-7=-77/669, 4-6=-5646/1035

NOTES
1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Unbalanced roof live loads have been considered for this design.
4) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
5) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
6) Provide adequate drainage to prevent water ponding.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Refer to girder(s) for truss to truss connections.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 164 lb uplift at joint 10 and 162 lb uplift at joint 6.
11) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD2	Half Hip	2	**2**	Job Reference (optional)







Scale = 1:44.6

Loading	(psf)	**Spacing**	2-0-0			
TCLL (roof)	100.0	Plate Grip DOL	1.00			
Snow (Pf)	0.0	Lumber DOL	1.00			
TCDL	12.0	Rep Stress Incr	YES			
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		
BCDL	7.0					

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD3	Half Hip	2	**2**	Job Reference (optional)







Scale = 1:40.8

Loading	(psf)	**Spacing**	2-0-0			
TCLL (roof)	100.0	Plate Grip DOL	1.00			
Snow (Pf)	0.0	Lumber DOL	1.00			
TCDL	12.0	Rep Stress Incr	YES			
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		
BCDL	7.0					

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD4	Half Hip	2	**2**	Job Reference (optional)







Scale = 1:43.7

Loading	(psf)	**Spacing**	2-0-0			
TCLL (roof)	100.0	Plate Grip DOL	1.00			
Snow (Pf)	0.0	Lumber DOL	1.00			
TCDL	12.0	Rep Stress Incr	YES			
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		
BCDL	7.0					

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD5	Half Hip	2	**2**	Job Reference (optional)

ID:alFYJKLWYITJjpxVxrclV4zhUZm-4p8KjRnk41?FMHi5m1MRjTFzGxr1Fcnr2dK7SBzcW1e







Scale = 1:44.4

Loading	(psf)	**Spacing**	2-0-0			
TCLL (roof)	100.0	Plate Grip DOL	1.00			
Snow (Pf)	0.0	Lumber DOL	1.00			
TCDL	12.0	Rep Stress Incr	YES			
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		
BCDL	7.0					

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD6	Half Hip	2	**2**	Job Reference (optional)







Scale = 1:44.3

Loading	(psf)	**Spacing**	2-0-0			
TCLL (roof)	100.0	Plate Grip DOL	1.00			
Snow (Pf)	0.0	Lumber DOL	1.00			
TCDL	12.0	Rep Stress Incr	YES			
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		
BCDL	7.0					

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD7	Half Hip	2	**2**	Job Reference (optional)







Scale = 1:44.2

Loading	(psf)	**Spacing**	2-0-0			
TCLL (roof)	100.0	Plate Grip DOL	1.00			
Snow (Pf)	0.0	Lumber DOL	1.00			
TCDL	12.0	Rep Stress Incr	YES			
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		
BCDL	7.0					

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD8	Half Hip Girder	2	**3**	Job Reference (optional)






Scale = 1:44.2

Loading	(psf)	**Spacing**	2-0-0			
TCLL (roof)	100.0	Plate Grip DOL	1.00			
Snow (Pf)	0.0	Lumber DOL	1.00			
TCDL	12.0	Rep Stress Incr	NO			
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MSH		
BCDL	7.0					

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD9	Jack-Closed	8	1	Job Reference (optional)




Scale = 1:37.6

Loading	(psf)	Spacing	2-0-0			
TCLL (roof)	100.0	Plate Grip DOL	1.00			
Snow (Pf)	0.0	Lumber DOL	1.00			
TCDL	12.0	Rep Stress Incr	YES			
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		
BCDL	7.0					

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD10	Jack-Closed	1	1	Job Reference (optional)


Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:38 Page: 1
ID:4f4BCoQmGH02k5WMSFAOw8zhUX5-Y?iixnoMrL76zQHHKkugGhn80LBG_21?GH3g_dzcW1d



Scale = 1:37.6

Loading	(psf)	Spacing	2-0-0			
TCLL (roof)	100.0	Plate Grip DOL	1.00			
Snow (Pf)	0.0	Lumber DOL	1.00			
TCDL	12.0	Rep Stress Incr	YES			
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP		
BCDL	7.0					


Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD11	Jack-Closed	1	1	Job Reference (optional)



Scale = 1:37.5

Loading	(psf)	Spacing	2-0-0			
TCLL (roof)	100.0	Plate Grip DOL	1.00			
Snow (Pf)	0.0	Lumber DOL	1.00			
TCDL	12.0	Rep Stress Incr	YES			
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS		
BCDL	7.0					

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD12	Jack-Closed	8	1	Job Reference (optional)




Scale = 1:41.7

Loading	(psf)	Spacing	2-0-0			
TCLL (roof)	100.0	Plate Grip DOL	1.00			
Snow (Pf)	0.0	Lumber DOL	1.00			
TCDL	12.0	Rep Stress Incr	YES			
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		
BCDL	7.0					

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD13	Jack-Closed	1	1	Job Reference (optional)


Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:39 Page: 1
ID:HVT9m17eNhHJjvdp46pFhmzhU1B-0BG486p_cfFzbarUuSPvouKJmlXVjVG8VxpDX3zcW1c



Scale = 1:42.3

Loading	(psf)	Spacing	2-0-0			
TCLL (roof)	100.0	Plate Grip DOL	1.00			
Snow (Pf)	0.0	Lumber DOL	1.00			
TCDL	12.0	Rep Stress Incr	YES			
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		
BCDL	7.0					

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD14	Jack-Closed	1	1	Job Reference (optional)




Scale = 1:42.3

Loading	(psf)	Spacing	2-0-0			
TCLL (roof)	100.0	Plate Grip DOL	1.00			
Snow (Pf)	0.0	Lumber DOL	1.00			
TCDL	12.0	Rep Stress Incr	YES			
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		
BCDL	7.0					

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD15	Half Hip	1	1	Job Reference (optional)


Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:39 Page: 1
ID:x7tlYsn9oi2c5pmnkeAaBmzhUSl-0BG486p_cfFzbarUuSPvouKJmlXVjVG8VxpDX3zcW1c



Scale = 1:48.5

Loading	(psf)	Spacing	2-0-0			
TCLL (roof)	100.0	Plate Grip DOL	1.00			
Snow (Pf)	0.0	Lumber DOL	1.00			
TCDL	12.0	Rep Stress Incr	YES			
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		
BCDL	7.0					


Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD16	Flat	1	1	Job Reference (optional)



Scale = 1:26.8

Loading	(psf)	Spacing	2-0-0			
TCLL (roof)	100.0	Plate Grip DOL	1.00			
Snow (Pf)	0.0	Lumber DOL	1.00			
TCDL	12.0	Rep Stress Incr	YES			
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP		
BCDL	7.0					


Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD17	Monopitch	22	1	Job Reference (optional)



Scale = 1:28.5

Loading	(psf)	Spacing	2-0-0			
TCLL (roof)	100.0	Plate Grip DOL	1.00			
Snow (Pf)	0.0	Lumber DOL	1.00			
TCDL	12.0	Rep Stress Incr	YES			
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP		
BCDL	7.0					

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD18	Jack-Closed	1	1	Job Reference (optional)




Scale = 1:36.2

Loading	(psf)	Spacing	2-0-0			
TCLL (roof)	100.0	Plate Grip DOL	1.00			
Snow (Pf)	0.0	Lumber DOL	1.00			
TCDL	12.0	Rep Stress Incr	YES			
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP		
BCDL	7.0					

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD19	Common	5	**2**	Job Reference (optional)


Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:40 Page: 1
ID:Fj73q0LV6XdfvFOLbSS3FGzhUPS-VNpSMSqcNyNqDkQgR9w8L6tUW9tkSyWIkbYn3WzcW1b




Scale = 1:64.9

Loading	(psf)	**Spacing**	2-0-0			
TCLL (roof)	100.0	Plate Grip DOL	1.00			
Snow (Pf)	0.0	Lumber DOL	1.00			
TCDL	12.0	Rep Stress Incr	YES			
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS		
BCDL	7.0					

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD20	Half Hip	3	**2**	Job Reference (optional)







Scale = 1:42.8

Loading	(psf)	**Spacing**	2-0-0			
TCLL (roof)	100.0	Plate Grip DOL	1.00			
Snow (Pf)	0.0	Lumber DOL	1.00			
TCDL	12.0	Rep Stress Incr	YES			
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		
BCDL	7.0					

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD21	Monopitch	1	1	Job Reference (optional)

Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:41 Page: 1
ID:uqWu72dZlIDRNeSNLoo4bwzhUJw-zaNrZoqE8GVhqu?s?tRNtJPfGYCzBPmRyFIKbyzcW1a







Scale = 1:57.1

Loading	(psf)	Spacing	2-0-0			
TCLL (roof)	100.0	Plate Grip DOL	1.00			
Snow (Pf)	0.0	Lumber DOL	1.00			
TCDL	12.0	Rep Stress Incr	YES			
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS		
BCDL	7.0					

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD22	Monopitch	4	**2**	Job Reference (optional)

ID:nyOXpUiNneRpYKmU2_vyihzhUIX-zaNrZoqE8GVhqu?s?tRNtJPfGYCzBPmRyFIKbyzcW1a






Scale = 1:56.5

Loading	(psf)	**Spacing**	2-0-0			
TCLL (roof)	100.0	Plate Grip DOL	1.00			
Snow (Pf)	0.0	Lumber DOL	1.00			
TCDL	12.0	Rep Stress Incr	YES			
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		
BCDL	7.0					

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD23	Half Hip	4	2	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:41 Page: 1
ID:r4c_9_q8bmE6sBG591q4p2zhXT4-zaNrZoqE8GVhqu?s?tRNtJPSXY2LBCtRyFlKbyzcW1a



Scale = 1:43.9

Plate Offsets (X, Y): [2:0-3-4,0-3-0], [8:0-8-12,0-3-0], [9:Edge,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.88	Vert(LL)	-0.57	12-13	>477	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.68	Vert(CT)	-0.68	12-13	>400	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.89	Horz(CT)	0.05	10	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.11	12-13	>999	240		
BCDL	7.0										Weight: 231 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2 *Except* T3:2x6 DF No.2
BOT CHORD 2x4 DF 2100F 1.8E *Except* B1:2x4 DF No.2
WEBS 2x4 DF Stud *Except* W4:2x4 DF No.2
OTHERS 2x6 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 8-9.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 8-10

REACTIONS (lb/size) 10=1111/0-5-8, (min. 0-1-8), 20=1269/0-4-0, (min. 0-1-8)
Max Horiz 20=55 (LC 9)
Max Uplift 10=-192 (LC 8), 20=-246 (LC 8)
Max Grav 10=2699 (LC 2), 20=3097 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-539/96, 3-4=-7561/1199, 4-5=-7569/1203, 5-6=-10477/1664, 6-25=-10467/1664, 7-25=-10467/1664, 7-8=-10303/1644, 8-9=-421/91, 9-10=-698/134
BOT CHORD 16-17=-686/4562, 15-16=-686/4562, 14-15=-1616/10465, 13-14=-1616/10465, 12-13=-1591/10291, 11-12=-1143/7447, 10-11=-1138/7446
WEBS 8-10=-7282/1143, 8-12=-480/3047, 4-15=-783/153, 5-15=-3061/481, 7-13=-335/184, 7-12=-999/189, 3-15=-555/3511, 3-17=-4666/727, 2-20=-1406/225, 17-20=-367/2410, 2-20=-367/2410

NOTES
1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-6-0 oc, 2x6 - 2 rows staggered at 0-9-0 oc.
Bottom chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-2-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Unbalanced roof live loads have been considered for this design.
4) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 12-1-12, Exterior (2) 12-1-12 to 12-6-8, Corner (3) 12-6-8 to 24-6-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
5) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
6) Provide adequate drainage to prevent water ponding.
7) All plates are MT20 plates unless otherwise indicated.
8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
10) Bearing at joint(s) 20 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
11) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 192 lb uplift at joint 10 and 246 lb uplift at joint 20.
12) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.


Continued on page 2

13) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD24	Monopitch	2	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:41 Page: 1
ID:WpgiTltnq1U113sC5FWEZ1zhU8_-zaNrZoqE8GVhqu?s?tRNtJPVoY7BBlyRyFlKbyzcW1a




22-11-8 23-1-14

2-2-6

1-11-12

1-6-6

1-6-4 9-3-2



0-2-10 0-3-8

0-0-2

0-5-6

0-2-10

Scale = 1:42.3

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.67	Vert(LL)	-0.06	5-6	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.37	Vert(CT)	-0.11	5-6	>838	240	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.50	Horz(CT)	0.01	17	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.00	7	>999	240		
BCDL	7.0										Weight: 41 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W7:2x4 DF No.2
OTHERS 2x8 DF 2250F 1.6E or 2x8 DF SS *Except* BL2:2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 12=530/0-5-4, (min. 0-1-8), 17=314/0-2-8, (min. 0-1-8)
Max Horiz 12=37 (LC 9)
Max Uplift 12=-120 (LC 8), 17=-55 (LC 12)
Max Grav 12=1296 (LC 2), 17=762 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-411/93, 5-17=-59/308, 4-17=-59/308
BOT CHORD 5-6=-335/1233
WEBS 3-6=-1278/379, 3-5=-869/281, 6-12=-156/628, 2-12=-156/628, 4-17=-1048/280


NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) All plates are MT20 plates unless otherwise indicated.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Bearing at joint(s) 12, 17 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
9) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 17.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 120 lb uplift at joint 12 and 55 lb uplift at joint 17.
11) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD25	Monopitch	6	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:42 Page: 1
ID:JnvaGLpnvVmBrog91Zu?a_zhU5T-RmxDn8rtvadYS2a2ZaycQXydVyTQwkabBv1u7OzcW1Z





Scale = 1:28.9

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.80	Vert(LL)	-0.05	4-5	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.37	Vert(CT)	-0.08	4-5	>999	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.54	Horz(CT)	0.02	8	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.00	4	>999	240		
BCDL	7.0										Weight: 40 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W5:2x4 DF No.2
OTHERS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 5=535/0-5-8, (min. 0-1-8), 8=315/0-2-8, (min. 0-1-8)
Max Horiz 5=37 (LC 9)
Max Uplift 5=-123 (LC 8), 8=-54 (LC 12)
Max Grav 5=1299 (LC 2), 8=766 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-185/415, 2-3=-372/85, 4-8=-70/355, 3-8=-70/355
BOT CHORD 4-5=-355/1368
WEBS 1-5=-762/307, 2-5=-1932/608, 2-4=-1051/311, 3-8=-1030/270

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Bearing at joint(s) 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
8) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 8.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 123 lb uplift at joint 5 and 54 lb uplift at joint 8.
10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard


Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FD26	Monopitch	8	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:42 Page: 1
ID:rDWlTt177XUsTKuZRHChAHzhU3u-RmxDn8rtvadYS2a2ZaycQXyhPyTHwiObBv1u7OzcW1Z



23-1-6 22-9-12

1-11-12 9-3-7



Scale = 1:29.1

0-5-8 0-3-8

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.55	Vert(LL)	-0.03	6	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.38	Vert(CT)	-0.04	6-7	>999	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.68	Horz(CT)	0.01	16	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.01	6	>999	240		
BCDL	7.0										Weight: 43 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud
OTHERS 2x6 DF No.2 *Except* BL2:2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 10=526/0-4-0, (min. 0-1-8), 16=316/0-3-0, (min. 0-1-8)
Max Horiz 10=32 (LC 9)
Max Uplift 10=-119 (LC 8), 16=-56 (LC 12)
Max Grav 10=1293 (LC 2), 16=768 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-333/87, 5-16=-93/414, 4-16=-93/414
BOT CHORD 6-7=-315/1270, 5-6=-315/1270
WEBS 3-7=-1188/308, 3-5=-1011/261, 7-10=-106/458, 2-10=-106/458, 4-16=-853/225

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Bearing at joint(s) 10, 16 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
8) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 16.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 119 lb uplift at joint 10 and 56 lb uplift at joint 16.
10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FJ1	Half Hip	1	1	Job Reference (optional)



Scale = 1:29.8

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.42	Vert(LL)	-0.03	5-6	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.18	Vert(CT)	-0.05	5-6	>999	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.24	Horz(CT)	0.00	5	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.00	5-6	>999	240		
BCDL	7.0										Weight: 39 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins: 2-4.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 5=226/ Mechanical, 6=529/0-5-8, (min. 0-1-8)
Max Horiz 6=58 (LC 9)
Max Uplift 5=-49 (LC 9), 6=-144 (LC 8)
Max Grav 5=549 (LC 2), 6=1286 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-161/330, 2-3=-145/284
BOT CHORD 5-6=-70/437
WEBS 1-6=-412/181, 2-6=-504/164, 3-6=-849/327, 3-5=-523/121

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 144 lb uplift at joint 6 and 49 lb uplift at joint 5.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FJ2	Jack-Closed	1	1	Job Reference (optional)



Scale = 1:30.4

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.65	Vert(LL)	-0.03	5-6	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.19	Vert(CT)	-0.05	5-6	>999	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.15	Horz(CT)	0.00	5	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.00	5-6	>999	240		
BCDL	7.0										Weight: 39 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2 *Except* T2:2x4 DF 2100F 1.8E
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

REACTIONS (lb/size) 5=238/ Mechanical, 6=518/0-5-8, (min. 0-1-8)
Max Horiz 6=60 (LC 9)
Max Uplift 5=-51 (LC 9), 6=-139 (LC 8)
Max Grav 5=578 (LC 2), 6=1257 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 4-5=-432/140
WEBS 1-6=-265/131, 3-5=-271/48, 2-6=-551/181, 3-6=-641/244

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins: 3-4.
BOT CHORD Rigid ceiling directly applied.


MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 51 lb uplift at joint 5 and 139 lb uplift at joint 6.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FJ3	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:42 Page: 1
ID:4ZVN2ccaz8zQjKQJp1cKvYzcYWx-RmxDn8rtvadYS2a2ZaycQXygoyWFwpubBv1u7OzcW1Z



2-2-12

Scale = 1:30.5

0-2-12

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.59	Vert(LL)	-0.03	5-6	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.19	Vert(CT)	-0.05	5-6	>999	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.20	Horz(CT)	0.00	5	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.00	5-6	>999	240		
BCDL	7.0										Weight: 39 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins: 3-4.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 5=238/ Mechanical, 6=518/0-5-8, (min. 0-1-8)
Max Horiz 6=62 (LC 9)
Max Uplift 5=-51 (LC 9), 6=-138 (LC 8)
Max Grav 5=578 (LC 2), 6=1257 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
BOT CHORD 5-6=-57/342
WEBS 3-5=-481/121, 2-6=-879/287, 3-6=-490/217


NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 51 lb uplift at joint 5 and 138 lb uplift at joint 6.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FJ4	Jack-Closed	12	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:43 Page: 1
ID:4ZVN2ccaz8zQjKQJp1cKvYzcYWx-vyVb_UsVgtlP4C9F7ITrzkVvIMsUfGrkQZnRgqzcW1Y





Scale = 1:29.9

0-2-12

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.35	Vert(LL)	-0.03	5-6	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.19	Vert(CT)	-0.05	5-6	>999	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.22	Horz(CT)	0.00	5	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.00	5-6	>999	240		
BCDL	7.0										Weight: 39 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 5=238/ Mechanical, 6=518/0-5-8, (min. 0-1-8)
Max Horiz 6=61 (LC 9)
Max Uplift 5=-27 (LC 8), 6=-138 (LC 8)
Max Grav 5=578 (LC 2), 6=1257 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 4-5=-254/82
BOT CHORD 5-6=-77/453
WEBS 2-6=-605/197, 3-5=-539/132, 3-6=-764/294

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 138 lb uplift at joint 6 and 27 lb uplift at joint 5.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FJ5	Jack-Closed	2	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:43 Page: 1
ID:4ZVN2ccaz8zQjKQJp1cKvYzcYWx-vyVb_UsVgtlP4C9F7ITrzkVsUMtLfG8kQZnRgqzcW1Y



Scale = 1:29.9

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.53	Vert(LL)	0.00	4-5	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.07	Vert(CT)	-0.01	4-5	>999	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.20	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS		Wind(LL)	0.00	4-5	>999	240		
BCDL	7.0										Weight: 30 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=113/ Mechanical, 5=438/0-5-8, (min. 0-1-8)
Max Horiz 5=60 (LC 9)
Max Uplift 4=-18 (LC 9), 5=-133 (LC 8)
Max Grav 4=275 (LC 2), 5=1063 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-321/114
WEBS 2-5=-899/357

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 133 lb uplift at joint 5 and 18 lb uplift at joint 4.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FJ6	Jack-Closed	2	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:43 Page: 1
ID:4ZVN2ccaz8zQjKQJp1cKvYzcYWx-vyVb_UsVgtlP4C9F7ITrzkVxrMuffHckQZnRgqzcW1Y



Scale = 1:29.9

0-2-12

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.25	Vert(LL)	n/a	-	n/a	999	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.05	Vert(CT)	0.00	4-5	>999	240		
TCDL	12.0	Rep Stress Incr	YES	WB	0.17	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 22 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 3-10-15 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=-63/ Mechanical, 5=418/0-5-8, (min. 0-1-8)
Max Horiz 5=59 (LC 9)
Max Uplift 4=-153 (LC 2), 5=-160 (LC 8)
Max Grav 4=64 (LC 8), 5=1015 (LC 2)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 1-5=-286/125, 2-5=-782/359, 2-4=-214/335

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 160 lb uplift at joint 5 and 153 lb uplift at joint 4.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FJ7	Jack-Closed	2	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:43 Page: 1
ID:4ZVN2ccaz8zQjKQJp1cKvYzcYWx-vyVb_UsVgtlP4C9F7ITrzkVyxMu8fJLkQZnRgqzcW1Y



Scale = 1:24.5

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.18	Vert(LL)	n/a	-	n/a	999	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.02	Vert(CT)	n/a	-	n/a	999		
TCDL	12.0	Rep Stress Incr	YES	WB	0.06	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 12 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

REACTIONS (lb/size) 2=0/ Mechanical, 3=159/ Mechanical
Max Horiz 2=179 (LC 2), 3=-179 (LC 2)
Max Uplift 3=-54 (LC 8)
Max Grav 3=386 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 1-3=-260/114

BRACING
TOP CHORD Structural wood sheathing directly applied or 1-10-15 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.


MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Refer to girder(s) for truss to truss connections.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 54 lb uplift at joint 3.
10) Non Standard bearing condition. Review required.
11) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FJ8	Diagonal Hip Girder	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 22:52:43 Page: 1
ID:4ZVN2ccaz8zQjKQJp1cKvYzcYWx-vyVb_UsVgtlP4C9F7ITrzkVpBMief8skQZnRgqzcW1Y



Scale = 1:35

Plate Offsets (X, Y): [2:0-3-8,0-1-8], [4:0-0-8,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.74	Vert(LL)	-0.09	5-6	>999	360	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.82	Vert(CT)	-0.10	5-6	>929	240		
TCDL	12.0	Rep Stress Incr	NO	WB	0.73	Horz(CT)	0.00	5	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MSH		Wind(LL)	-0.02	6-7	>999	240		
BCDL	7.0										Weight: 53 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF 2100F 1.8E
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 4-11-9 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 5=441/ Mechanical, 7=1020/0-7-12, (min. 0-2-13)
Max Horiz 7=54 (LC 7)
Max Uplift 5=-104 (LC 10), 7=-376 (LC 6)
Max Grav 5=1143 (LC 2), 7=2621 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-91/455, 2-3=-1309/198, 4-5=-411/24
BOT CHORD 7-10=-449/115, 6-10=-449/115, 6-11=-176/1302, 5-11=-176/1302
WEBS 1-7=-552/99, 2-7=-1641/198, 2-6=-254/1892, 3-6=-690/151, 3-5=-1273/199


NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 376 lb uplift at joint 7 and 104 lb uplift at joint 5.
9) Use Simpson Strong-Tie SUL24 (4-10dx1 1/2 Girder, 4-10dx1 1/2 Truss, Single Ply Girder) or equivalent spaced at 5-7-14 oc max. starting at 2-9-8 from the left end to 8-5-6 to connect truss(es) FJ7 (1 ply 2x4 DF), FJ5 (1 ply 2x4 DF) to front face of bottom chord.
10) Use Simpson Strong-Tie SUR24 (4-10dx1 1/2 Girder, 4-10dx1 1/2 Truss, Single Ply Girder) or equivalent at 2-9-8 from the left end to connect truss(es) FJ7 (1 ply 2x4 DF) to back face of bottom chord, skewed 45.0 deg.to the right, sloping 0.0 deg. down.
11) Use Simpson Strong-Tie SUR24 (4-10dx1 1/2 Girder, 4-10dx1 1/2 Truss, Single Ply Girder) or equivalent at 8-5-6 from the left end to connect truss(es) FJ5 (1 ply 2x4 DF) to back face of bottom chord, skewed 45.0 deg.to the right, sloping 0.0 deg. down.
12) Fill all nail holes where hanger is in contact with lumber.
13) "NAILED" indicates Girder: 3-10d (0.148" x 3") toe-nails per NDS guidelines.

LOAD CASE(S) Standard
1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-4=-84, 5-8=-14
Concentrated Loads (lb)

Continued on page 2

Vert: 7=-278, 10=72, 11=-187

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-UF	FJ9	Monopitch	19	1	Job Reference (optional)



Scale = 1:25.2

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	100.0	Plate Grip DOL	1.00	TC	0.21	Vert(LL)	n/a	-	n/a	999	MT20	220/195
Snow (Pf)	30.0	Lumber DOL	1.00	BC	0.02	Vert(CT)	n/a	-	n/a	999		
TCDL	12.0	Rep Stress Incr	YES	WB	0.07	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 12 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

REACTIONS (lb/size) 2=0/ Mechanical, 3=167/ Mechanical
Max Horiz 2=198 (LC 2), 3=-198 (LC 2)
Max Uplift 3=-57 (LC 8)
Max Grav 3=406 (LC 2)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 1-3=-281/123

BRACING
TOP CHORD Structural wood sheathing directly applied or 2-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
3) TCLL: ASCE 7-16; Pr=100.0 psf (roof LL: Lum DOL=1.00 Plate DOL=1.00); Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Refer to girder(s) for truss to truss connections.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 57 lb uplift at joint 3.
10) Non Standard bearing condition. Review required.
11) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.

LOAD CASE(S) Standard