
Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	A1	Monopitch	5	1	Job Reference (optional)



Scale = 1:42.1

Plate Offsets (X, Y): [5:0-1-9,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.93	Vert(LL)	-0.34	7-9	>772	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.77	Vert(CT)	-0.57	7-9	>464	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.76	Horz(CT)	0.07	6	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 98 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud *Except* W2,W4,W6:2x4 DF No.2
OTHERS	2x4 DF Stud

REACTIONS (lb/size) 6=1078/0-5-8, (min. 0-1-8), 10=1078/ Mechanical
Max Horiz 10=63 (LC 9)
Max Uplift 6=-185 (LC 10), 10=-187 (LC 6)

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.
WEBS	1 Row at midpt 1-9, 4-6

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	1-10=-1010/457, 1-2=-3506/1440, 2-3=-3238/1346, 3-4=-3230/1347, 5-6=-294/160
BOT CHORD	9-10=-55/276, 8-9=-1392/3497, 7-8=-1392/3497, 6-7=-1291/3232
WEBS	1-9=-1363/3284, 2-9=-548/318, 2-7=-272/104, 4-7=0/288, 4-6=-3133/1285


NOTES


1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 187 lb uplift at joint 10 and 185 lb uplift at joint 6.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	A2	Half Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:31 Page: 1
ID:pSc3xHxB7Kwdb_FkrywZxlzgeSF-am1otobV6Vnmo5VmoOFsiAcK_M21MGZbNPmM?6zcVfM





Scale = 1:42.1

Plate Offsets (X, Y): [3:0-2-0,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.84	Vert(LL)	-0.32	9-11	>835	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.74	Vert(CT)	-0.53	9-11	>500	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.70	Horz(CT)	0.07	7	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 100 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W2:2x4 DF No.2

REACTIONS (lb/size) 7=1078/0-5-8, (min. 0-1-8), 12=1078/ Mechanical
Max Horiz 12=62 (LC 7)
Max Uplift 7=-185 (LC 6), 12=-187 (LC 6)

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 5-6.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 1-11, 4-8

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-12=-1012/456, 1-2=-3409/1400, 2-3=-3375/1403, 3-4=-3367/1404, 4-5=-926/400
BOT CHORD 11-12=-52/251, 10-11=-1351/3400, 9-10=-1351/3400, 8-9=-1348/3369, 7-8=-318/862
WEBS 1-11=-1335/3218, 2-11=-573/325, 4-8=-2530/1045, 5-8=-237/743, 5-7=-1501/611

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 187 lb uplift at joint 12 and 185 lb uplift at joint 7.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	A3	Half Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:32 Page: 1
ID:SmKbSO5il0Rw1q92YT8NQHzgeS3-2zbB48c7tpvcPF4yM6m5EO9XmmNf5hOkc3VvXYzcVfL



Scale = 1:42.1

Plate Offsets (X, Y): [2:0-1-8,0-1-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.71	Vert(LL)	-0.28	8-10	>943	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.78	Vert(CT)	-0.48	8-10	>552	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.79	Horz(CT)	0.10	7	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 99 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud
OTHERS	2x4 DF Stud

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.
WEBS	1 Row at midpt 2-11, 3-8

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 7=1078/0-5-8, (min. 0-1-8), 11=1078/ Mechanical
Max Horiz 11=60 (LC 7)
Max Uplift 7=-185 (LC 6), 11=-187 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	1-11=-272/145, 2-3=-3468/1365, 3-4=-1816/748, 4-5=-1811/749
BOT CHORD	10-11=-1303/3171, 9-10=-1441/3510, 8-9=-1441/3510, 7-8=-672/1764
WEBS	2-11=-3034/1331, 2-10=-8/480, 3-8=-1766/784, 5-8=-170/586, 5-7=-1982/787


NOTES

1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 187 lb uplift at joint 11 and 185 lb uplift at joint 7.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	A4	Half Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:32 Page: 1
ID:2SAuOAFU?JCxjzEkMPOf_EzgeRr-2zbB48c7tpvcPF4yM6m5EO9ZomNf5jzkc3VvXYzcVfL



Scale = 1:42.1

Plate Offsets (X, Y): [2:0-1-12,0-2-0], [6:Edge,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.58	Vert(LL)	-0.28	8-10	>946	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.78	Vert(CT)	-0.48	8-10	>551	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.69	Horz(CT)	0.10	7	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 98 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud
OTHERS	2x4 DF Stud

REACTIONS (lb/size) 7=1078/0-5-8, (min. 0-1-8), 11=1078/ Mechanical
Max Horiz 11=59 (LC 9)
Max Uplift 7=-185 (LC 6), 11=-187 (LC 6)

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.
WEBS	1 Row at midpt 2-11, 5-7

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	2-3=-3393/1345, 3-4=-3385/1346, 4-5=-2550/1054
BOT CHORD	10-11=-1209/2965, 9-10=-1466/3599, 8-9=-1466/3599, 7-8=-984/2511
WEBS	2-11=-2883/1255, 2-10=-95/526, 4-8=-1104/497, 5-8=-102/419, 5-7=-2531/1021


NOTES

1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 187 lb uplift at joint 11 and 185 lb uplift at joint 7.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	A5	Half Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:32 Page: 1
ID:PQ_nRuJdqrqEpk6h9y_qhIzgeRm-2zbB48c7tpvcPF4yM6m5EO9UTmNp5i0kc3VvXYzcVfL



Scale = 1:42.1

Plate Offsets (X, Y): [4:0-3-8,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.92	Vert(LL)	-0.34	6-8	>781	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.77	Vert(CT)	-0.56	6-8	>471	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.75	Horz(CT)	0.07	5	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 98 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W2,W6:2x4 DF No.2
OTHERS 2x4 DF Stud

REACTIONS (lb/size) 5=1078/0-5-8, (min. 0-1-8), 9=1078/ Mechanical
Max Horiz 9=58 (LC 7)
Max Uplift 5=-185 (LC 6), 9=-187 (LC 6)

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 1-8, 3-5

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-9=-1009/458, 1-2=-3528/1454, 2-3=-3177/1312, 4-5=-310/169
BOT CHORD 8-9=-50/274, 7-8=-1403/3519, 6-7=-1403/3519, 5-6=-1253/3155
WEBS 1-8=-1379/3308, 2-8=-552/320, 2-6=-358/154, 3-6=0/292, 3-5=-3030/1234

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 187 lb uplift at joint 9 and 185 lb uplift at joint 5.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	A6	Half Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:33 Page: 1
ID:lOngUbNmeOSWvW?fyWa?OLzgeRh-W99ZIUcle71T1Of8wpHKnbhjgAlbq7ttrjFT4?zcVfK



Scale = 1:42.1

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.70	Vert(LL)	-0.28	7-9	>926	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.67	Vert(CT)	-0.46	7-9	>576	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.84	Horz(CT)	0.06	6	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 97 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W2:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 4-6

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 6=1078/0-5-8, (min. 0-1-8), 10=1078/ Mechanical
Max Horiz 10=56 (LC 7)
Max Uplift 6=-185 (LC 6), 10=-187 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-10=-1014/455, 1-2=-3258/1346, 2-3=-3499/1424, 3-4=-3470/1414
BOT CHORD 8-9=-1294/3250, 7-8=-1294/3250, 6-7=-985/2366
WEBS 1-9=-1304/3113, 2-9=-626/334, 3-7=-364/210, 4-7=-394/1182, 4-6=-2387/1057

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 187 lb uplift at joint 10 and 185 lb uplift at joint 6.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	A7	Half Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:33 Page: 1
ID:aX8xleSXEEDgdRSpImhPdczgeRb-W99ZIUcle71T1Of8wpHKnbhk3Aq8q9ktrjFT4?zcVfK



Scale = 1:42.1

Plate Offsets (X, Y): [4:0-3-8,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.61	Vert(LL)	-0.11	8-10	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.38	Vert(CT)	-0.18	8-10	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.72	Horz(CT)	0.01	6	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 98 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 6=-29/0-5-8, (min. 0-1-8), 7=1465/0-5-8, (min. 0-1-9), 11=720/ Mechanical
Max Horiz 11=55 (LC 7)
Max Uplift 6=-51 (LC 20), 7=-252 (LC 6), 11=-126 (LC 10)
Max Grav 6=44 (LC 10), 7=1465 (LC 1), 11=720 (LC 1)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-11=-670/308, 1-2=-1704/700, 2-3=-1348/561, 3-4=-1377/583, 4-5=-256/689
BOT CHORD 9-10=-649/1699, 8-9=-649/1699, 7-8=-689/316
WEBS 1-10=-677/1616, 2-10=-356/215, 2-8=-373/152, 3-8=-394/225, 5-7=-764/318, 4-7=-1127/533, 4-8=-870/2142

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 126 lb uplift at joint 11, 51 lb uplift at joint 6 and 252 lb uplift at joint 7.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	A8	Half Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:33 Page: 1
ID:HkH9QtnTtXdrNa0?NxgkElzgeRA-W99ZIUcle71T1Of8wpHKnbhf3Akpq5gtrjFT4?zcVfK



Scale = 1:54.9

Plate Offsets (X, Y): [3:0-2-0,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.93	Vert(LL)	-0.37	13-14	>818	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.72	Vert(CT)	-0.61	13-14	>498	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.98	Horz(CT)	0.08	9	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 135 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud
OTHERS	2x4 DF Stud

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.
WEBS	1 Row at midpt 8-10, 6-10, 2-15

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 9=-656/0-5-8, (min. 0-1-8), 10=2614/0-5-8, (min. 0-2-13), 15=1039/ Mechanical
Max Horiz 15=54 (LC 7)
Max Uplift 9=-656 (LC 1), 10=-449 (LC 6), 15=-181 (LC 6)
Max Grav 9=149 (LC 10), 10=2614 (LC 1), 15=1039 (LC 1)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-15=-253/109, 2-3=-3760/1136, 3-4=-3753/1137, 4-5=-2193/654, 5-6=-2220/670, 6-17=-800/2756, 7-17=-800/2756, 7-18=-800/2756, 8-18=-800/2756, 8-9=-168/659
BOT CHORD 14-15=-928/3237, 13-14=-928/3238, 12-13=-1086/3754, 11-12=-1086/3754
WEBS 5-11=-371/160, 8-10=-2887/875, 7-10=-508/209, 6-11=-661/2390, 6-10=-2976/924, 2-15=-3089/936, 4-11=-1623/506, 2-13=-163/531


NOTES

1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 26-8-12, Corner (3) 26-8-12 to 30-8-12 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 181 lb uplift at joint 15, 656 lb uplift at joint 9 and 449 lb uplift at joint 10.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	A9	Half Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:34 Page: 1
ID:xsazeQY_1tZvQGK6agIWHbzgeQB-?LjxVqdOPQ9KfYEKUXoZKpEp1a2BZYc14N_0cRzcVfJ



Scale = 1:54.9

Plate Offsets (X, Y): [11:0-2-4,0-2-4]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.98	Vert(LL)	-0.43	10-11	>708	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.84	Vert(CT)	-0.70	10-11	>433	180		
TCDL	12.0	Rep Stress Incr	YES	WB	1.00	Horz(CT)	0.06	7	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 132 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF 2100F 1.8E *Except* T2:2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W2,W4:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 6-8, 4-8

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 7=-624/0-5-8, (min. 0-1-8), 8=2576/0-5-8, (min. 0-2-12), 13=1046/ Mechanical
Max Horiz 13=52 (LC 7)
Max Uplift 7=-624 (LC 1), 8=-441 (LC 6), 13=-182 (LC 6)
Max Grav 7=140 (LC 10), 8=2576 (LC 1), 13=1046 (LC 1)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-13=-971/337, 1-14=-3850/1161, 2-14=-3843/1162, 2-3=-3027/894, 3-4=-2977/878, 4-15=-788/2684, 5-15=-788/2684, 5-16=-788/2684, 6-16=-788/2684, 6-7=-161/623
BOT CHORD 12-13=-49/348, 11-12=-49/348, 10-11=-1115/3841, 9-10=-229/721, 8-9=-229/721
WEBS 1-11=-1081/3542, 2-11=-499/232, 2-10=-835/280, 3-10=-467/199, 6-8=-2794/861, 5-8=-544/224, 4-8=-3574/1127, 4-10=-624/2375

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 26-8-12, Corner (3) 26-8-12 to 30-8-12 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 182 lb uplift at joint 13, 624 lb uplift at joint 7 and 441 lb uplift at joint 8.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	A10	Half Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:34 Page: 1
ID:AadNXVfdwehd0eXqb3yd8UzgeQ2-?LjxVqdOPQ9KfYEKUXoZKpEqWa3oZae14N_0cRzcVfJ



Scale = 1:54.9

Plate Offsets (X, Y): [7:0-2-0,Edge], [8:0-3-8,0-1-8], [16:0-3-8,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.95	Vert(LL)	-0.90	13-15	>407	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.80	Vert(CT)	-1.48	13-15	>249	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.87	Horz(CT)	0.22	10	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 137 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2 *Except* T1:2x4 DF 2100F 1.8E
BOT CHORD 2x4 DF 2100F 1.8E
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 2-18, 8-10, 6-11

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 10=1499/0-5-8, (min. 0-1-10), 18=1499/ Mechanical
Max Horiz 18=51 (LC 7)
Max Uplift 10=-258 (LC 6), 18=-259 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-6510/1949, 3-4=-7284/2180, 4-5=-7270/2187, 5-6=-6078/1837, 6-7=-3667/1127, 7-8=-3667/1127
BOT CHORD 17-18=-1207/4176, 16-17=-1207/4176, 15-16=-1899/6505, 14-15=-2135/7297, 13-14=-2135/7297, 12-13=-2132/7270, 11-12=-1782/6078, 10-11=-1072/3667
WEBS 2-18=-4148/1253, 3-15=-239/817, 8-10=-3745/1122, 5-12=-1264/371, 6-12=-100/487, 6-11=-2557/752, 8-11=-213/884, 2-16=-724/2436, 3-16=-651/237

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 26-8-12, Corner (3) 26-8-12 to 30-8-12 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 259 lb uplift at joint 18 and 258 lb uplift at joint 10.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	A11	Half Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:34 Page: 1
ID:FHcJN3S1Nw?GwnZWTw85pPzgeP0-?LjxVqdOPQ9KfYEKUXoZKpEqMa3LZZB14N_0cRzcVfJ



Scale = 1:54.9

Plate Offsets (X, Y): [2:0-3-12,0-2-12], [3:0-5-0,0-2-8], [5:0-3-0,Edge], [6:0-3-8,0-1-8], [7:Edge,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.96	Vert(LL)	-0.96	11-13	>382	240	M18AHS	169/162
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.83	Vert(CT)	-1.57	11-13	>234	180	MT20	220/195
TCDL	12.0	Rep Stress Incr	YES	WB	0.90	Horz(CT)	0.24	8	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 135 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2 *Except* T2:2x4 DF 2100F 1.8E
BOT CHORD 2x4 DF 2100F 1.8E
WEBS 2x4 DF Stud *Except* W2:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 6-8, 5-9, 3-14, 2-15

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 8=1499/0-5-8, (min. 0-1-10), 15=1499/ Mechanical
Max Horiz 15=49 (LC 7)
Max Uplift 8=-258 (LC 6), 15=-259 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-15=-258/109, 1-16=-281/74, 2-16=-274/75, 2-3=-5084/1528, 3-4=-7635/2295, 4-17=-6613/1987, 5-17=-6613/1987, 5-6=-4105/1255
BOT CHORD 14-15=-1476/5076, 13-14=-2082/7140, 12-13=-2085/7132, 11-12=-2085/7132, 10-11=-2241/7635, 9-10=-1914/6503, 8-9=-1202/4105
WEBS 6-8=-4112/1228, 3-11=-207/528, 4-10=-1070/322, 5-10=-73/410, 5-9=-2531/752, 6-9=-197/839, 3-14=-2136/628, 2-14=-112/591, 2-15=-4939/1489

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 26-8-12, Corner (3) 26-8-12 to 30-8-12 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 259 lb uplift at joint 15 and 258 lb uplift at joint 8.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	A12	Half Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:34 Page: 1
ID:UYjaPmz?F8Q9bOMnUSPB3TzgeOL-?LjxVqdOPQ9KfYEKUXoZKpEqza1FZY414N_0cRzcVfJ



Scale = 1:54.9

Plate Offsets (X, Y): [1:0-2-12,0-2-12], [3:0-4-0,0-3-7], [7:0-4-0,0-3-4], [8:Edge,0-1-8], [11:0-6-12,Edge], [13:0-5-12,Edge], [14:0-3-8,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.92	Vert(LL)	-1.01	11-12	>363	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.90	Vert(CT)	-1.65	11-12	>222	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.97	Horz(CT)	0.21	9	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 134 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2 *Except* T2:2x4 DF 2100F 1.8E
BOT CHORD 2x4 DF 2100F 1.8E *Except* B1:2x4 DF No.2
WEBS 2x4 DF Stud *Except* W2:2x4 DF No.2

REACTIONS (lb/size) 9=1499/0-5-8, (min. 0-1-10), 15=1499/ Mechanical
Max Horiz 15=48 (LC 7)
Max Uplift 9=-258 (LC 6), 15=-260 (LC 6)

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 5-10
WEBS 2 Rows at 1/3 pts 7-9

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-15=-1431/459, 1-16=-4391/1315, 2-16=-4384/1315, 2-3=-6643/1984, 3-4=-7858/2358, 4-5=-7218/2168, 5-6=-4603/1403, 6-7=-4603/1403
BOT CHORD 13-14=-1267/4381, 12-13=-1942/6664, 11-12=-2305/7858, 10-11=-2114/7192, 9-10=-1350/4603
WEBS 2-13=-695/2358, 3-13=-601/225, 2-14=-1100/382, 1-14=-1305/4324, 7-9=-4556/1360, 4-12=-271/137, 3-12=-377/1239, 4-11=-665/234, 5-11=-32/287, 5-10=-2683/791, 7-10=-161/748

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 26-8-12, Corner (3) 26-8-12 to 30-8-12 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 260 lb uplift at joint 15 and 258 lb uplift at joint 9.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	A13	Half Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:35 Page: 1
ID:U5mQYONKFaiKgdyJUb09RezgeNp-TXHJjAe0AkHBGioX1EJos0n_m_NJI11AI1kZ8tzcVfl



Scale = 1:54.9

Plate Offsets (X, Y): [3:0-4-0,0-3-7], [7:0-5-0,0-1-12], [8:Edge,0-2-0], [13:0-4-8,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.98	Vert(LL)	-1.05	11-12	>348	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.91	Vert(CT)	-1.73	11-12	>212	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.86	Horz(CT)	0.23	9	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 133 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2 *Except* T2:2x4 DF 2100F 1.8E
BOT CHORD 2x4 DF 2100F 1.8E *Except* B1:2x4 DF No.2
WEBS 2x4 DF Stud *Except* W7:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 2-14, 7-9, 5-10

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 9=1499/0-5-8, (min. 0-1-10), 14=1499/ Mechanical
Max Horiz 14=47 (LC 7)
Max Uplift 9=-258 (LC 6), 14=-260 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-15=-5743/1695, 3-15=-5742/1696, 3-4=-7950/2385, 4-5=-7710/2312, 5-6=-5098/1549, 6-7=-5098/1549, 8-9=-254/110
BOT CHORD 13-14=-1045/3544, 12-13=-1709/5915, 11-12=-2334/7950, 10-11=-2263/7695, 9-10=-1498/5098
WEBS 3-13=-816/294, 2-13=-648/2367, 2-14=-3617/1144, 7-9=-5003/1492, 4-12=-434/191, 3-12=-644/2097, 4-11=-302/202, 5-10=-2671/786, 7-10=-136/681

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 26-8-12, Corner (3) 26-8-12 to 30-8-12 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 260 lb uplift at joint 14 and 258 lb uplift at joint 9.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	A14	Half Hip Girder	1	2	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:35 Page: 1
ID:8D4Fmx8rPxeOjIGQgKfwVwzgeMq-TXHJjAe0AkHBGioX1EJos0n2M_O5l05AI1kZ8tzcVfI



Scale = 1:54.9

Plate Offsets (X, Y): [10:0-3-8,0-1-8], [19:0-3-8,0-1-8], [21:0-3-8,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.75	Vert(LL)	-0.98	16-18	>376	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.86	Vert(CT)	-1.54	16-18	>239	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	NO	WB	0.92	Horz(CT)	0.16	12	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	7.0										Weight: 318 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2 *Except* T2:2x4 DF 2100F 1.8E
BOT CHORD 2x6 DF 1950F 1.5E or 2x6 DF SS
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 3-1-14 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 12=2783/0-5-8, (min. 0-1-8), 22=2779/ Mechanical
Max Horiz 22=42 (LC 23)
Max Uplift 12=-501 (LC 4), 22=-502 (LC 4)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-22=-2523/464, 1-2=-5243/941, 2-3=-9167/1648, 3-4=-13244/2388, 4-5=-15609/2816, 5-6=-16150/2915, 6-23=-14876/2687, 7-23=-14876/2687, 7-8=-11769/2129, 8-9=-11769/2129, 9-10=-6806/1236, 10-11=-264/60
BOT CHORD 21-25=-920/5238, 20-25=-920/5238, 20-26=-1659/9338, 19-26=-1659/9338, 19-27=-2364/13244, 27-28=-2364/13244, 18-28=-2364/13244, 18-29=-2792/15609, 17-29=-2792/15609, 17-30=-2792/15609, 16-30=-2792/15609, 16-31=-2891/16150, 31-32=-2891/16150, 15-32=-2891/16150, 15-33=-2663/14876, 14-33=-2663/14876, 14-34=-2105/11769, 13-34=-2105/11769, 13-35=-1219/6806, 35-36=-1219/6806, 12-36=-1219/6806
WEBS 3-20=-1562/304, 2-20=-787/4384, 2-21=-2174/414, 1-21=-991/5486, 10-12=-6942/1248, 4-19=-1125/239, 3-19=-769/4164, 4-18=-469/2510, 5-18=-495/123, 5-16=-171/574, 6-15=-1353/343, 7-15=-152/805, 7-14=-3297/592, 9-14=-234/1454, 9-13=-5266/947, 10-13=-337/2044

NOTES
1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 2 rows staggered at 0-6-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
4) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
5) Provide adequate drainage to prevent water ponding.
6) All plates are MT20 plates unless otherwise indicated.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Refer to girder(s) for truss to truss connections.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 502 lb uplift at joint 22 and 501 lb uplift at joint 12.
11) "NAILED" indicates Girder: 3-10d (0.148" x 3") toe-nails per NDS guidelines.

LOAD CASE(S) Standard
1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15

Continued on page 2

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	A14	Half Hip Girder	1	**2**	Job Reference (optional)


Uniform Loads (lb/ft)

Vert: 1-11=-84, 12-22=-14

Concentrated Loads (lb)

Vert: 20=-171, 14=-171, 24=-171, 25=-171, 26=-171, 27=-171, 28=-171, 29=-171, 30=-171, 31=-171, 32=-171, 33=-171, 34=-171, 35=-171, 36=-171

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	A15	Monopitch	11	1	Job Reference (optional)



Scale = 1:25.4

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.23	Vert(LL)	-0.22	4-5	>447	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.62	Vert(CT)	-0.37	4-5	>262	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.23	Horz(CT)	0.01	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 36 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 4=392/ Mechanical, 5=392/ Mechanical
Max Horiz 5=47 (LC 7)
Max Uplift 4=-65 (LC 10), 5=-71 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
BOT CHORD 4-5=-480/605
WEBS 2-5=-639/561, 2-4=-639/533

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 71 lb uplift at joint 5 and 65 lb uplift at joint 4.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	AJ1	Jack-Closed	14	1	Job Reference (optional)



Scale = 1:36.6

0-5-8

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.56	Vert(LL)	-0.02	7-8	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.14	Vert(CT)	-0.03	7-8	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.03	Horz(CT)	0.00	7	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 36 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 3=560/0-4-0, (min. 0-1-8), 7=185/ Mechanical
Max Horiz 3=45 (LC 7)
Max Uplift 3=-146 (LC 6), 7=-26 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 26 lb uplift at joint 7 and 146 lb uplift at joint 3.
8) Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 3.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard


Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	AJ2	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:36 Page: 1
ID:oFGMjE4iaP06dXOTtn3lotzgeMv-xkrhwVfex2Q2usNjbyr1PEJG4Nw91hxKXhT7gJzcVfH



37-8-14 36-5-12

2-11-12



Scale = 1:35.1

0-5-8

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.56	Vert(LL)	-0.01	9	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.04	Vert(CT)	0.01	9	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.05	Horz(CT)	0.00	7	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 37 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 5-6.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 3=560/0-4-0, (min. 0-1-8), 7=185/ Mechanical
Max Horiz 3=46 (LC 7)
Max Uplift 3=-146 (LC 6), 7=-27 (LC 7)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 27 lb uplift at joint 7 and 146 lb uplift at joint 3.
8) Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 3.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	AJ3	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:36 Page: 1
ID:GSqkwZ5KLj8zFhzfRUa_K4zgeMu-xkrhwVfex2Q2usNjbyr1PEJG4Nua1hGKXhT7gJzcVfH



37-8-14 36-5-12



Scale = 1:39.8

0-5-8

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.56	Vert(LL)	-0.02	7-8	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.14	Vert(CT)	-0.03	7-8	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.03	Horz(CT)	0.00	7	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 36 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 5-6.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 3=560/0-4-0, (min. 0-1-8), 7=185/ Mechanical
Max Horiz 3=44 (LC 7)
Max Uplift 3=-146 (LC 6), 7=-27 (LC 7)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 27 lb uplift at joint 7 and 146 lb uplift at joint 3.
8) Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 3.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	AJ4	Monopitch	21	1	Job Reference (optional)



Scale = 1:23.6

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.07	Vert(LL)	n/a	-	n/a	999	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.02	Vert(CT)	n/a	-	n/a	999		
TCDL	12.0	Rep Stress Incr	YES	WB	0.04	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 10 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 2-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 2=0/ Mechanical, 3=167/ Mechanical
Max Horiz 2=115 (LC 1), 3=-115 (LC 1)
Max Uplift 3=-57 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 57 lb uplift at joint 3.
9) Non Standard bearing condition. Review required.
10) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	AJ5	Roof Special	1	1	Job Reference (optional)



Scale = 1:31.7

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.15	Vert(LL)	n/a	-	n/a	999	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.04	Vert(CT)	n/a	-	n/a	999		
TCDL	12.0	Rep Stress Incr	YES	WB	0.08	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 13 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 2-8-7 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 2=0/ Mechanical, 3=236/ Mechanical
Max Horiz 2=229 (LC 1), 3=-229 (LC 1)
Max Uplift 3=-81 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-256/230
WEBS 1-3=-256/272


NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 81 lb uplift at joint 3.
9) Non Standard bearing condition. Review required.
10) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	B1	Monopitch	11	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:36 Page: 1
ID:MdZxU9MBBlWQWFyhlfpOrPzgeAx-xkrhwVfex2Q2usNjbyr1PEJJvNqW1VwKXhT7gJzcVfH





Scale = 1:34

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.38	Vert(LL)	-0.10	8-9	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.40	Vert(CT)	-0.17	8-9	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.82	Horz(CT)	0.03	7	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 77 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 7=719/ Mechanical, 11=951/0-5-8, (min. 0-1-8)
Max Horiz 11=52 (LC 7)
Max Uplift 7=-123 (LC 10), 11=-202 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1773/816, 3-4=-1724/821, 4-5=-1720/822
BOT CHORD 8-9=-776/1768, 7-8=-775/1720
WEBS 2-11=-878/481, 2-9=-880/1799, 3-9=-388/256, 5-7=-1679/783

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 123 lb uplift at joint 7 and 202 lb uplift at joint 11.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	B2	Half Hip	1	1	Job Reference (optional)



34-3-12 34-3-12

2-2-12

Scale = 1:37.6

0-2-12

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.54	Vert(LL)	-0.13	9	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.47	Vert(CT)	-0.21	8-9	>855	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.82	Horz(CT)	0.02	7	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 77 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

REACTIONS (lb/size) 7=719/ Mechanical, 11=951/0-5-8, (min. 0-1-8)
Max Horiz 11=51 (LC 7)
Max Uplift 7=-121 (LC 6), 11=-202 (LC 6)

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (10-0-0 max.): 5-6.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 3-8

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-2065/968, 3-4=-736/357, 4-5=-730/357
BOT CHORD 8-9=-925/2057, 7-8=-295/692
WEBS 5-8=-114/407, 5-7=-1145/533, 2-11=-933/528, 2-9=-960/1937, 3-9=-286/235, 3-8=-1355/632

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 121 lb uplift at joint 7 and 202 lb uplift at joint 11.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	B3	Half Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:37 Page: 1
ID:9YgVbe40i51IhSIVhLmEE9zge0y-PwP38rfGiLYvW0yv9fMGxRsTBnA8m?_TmKDgDmzcVfG



34-3-12 34-3-12



Scale = 1:34

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.41	Vert(LL)	-0.11	7-8	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.44	Vert(CT)	-0.18	7-8	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.64	Horz(CT)	0.02	6	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 77 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 4-5.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 6=719/ Mechanical, 10=951/0-5-8, (min. 0-1-8)
Max Horiz 10=49 (LC 7)
Max Uplift 6=-121 (LC 6), 10=-203 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1950/908, 3-4=-1320/633
BOT CHORD 7-8=-864/1943, 6-7=-578/1292
WEBS 4-6=-1385/648, 2-10=-898/499, 3-8=-343/249, 2-8=-940/1909, 3-7=-647/290, 4-7=-42/255

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 121 lb uplift at joint 6 and 203 lb uplift at joint 10.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	B4	Half Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:37 Page: 1
ID:p7wTgZRCt?hefv03txo1vHzge0V-PwP38rfGiLYvW0yv9fMGxRsSFnAwmwwTmKDgDmzcVfG



Scale = 1:34

Plate Offsets (X, Y): [5:Edge,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.47	Vert(LL)	-0.10	7-8	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.39	Vert(CT)	-0.17	7-8	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.90	Horz(CT)	0.03	6	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 76 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 4-5.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 6=719/ Mechanical, 10=951/0-5-8, (min. 0-1-8)
Max Horiz 10=48 (LC 7)
Max Uplift 6=-120 (LC 6), 10=-203 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1756/810, 3-4=-1737/821
BOT CHORD 7-8=-767/1752, 6-7=-775/1725
WEBS 4-6=-1644/762, 2-10=-872/477, 3-8=-398/258, 2-8=-878/1788


NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 120 lb uplift at joint 6 and 203 lb uplift at joint 10.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	B5	Half Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:37 Page: 1
ID:9MFnI4i?hmSWIIiIAZBBovzge09-PwP38rfGiLYvW0yv9fMGxRsVknBNm0XTmKDgDmzcVfG





Scale = 1:34

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.31	Vert(LL)	-0.08	8-9	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.36	Vert(CT)	-0.15	7-8	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.54	Horz(CT)	0.02	7	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 77 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (4-4-4 max.): 4-6.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 7=719/ Mechanical, 11=951/0-5-8, (min. 0-1-8)
Max Horiz 11=47 (LC 7)
Max Uplift 7=-120 (LC 6), 11=-203 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1500/688, 3-4=-1904/869, 4-5=-1927/889
BOT CHORD 8-9=-644/1496, 7-8=-663/1392
WEBS 4-8=-261/171, 2-11=-845/457, 3-8=-187/429, 3-9=-476/272, 2-9=-792/1605, 5-8=-187/572, 5-7=-1401/720

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 120 lb uplift at joint 7 and 203 lb uplift at joint 11.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	B6	Half Hip Girder	1	2	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:38 Page: 1
ID:_n8U7y_RHqMFZqyj0u5bEmzge?o-t6ySLBguTfgm7AX6jNtVUfPfiBUUVRlc__yDlCzcVfF



Scale = 1:34

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.36	Vert(LL)	-0.11	8-9	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.56	Vert(CT)	-0.17	8-9	>999	180		
TCDL	12.0	Rep Stress Incr	NO	WB	0.67	Horz(CT)	0.01	7	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	7.0										Weight: 179 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x6 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 4-6.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 12-13.


REACTIONS (lb/size) 7=1608/ Mechanical, 12=1598/0-5-8, (min. 0-1-8)
Max Horiz 12=42 (LC 23)
Max Uplift 7=-280 (LC 4), 12=-330 (LC 4)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-2618/463, 3-4=-4659/849, 4-5=-4090/730, 5-6=-4090/730, 6-7=-1268/239
BOT CHORD 9-10=-443/2615, 9-14=-829/4662, 14-15=-829/4662, 8-15=-829/4662, 8-16=-55/259, 16-17=-55/259, 7-17=-55/259
WEBS 4-8=-595/178, 5-8=-385/129, 6-8=-697/3975, 2-12=-1366/276, 3-9=-421/2239, 3-10=-1162/240, 2-10=-510/2723

NOTES
1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
4) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
5) Provide adequate drainage to prevent water ponding.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Refer to girder(s) for truss to truss connections.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 280 lb uplift at joint 7 and 330 lb uplift at joint 12.
10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
11) Use Simpson Strong-Tie THJA26 (THJA26 on 2 ply, Left Hand Hip) or equivalent at 8-0-6 from the left end to connect truss(es) BJ1 (1 ply 2x4 DF), BJ11 (1 ply 2x4 DF) to front face of bottom chord.
12) Fill all nail holes where hanger is in contact with lumber.
13) "NAILED" indicates Girder: 3-10d (0.148" x 3") toe-nails per NDS guidelines.

LOAD CASE(S) Standard
1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-6=-84, 7-13=-14
Concentrated Loads (lb)
Vert: 9=-640, 14=-224, 15=-224, 16=-224, 17=-224

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	B1	Monopitch	11	1	Job Reference (optional)





Scale = 1:34

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.38	Vert(LL)	-0.10	8-9	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.40	Vert(CT)	-0.17	8-9	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.82	Horz(CT)	0.03	7	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 77 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 7=719/ Mechanical, 11=951/0-5-8, (min. 0-1-8)
Max Horiz 11=52 (LC 7)
Max Uplift 7=-123 (LC 10), 11=-202 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1773/816, 3-4=-1724/821, 4-5=-1720/822
BOT CHORD 8-9=-776/1768, 7-8=-775/1720
WEBS 2-11=-878/481, 2-9=-880/1799, 3-9=-388/256, 5-7=-1679/783

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 123 lb uplift at joint 7 and 202 lb uplift at joint 11.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	B8	Half Hip	1	1	Job Reference (optional)



Scale = 1:43

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.36	Vert(LL)	-0.09	10-11	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.39	Vert(CT)	-0.15	10-11	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.55	Horz(CT)	0.02	8	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 79 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W4:2x8 DF 2250F 1.6E or 2x8 DF SS, W5,W3:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 6-7, 2-15. Except: 10-0-0 oc bracing: 12-15
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 8=737/ Mechanical, 15=920/0-5-8, (min. 0-1-8)
Max Horiz 15=59 (LC 7)
Max Uplift 8=-126 (LC 6), 15=-192 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-393/180, 3-4=-1901/920, 4-5=-1895/921, 5-6=-648/328, 12-15=-258/635, 2-15=-350/218
BOT CHORD 11-12=-837/1827, 10-11=-837/1827, 9-10=-874/1896, 8-9=-258/599
WEBS 6-9=-181/472, 6-8=-965/460, 5-9=-1317/630, 3-12=-1514/734


NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Bearing at joint(s) 15 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 126 lb uplift at joint 8 and 192 lb uplift at joint 15.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	B9	Half Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:38 Page: 1
ID:nSjdgeWboxj?BQVGSWFSRxzgds4-t6ySLBguTfgm7AX6jNtVUfPdrBVlVN?c__yDlCzcVfF





Scale = 1:38

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.48	Vert(LL)	-0.11	7-8	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.48	Vert(CT)	-0.18	7-8	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.91	Horz(CT)	0.03	6	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 77 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W4:2x8 DF 2250F 1.6E or 2x8 DF SS, W3,W5:2x4 DF No.2

REACTIONS (lb/size) 6=755/ Mechanical, 12=903/0-5-8, (min. 0-1-8)
Max Horiz 12=58 (LC 7)
Max Uplift 6=-130 (LC 6), 12=-185 (LC 6)

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 4-5, 2-12. Except: 10-0-0 oc bracing: 10-12
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-617/294, 3-4=-1398/681, 9-15=-308/742, 12-15=-256/611, 2-12=-411/258
BOT CHORD 8-9=-1022/2190, 7-8=-1022/2190, 6-7=-624/1366
WEBS 4-6=-1465/698, 4-7=-68/277, 3-7=-821/403, 3-9=-1629/795

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Bearing at joint(s) 12 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 130 lb uplift at joint 6 and 185 lb uplift at joint 12.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	B10	Half Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:39 Page: 1
ID:UesqKsqXRE7AwZ4SXhEn1dzgdrf-LJWqZXhWEzodlJ6IG4Ok1sxobbslEpJmDeinHezcVfE



Scale = 1:38

Plate Offsets (X, Y): [5:Edge,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.48	Vert(LL)	-0.11	7-8	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.43	Vert(CT)	-0.18	7-8	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.97	Horz(CT)	0.02	6	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 77 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W4:2x8 DF 2250F 1.6E or 2x8 DF SS, W3,W5:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 4-5, 2-12. Except: 10-0-0 oc bracing: 10-12
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 6=755/ Mechanical, 12=903/0-5-8, (min. 0-1-8)
Max Horiz 12=56 (LC 7)
Max Uplift 6=-130 (LC 6), 12=-185 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-570/273, 3-4=-1864/901, 9-15=-312/745, 12-15=-312/745, 2-12=-361/224
BOT CHORD 8-9=-944/2028, 7-8=-944/2028, 6-7=-853/1848
WEBS 4-6=-1768/840, 3-9=-1529/746


NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Bearing at joint(s) 12 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 130 lb uplift at joint 6 and 185 lb uplift at joint 12.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	B11	Half Hip	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:39 Page: 1
ID:jeQfol9qJDOT2Z3R39it56zgdrF-LJWqZXhWEzodlJ6lG4Ok1sxqdbswEx8mDeinHezcVfE





Scale = 1:38

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.35	Vert(LL)	-0.09	8-9	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.42	Vert(CT)	-0.16	8-9	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.47	Horz(CT)	0.01	7	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 76 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W4:2x8 DF 2250F 1.6E or 2x8 DF SS, W3,W5:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (4-1-8 max.): 4-6, 2-12. Except: 10-0-0 oc bracing: 10-12
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 7=755/ Mechanical, 12=903/0-5-8, (min. 0-1-8)
Max Horiz 12=55 (LC 7)
Max Uplift 7=-130 (LC 6), 12=-185 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-551/245, 3-4=-2097/978, 4-5=-2119/997, 9-14=-305/754, 12-14=-305/754, 2-12=-321/199
BOT CHORD 8-9=-856/1774, 7-8=-718/1486
WEBS 4-8=-255/168, 3-8=-78/382, 3-9=-1317/702, 5-8=-245/678, 5-7=-1504/775

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Bearing at joint(s) 12 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 130 lb uplift at joint 7 and 185 lb uplift at joint 12.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	B12	Half Hip Girder	1	2	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:39 Page: 1
ID:8m9eZPb2bb3D_FOZjQtY5vzgdqg-LJWqZXhWEzodlJ6IG4Ok1sxobbnvErtmDeinHezcVfE



Scale = 1:34.1

Plate Offsets (X, Y): [6:0-2-8,0-1-12], [7:Edge,0-3-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.48	Vert(LL)	-0.15	8-9	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.74	Vert(CT)	-0.23	8-9	>790	180		
TCDL	12.0	Rep Stress Incr	NO	WB	0.87	Horz(CT)	0.00	7	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	7.0										Weight: 181 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x6 DF No.2
WEBS	2x4 DF Stud
OTHERS	2x6 DF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied or 5-3-15 oc purlins, except end verticals, and 2-0-0 oc purlins (5-4-7 max.): 4-6.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 12-13.

REACTIONS (lb/size) 7=2331/ Mechanical, 14=1912/0-4-0, (min. 0-1-8)
Max Horiz 14=42 (LC 23)
Max Uplift 7=-435 (LC 4), 14=-393 (LC 4)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	2-3=-393/91, 3-4=-6157/1176, 4-5=-5352/1020, 5-6=-5352/1020, 6-7=-1576/311
BOT CHORD	10-11=-673/3668, 9-10=-673/3668, 9-19=-1154/6149, 19-20=-1154/6149, 8-20=-1154/6149, 8-21=-72/332, 21-22=-72/332, 7-22=-72/332
WEBS	4-8=-828/216, 5-8=-381/138, 6-8=-977/5199, 3-9=-531/2756, 3-11=-3597/682, 2-14=-517/88, 11-14=-285/1560, 2-14=-285/1560

NOTES

1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
   Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
   Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
   Web connected as follows: 2x4 - 1 row at 0-6-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
4) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
5) Provide adequate drainage to prevent water ponding.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Refer to girder(s) for truss to truss connections.
9) Bearing at joint(s) 14 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 435 lb uplift at joint 7 and 393 lb uplift at joint 14.
11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
12) Use Simpson Strong-Tie THJA26 (THJA26 on 2 ply, Right Hand Hip) or equivalent at 8-0-6 from the left end to connect truss(es) BJ5 (1 ply 2x4 DF), BJ12 (1 ply 2x4 DF) to back face of bottom chord.
13) Use Simpson Strong-Tie LUS24 (4-10d Girder, 2-10d Truss) or equivalent spaced at 2-0-0 oc max. starting at 10-0-12 from the left end to 16-0-12 to connect truss(es) BJ5 (1 ply 2x4 DF) to back face of bottom chord.
14) Fill all nail holes where hanger is in contact with lumber.

Continued on page 2


15) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 328 lb down and 59 lb up at 17-5-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard

1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
   Uniform Loads (lb/ft)
   Vert: 1-6=-84, 12-13=-14, 7-11=-14
   Concentrated Loads (lb)
   Vert: 7=-328, 9=-948, 19=-320, 20=-320, 21=-320, 22=-320

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	BJ1	Jack-Closed	5	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:39 Page: 1
ID:_n8U7y_RHqMFZqyj0u5bEmzge?o-LJWqZXhWEzodlJ6IG4Ok1sxpMbwWE1cmDeinHezcVfE



Scale = 1:27.7

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.43	Vert(LL)	-0.03	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.19	Vert(CT)	-0.05	4-5	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.12	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 36 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=238/ Mechanical, 5=518/0-5-8, (min. 0-1-8)
Max Horiz 5=45 (LC 7)
Max Uplift 4=-31 (LC 6), 5=-134 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-5=-471/429

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 31 lb uplift at joint 4 and 134 lb uplift at joint 5.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard


Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	BJ2	Jack-Closed	2	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:39 Page: 1
ID:_n8U7y_RHqMFZqyj0u5bEmzge?o-LJWqZXhWEzodlJ6IG4Ok1sxtGbxNE1vmDeinHezcVfE



34-3-12 34-3-12

2-2-12



Scale = 1:28.2

0-2-12

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.18	Vert(LL)	0.00	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.07	Vert(CT)	-0.01	4-5	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.10	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 27 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=113/ Mechanical, 5=438/0-5-8, (min. 0-1-8)
Max Horiz 5=44 (LC 7)
Max Uplift 4=-14 (LC 10), 5=-126 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-5=-341/347

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 126 lb uplift at joint 5 and 14 lb uplift at joint 4.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard


Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	BJ3	Jack-Closed	2	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:40 Page: 1
ID:_n8U7y_RHqMFZqyj0u5bEmzge?o-pV4Cmti8_GwUNThUqnvzZ4U0r?I5zU0vSIRKp5zcVfD



34-3-12 34-3-12

2-2-12



Scale = 1:31.7

0-2-12

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.32	Vert(LL)	n/a	-	n/a	999	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.04	Vert(CT)	n/a	-	n/a	999		
TCDL	12.0	Rep Stress Incr	YES	WB	0.11	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 18 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 3-10-15 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 3=-63/ Mechanical, 4=418/0-5-8, (min. 0-1-8)
Max Horiz 4=42 (LC 7)
Max Uplift 3=-63 (LC 1), 4=-145 (LC 6)
Max Grav 3=49 (LC 6), 4=418 (LC 1)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-279/263
WEBS 1-4=-301/310, 2-4=-340/389

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 63 lb uplift at joint 3 and 145 lb uplift at joint 4.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	BJ4	Jack-Closed	2	1	Job Reference (optional)



Scale = 1:23

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.07	Vert(LL)	n/a	-	n/a	999	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.02	Vert(CT)	n/a	-	n/a	999		
TCDL	12.0	Rep Stress Incr	YES	WB	0.04	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 10 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 1-10-15 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 2=0/ Mechanical, 3=159/ Mechanical
Max Horiz 2=103 (LC 1), 3=-103 (LC 1)
Max Uplift 3=-54 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 54 lb uplift at joint 3.
9) Non Standard bearing condition. Review required.
10) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	BJ5	Jack-Closed	6	1	Job Reference (optional)



Scale = 1:33.6

Plate Offsets (X, Y): [2:0-3-8,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.59	Vert(LL)	-0.09	4-5	>885	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.40	Vert(CT)	-0.16	4-5	>520	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.32	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 33 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud
OTHERS	2x6 DF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=334/ Mechanical, 7=417/0-4-1, (min. 0-1-8)
Max Horiz 7=38 (LC 9)
Max Uplift 4=-56 (LC 6), 7=-100 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
BOT CHORD 4-5=-323/406
WEBS 2-4=-414/354, 2-7=-606/471


NOTES

1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) This truss has been designed for greater of min roof live load of 20.0 psf or 2.00 times flat roof load of 30.0 psf on overhangs non-concurrent with other live loads.
4) Provide adequate drainage to prevent water ponding.
5) All plates are MT20 plates unless otherwise indicated.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Refer to girder(s) for truss to truss connections.
9) Bearing at joint(s) 7 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 56 lb uplift at joint 4 and 100 lb uplift at joint 7.
11) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	BJ6	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:40 Page: 1
ID:Liq4V6qPXECj?2NYpqGsJdzgduF-pV4Cmti8_GwUNThUqnvzZ4U0S?GuzUsvSIRKp5zcVfD



34-9-7 34-3-12



Scale = 1:33.6

Plate Offsets (X, Y): [2:0-4-8,0-2-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.28	Vert(LL)	-0.02	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.18	Vert(CT)	-0.03	4-5	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.08	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 24 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud
OTHERS 2x6 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=230/ Mechanical, 7=316/0-4-1, (min. 0-1-8)
Max Horiz 7=36 (LC 9)
Max Uplift 4=-39 (LC 10), 7=-84 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-7=-401/341

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) This truss has been designed for greater of min roof live load of 20.0 psf or 2.00 times flat roof load of 30.0 psf on overhangs non-concurrent with other live loads.
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Bearing at joint(s) 7 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 39 lb uplift at joint 4 and 84 lb uplift at joint 7.
10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	BJ7	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:40 Page: 1
ID:2eQsbWygAITICb8TOxRCjkzgdu5-pV4Cmti8_GwUNThUqnvzZ4U1E?lwzUUvSIRKp5zcVfD



Scale = 1:33.3

Plate Offsets (X, Y): [2:0-4-8,0-2-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.23	Vert(LL)	0.00	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.05	Vert(CT)	0.00	4-5	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.02	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 16 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud
OTHERS	2x6 DF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied or 3-1-15 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=126/ Mechanical, 7=224/0-4-1, (min. 0-1-8)
Max Horiz 7=35 (LC 9)
Max Uplift 4=-20 (LC 10), 7=-70 (LC 6)
Max Grav 4=126 (LC 1), 7=251 (LC 16)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


NOTES

1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) This truss has been designed for greater of min roof live load of 20.0 psf or 2.00 times flat roof load of 30.0 psf on overhangs non-concurrent with other live loads.
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Bearing at joint(s) 7 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 20 lb uplift at joint 4 and 70 lb uplift at joint 7.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	BJ8	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:41 Page: 1
ID:mZ1dhx3xpNjtP7vO_1dY7rzgdtx-HheazDjnla2L_dGhOVQC6H1B_Oeoixk3hyBuMXzcVfC



Scale = 1:39.5

Plate Offsets (X, Y): [2:0-4-8,0-2-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.23	Vert(LL)	n/a	-	n/a	999	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.01	Vert(CT)	n/a	-	n/a	999		
TCDL	12.0	Rep Stress Incr	YES	WB	0.01	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 11 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud
OTHERS	2x6 DF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied or 1-7-7 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=51/ Mechanical, 7=148/0-4-1, (min. 0-1-8)
Max Horiz 7=34 (LC 9)
Max Uplift 4=-5 (LC 10), 7=-58 (LC 6)
Max Grav 4=51 (LC 1), 7=220 (LC 16)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES

1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) This truss has been designed for greater of min roof live load of 20.0 psf or 2.00 times flat roof load of 30.0 psf on overhangs non-concurrent with other live loads.
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Bearing at joint(s) 7 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 5 lb uplift at joint 4 and 58 lb uplift at joint 7.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	BJ9	Jack-Closed	1	1	Job Reference (optional)



Scale = 1:28.2

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.22	Vert(LL)	-0.01	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.08	Vert(CT)	-0.01	4-5	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.29	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 28 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud
OTHERS	2x6 DF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=121/ Mechanical, 8=419/0-4-0, (min. 0-1-8)
Max Horiz 8=44 (LC 7)
Max Uplift 4=-23 (LC 10), 8=-113 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


NOTES

1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Bearing at joint(s) 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 23 lb uplift at joint 4 and 113 lb uplift at joint 8.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	BJ10	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:41 Page: 1
ID:Eles1vUva78w6V46XtIl2DzgdtO-HheazDjnla2L_dGhOVQC6H1CEOeeitp3hyBuMXzcVfC



Scale = 1:28.2

0-5-8

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.15	Vert(LL)	0.00	5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.02	Vert(CT)	0.00	5	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.33	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 20 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud
OTHERS	2x6 DF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied or 3-10-15 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=-47/ Mechanical, 8=391/0-4-0, (min. 0-1-8)
Max Horiz 8=42 (LC 7)
Max Uplift 4=-47 (LC 1), 8=-116 (LC 6)
Max Grav 4=23 (LC 6), 8=391 (LC 1)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


NOTES

1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Bearing at joint(s) 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 47 lb uplift at joint 4 and 116 lb uplift at joint 8.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	BJ11	Diagonal Hip Girder	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:41 Page: 1
ID:_n8U7y_RHqMFZqyj0u5bEmzge?o-HheazDjnla2L_dGhOVQC6H1AMOX7iuH3hyBuMXzcVfC



Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.27	Vert(LL)	-0.03	5-6	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.50	Vert(CT)	-0.05	5-6	>999	180		
TCDL	12.0	Rep Stress Incr	NO	WB	0.30	Horz(CT)	0.00	5	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	7.0										Weight: 50 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 5=436/ Mechanical, 7=1008/0-7-12, (min. 0-1-8)
Max Horiz 7=40 (LC 5)
Max Uplift 5=-93 (LC 8), 7=-354 (LC 4)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-110/256, 2-3=-623/227
BOT CHORD 7-10=-253/126, 6-10=-253/126, 6-11=-212/621, 5-11=-212/621
WEBS 1-7=-290/118, 2-7=-616/184, 2-6=-282/903, 3-5=-557/220


NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 354 lb uplift at joint 7 and 93 lb uplift at joint 5.
8) "NAILED" indicates Girder: 3-10d (0.148" x 3") toe-nails per NDS guidelines.

LOAD CASE(S) Standard
1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-4=-84, 5-8=-14
Concentrated Loads (lb)
Vert: 7=-278, 10=89, 11=-187

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	BJ12	Diagonal Hip Girder	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:41 Page: 1
ID:8m9eZPb2bb3D_FOZjQtY5vzgdqg-HheazDjnla2L_dGhOVQC6H14pOWgit23hyBuMXzcVfC





Scale = 1:43.3

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.69	Vert(LL)	-0.05	5-6	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.53	Vert(CT)	-0.08	5-6	>999	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	NO	WB	0.38	Horz(CT)	0.00	5	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	7.0										Weight: 50 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud
OTHERS	2x10 DF SS

BRACING

TOP CHORD	Structural wood sheathing directly applied or 5-4-12 oc purlins, except end verticals. Except: 10-0-0 oc bracing: 7-10
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 5=648/ Mechanical, 12=823/0-5-11, (min. 0-1-8)
Max Horiz 12=40 (LC 5)
Max Uplift 5=-124 (LC 8), 12=-223 (LC 4)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	2-3=-330/107, 3-13=-1203/290, 4-13=-1200/290, 4-5=-513/110, 7-12=-123/481, 2-12=-357/101
BOT CHORD	7-14=-273/1200, 6-14=-273/1200
WEBS	3-7=-936/210, 4-6=-277/1146

NOTES


1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Bearing at joint(s) 12 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 124 lb uplift at joint 5 and 223 lb uplift at joint 12.
10) "NAILED" indicates Girder: 3-10d (0.148" x 3") toe-nails per NDS guidelines.

LOAD CASE(S) Standard

1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
   Uniform Loads (lb/ft)
   Vert: 1-2=-84, 2-4=-84, 9-11=-14, 5-8=-14
   Concentrated Loads (lb)
   Vert: 8=-31, 14=-69, 15=-311

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	BJ13	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:42 Page: 1
ID:_n8U7y_RHqMFZqyj0u5bEmzge?o-muCyBZjPWuACcnrtyCxReVZPOoztRPbCvcwRuzzcVfB



Scale = 1:28.2

0-7-4

Plate Offsets (X, Y): [3:0-1-12,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.06	Vert(LL)	n/a	-	n/a	999	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.02	Vert(CT)	n/a	-	n/a	999		
TCDL	12.0	Rep Stress Incr	YES	WB	0.04	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 13 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud
OTHERS	2x6 DF No.2

REACTIONS (lb/size) 2=0/ Mechanical, 3=159/0-4-0, (min. 0-1-8)
Max Horiz 2=92 (LC 1), 3=-92 (LC 1)
Max Uplift 3=-54 (LC 6)

BRACING

TOP CHORD	Structural wood sheathing directly applied or 2-4-7 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


NOTES


1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Bearing at joint(s) 3 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 54 lb uplift at joint 3.
9) Non Standard bearing condition. Review required.
10) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	C1	Roof Special	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:42 Page: 1
ID:NE_PLMY?xTwCHeWSGiReEZzcXsP-muCyBZjPWuACcnrtyCxReVZBxonWRDPCvcwRuzzcVfB





Scale = 1:56.1

Plate Offsets (X, Y): [2:0-3-8,0-2-0], [3:0-3-8,0-2-0], [9:0-3-8,0-2-0], [12:0-3-8,0-2-0], [13:0-3-8,0-2-0], [16:0-3-8,0-2-0], [17:0-4-8,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.92	Vert(LL)	-0.91	14-15	>393	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.81	Vert(CT)	-1.49	14-15	>240	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.82	Horz(CT)	0.15	11	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 142 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF 2100F 1.8E *Except* B1:2x4 DF No.2
WEBS 2x4 DF Stud *Except* W4,W16:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 11=1451/0-6-4, (min. 0-1-9), 18=1669/0-5-8, (min. 0-1-12)
Max Horiz 18=38 (LC 7)
Max Uplift 11=-212 (LC 7), 18=-250 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-20=-3784/1059, 3-20=-3780/1060, 3-4=-6036/1737, 4-5=-6895/1999, 5-6=-6893/1999, 6-7=-7229/2109, 7-8=-6355/1867, 8-9=-6359/1867, 9-10=-4028/1200, 10-11=-1386/429
BOT CHORD 16-17=-1013/3779, 15-16=-1685/6032, 14-15=-2067/7249, 13-14=-1816/6355, 12-13=-1153/4025
WEBS 2-18=-1576/509, 4-15=-272/907, 3-17=-1094/368, 2-17=-1150/3904, 3-16=-706/2365, 4-16=-664/239, 6-15=-380/177, 7-14=-252/918, 7-13=-659/229, 9-13=-695/2439, 9-12=-1103/368, 10-12=-1166/4002


NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 27-11-13, Corner (3) 27-11-13 to 31-11-13 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 212 lb uplift at joint 11 and 250 lb uplift at joint 18.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	C2	Roof Special	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:42 Page: 1
ID:Z9krLZIuKWjPjAFNvkYBlezcXrR-muCyBZjPWuACcnrtyCxReVZF?oksRDYCvcwRuzzcVfB





Scale = 1:56.2

Plate Offsets (X, Y): [2:0-3-8,0-2-8], [3:0-3-8,0-1-8], [8:0-3-8,0-2-0], [10:0-3-8,0-2-8], [14:0-3-8,0-2-8], [15:0-3-8,0-2-0], [19:0-3-8,0-1-8], [20:0-3-8,0-2-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.66	Vert(LL)	-0.64	17-18	>511	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.98	Vert(CT)	-1.05	17-18	>312	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.81	Horz(CT)	0.11	13	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 149 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2 *Except* B2:2x4 DF 2100F 1.8E
WEBS 2x4 DF Stud *Except* W4,W16:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 13=1746/1-5-7, (min. 0-1-14), 22=1531/0-5-8, (min. 0-1-10)
Max Horiz 22=-35 (LC 6)
Max Uplift 13=-335 (LC 7), 22=-237 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-24=-3174/836, 3-24=-3170/837, 3-4=-5061/1372, 4-5=-5739/1557, 5-6=-5738/1557, 6-7=-5910/1592, 7-8=-4929/1293, 8-9=-2623/610, 9-10=-2626/610, 10-11=-242/399
BOT CHORD 19-20=-789/3169, 18-19=-1320/5057, 17-18=-1539/5907, 16-17=-1243/4926, 15-16=-1243/4926, 14-15=-563/2623, 13-14=-396/286
WEBS 11-13=-440/301, 2-22=-1429/443, 4-18=-193/721, 3-20=-990/320, 2-20=-931/3318, 3-19=-561/1994, 4-19=-589/204, 10-13=-1515/472, 6-17=-280/126, 7-17=-312/1036, 7-15=-690/244, 8-15=-715/2420, 8-14=-1066/347, 10-14=-903/3212


NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 29-7-0, Corner (3) 29-7-0 to 33-7-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) All plates are 3x4 (=) MT20 unless otherwise indicated.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 237 lb uplift at joint 22 and 335 lb uplift at joint 13.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	C3	Roof Special	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:42 Page: 1
ID:KnJaIYDZRtIdrs3zMhv?qgzcXqF-muCyBZjPWuACcnrtyCxReVZI_oksRAkCvcwRuzzcVfB





Scale = 1:53.2

Plate Offsets (X, Y): [2:0-2-4,0-2-0], [10:0-2-0,0-1-12], [14:0-2-4,0-2-8], [20:0-2-0,0-1-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.47	Vert(LL)	-0.50	16-18	>610	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.98	Vert(CT)	-0.82	16-18	>373	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.99	Horz(CT)	0.11	13	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 141 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 13=1650/1-5-7, (min. 0-1-12), 21=1431/0-5-8, (min. 0-1-8)
Max Horiz 21=-36 (LC 6)
Max Uplift 13=-321 (LC 7), 21=-226 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-23=-2710/724, 3-23=-2706/725, 3-4=-4359/1204, 4-5=-4954/1370, 5-6=-4952/1370, 6-7=-4197/1117, 7-8=-2418/570, 8-9=-2417/567, 9-10=-2420/567, 10-11=-244/381
BOT CHORD 19-20=-677/2705, 18-19=-1153/4355, 17-18=-1341/5079, 16-17=-1341/5079, 15-16=-1341/5079, 14-15=-1064/4194, 13-14=-378/288
WEBS 11-13=-414/302, 2-21=-1325/425, 4-18=-174/638, 3-20=-916/304, 2-20=-824/2865, 3-19=-506/1756, 4-19=-552/195, 10-13=-1416/460, 6-15=-941/295, 7-15=-84/383, 7-14=-1921/589, 10-14=-855/2959

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 27-7-0, Corner (3) 27-7-0 to 31-7-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 226 lb uplift at joint 21 and 321 lb uplift at joint 13.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	C4	Roof Special	1	1	Job Reference (optional)



Scale = 1:50.2

Plate Offsets (X, Y): [2:0-3-8,0-2-0], [10:0-3-8,0-2-0], [14:0-3-8,0-2-0], [20:0-3-8,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.37	Vert(LL)	-0.37	16-18	>769	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.82	Vert(CT)	-0.60	16-18	>471	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.86	Horz(CT)	0.07	13	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 133 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 13=1554/1-5-7, (min. 0-1-11), 21=1331/0-5-8, (min. 0-1-8)
Max Horiz 21=-36 (LC 6)
Max Uplift 13=-308 (LC 7), 21=-214 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-2284/904, 3-4=-3699/1585, 4-5=-4212/1756, 5-6=-4211/1758, 6-23=-4290/1645, 7-23=-4292/1645, 7-8=-3598/1306, 8-9=-1991/646, 9-10=-1994/645, 10-11=-251/401
BOT CHORD 19-20=-859/2280, 18-19=-1537/3695, 17-18=-1592/4289, 16-17=-1592/4289, 15-16=-1256/3595, 14-15=-598/1991, 13-14=-398/295
WEBS 2-21=-1219/522, 10-13=-1320/524, 11-13=-442/310, 7-16=-363/749, 7-15=-581/276, 8-15=-708/1724, 8-14=-891/380, 10-14=-955/2555, 4-18=-179/556, 3-20=-844/391, 2-20=-1019/2461, 3-19=-729/1521, 4-19=-509/288


NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 12-1-12, Exterior (2) 12-1-12 to 17-7-0, Corner (3) 17-7-0 to 29-7-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) All plates are 3x4 (=) MT20 unless otherwise indicated.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 214 lb uplift at joint 21 and 308 lb uplift at joint 13.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	C5	Roof Special	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:43 Page: 1
ID:XoAja?o5qphBRq?yz_FU54zcXoD-E4mLOvk1HBI3ExQ3VwTgBi6VHC9wAfZM8Gg_QQzcVfA





Scale = 1:47.2

Plate Offsets (X, Y): [2:0-3-8,0-1-8], [9:0-3-8,0-2-0], [13:0-3-8,0-2-0], [18:0-3-8,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.37	Vert(LL)	-0.27	14-16	>950	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.67	Vert(CT)	-0.45	14-16	>577	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.89	Horz(CT)	0.05	12	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 123 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 12=1458/1-5-7, (min. 0-1-9), 19=1231/0-5-8, (min. 0-1-8)
Max Horiz 19=-36 (LC 6)
Max Uplift 12=-295 (LC 7), 19=-203 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1891/588, 3-4=-3081/994, 4-5=-3534/1130, 5-21=-3529/1130, 6-21=-3534/1130, 6-7=-3485/1094, 7-8=-2188/631, 8-9=-2191/630, 9-10=-254/374
BOT CHORD 17-18=-540/1887, 16-17=-943/3078, 15-16=-1043/3482, 14-15=-1043/3482, 13-14=-582/2188, 12-13=-371/298
WEBS 2-19=-1114/414, 4-16=-146/496, 3-18=-771/299, 2-18=-707/2087, 3-17=-438/1294, 4-17=-466/188, 9-12=-1231/476, 10-12=-404/312, 6-14=-369/174, 7-14=-485/1363, 7-13=-752/312, 9-13=-920/2674

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 12-1-12, Exterior (2) 12-1-12 to 15-7-0, Corner (3) 15-7-0 to 27-7-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 203 lb uplift at joint 19 and 295 lb uplift at joint 12.
7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	C6	Roof Special	1	1	Job Reference (optional)




Plate Offsets (X, Y): [7:0-2-12,Edge], [13:0-3-8,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.53	Vert(LL)	-0.18	14-15	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.53	Vert(CT)	-0.29	14-15	>794	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.72	Horz(CT)	0.05	11	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 112 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2 *Except* T3:2x6 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 11=0/1-3-15, (min. 0-1-8), 12=1332/0-3-8, (min. 0-1-8), 18=1133/0-5-8, (min. 0-1-8)
Max Horiz 18=-37 (LC 8)
Max Uplift 11=REL, 12=-372 (LC 11), 18=-185 (LC 6)
Max Grav 11=148 (LC 11), 12=1332 (LC 1), 18=1133 (LC 1)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-2055/669, 4-5=-2908/944, 5-21=-2905/944, 21-22=-2905/944, 6-22=-2908/944, 6-7=-2833/841, 7-8=-1779/335, 9-11=-799/167
BOT CHORD 17-18=-459/1522, 16-17=-800/2517, 15-16=-800/2517, 14-15=-786/2831, 13-14=-249/1702, 12-13=-654/590, 11-12=-654/590
WEBS 2-18=-277/142, 8-12=-1136/1066, 8-11=-729/738, 4-15=-96/432, 3-18=-1753/656, 3-17=-214/728, 4-17=-649/259, 6-14=-359/212, 7-14=-570/1199, 7-13=-616/317, 8-13=-914/2142


NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 12-1-12, Exterior (2) 12-1-12 to 13-8-12, Corner (3) 13-8-12 to 25-8-12 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) This truss has been designed for greater of min roof live load of 20.0 psf or 2.00 times flat roof load of 30.0 psf on overhangs non-concurrent with other live loads.
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 185 lb uplift at joint 18 and 372 lb uplift at joint 12.
8) "/\" indicates Released bearing: allow for upward movement at joint(s) 11.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	C7	Roof Special Girder	1	2	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:44 Page: 1
ID:MrE_pkJWODQSx23_ol_ofRzcXmG-iGKjcFlf2VQvr5_G3d_vkweaPcYpv7lVNwPYyszcVf9





Scale = 1:48.1

Plate Offsets (X, Y): [10:Edge,0-2-4], [13:0-2-8,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.73	Vert(LL)	-0.16	12-13	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.50	Vert(CT)	-0.24	12-13	>859	180		
TCDL	12.0	Rep Stress Incr	NO	WB	0.83	Horz(CT)	0.01	11	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	7.0										Weight: 225 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x6 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 5-3-11 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS (lb/size) 10=-3577/1-3-15, (min. 0-1-8), 11=5757/1-3-15, (min. 0-1-8), 17=1637/0-5-8, (min. 0-1-8)
Max Horiz 17=36 (LC 7)
Max Uplift 10=-3577 (LC 1), 11=-1016 (LC 5), 17=-329 (LC 4)
Max Grav 10=589 (LC 4), 11=5757 (LC 1), 17=1637 (LC 1)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-3028/575, 3-4=-4794/892, 4-5=-5387/980, 5-6=-5410/988, 6-7=-1823/332, 7-8=-101/369, 8-10=-835/257
BOT CHORD 15-16=-587/3024, 14-15=-587/3024, 14-19=-903/4792, 13-19=-903/4792, 13-20=-344/1815, 20-21=-344/1815, 12-21=-344/1815, 12-22=-2970/561, 11-22=-2970/561, 10-11=-2576/492
WEBS 3-16=-1069/192, 2-17=-1406/279, 2-16=-554/3055, 6-12=-1306/278, 6-13=-673/3695, 7-12=-942/4981, 7-11=-4562/799, 7-10=-654/3571, 4-13=-142/672, 4-14=-531/106, 3-14=-351/1960

NOTES
1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
4) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
5) This truss has been designed for greater of min roof live load of 20.0 psf or 2.00 times flat roof load of 30.0 psf on overhangs non-concurrent with other live loads.
6) Provide adequate drainage to prevent water ponding.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 3577 lb uplift at joint 10, 329 lb uplift at joint 17 and 1016 lb uplift at joint 11.
10) This truss has large uplift reaction(s) from gravity load case(s). Proper connection is required to secure truss against upward movement at the bearings. Building designer must provide for uplift reactions indicated.
11) Use Simpson Strong-Tie TJC37 (4 nail, 150-157) or equivalent at 5-6-7 from the left end to connect truss(es) CJ13 (1 ply 2x4 DF) to back face of bottom chord, skewed 67.5 deg.to the right, sloping 0.0 deg. down.
12) Use Simpson Strong-Tie HGUS26-2 (20-10d Girder, 6-10d Truss) or equivalent at 10-8-10 from the left end to connect truss(es) C14 (2 ply 2x4 DF) to back face of bottom chord, skewed 0.0 deg.to the right, sloping 0.0 deg. down.
13) Fill all nail holes where hanger is in contact with lumber.

Continued on page 2


14) "NAILED" indicates Girder: 3-10d (0.148" x 3") toe-nails per NDS guidelines.


LOAD CASE(S) Standard

1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
   Uniform Loads (lb/ft)
   Vert: 1-8=-84, 8-9=-84, 10-18=-14
   Concentrated Loads (lb)
   Vert: 15=-117, 16=-55, 13=-778, 19=-233, 20=-239, 21=-125

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	C8	Roof Special	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:44 Page: 1
ID:0mEzqalihdnZlBU5UdfPnYzcY_U-iGKjcFlf2VQvr5_G3d_vkweb2cQ?v88VNwPYyszcVf9





Scale = 1:53.1

Plate Offsets (X, Y): [2:0-3-8,0-2-8], [3:0-3-8,0-1-8], [13:0-5-8,0-3-4], [14:0-3-8,0-1-8], [15:0-3-8,0-2-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.69	Vert(LL)	-0.71	12-13	>472	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	1.00	Vert(CT)	-1.18	12-13	>282	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.74	Horz(CT)	0.15	11	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 131 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2 *Except* B2:2x4 DF 2100F 1.8E
WEBS 2x4 DF Stud *Except* W4:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 9-11

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 11=1352/ Mechanical, 16=1572/0-5-8, (min. 0-1-11)
Max Horiz 16=38 (LC 7)
Max Uplift 11=-198 (LC 7), 16=-238 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-18=-3295/944, 3-18=-3291/945, 3-4=-5280/1565, 4-5=-6083/1801, 5-6=-6082/1801, 6-7=-5606/1664, 7-8=-5604/1661, 8-9=-5607/1660
BOT CHORD 14-15=-897/3290, 13-14=-1514/5276, 12-13=-1877/6320, 11-12=-1067/3493
WEBS 2-16=-1472/492, 4-13=-246/854, 3-15=-1023/356, 2-15=-1044/3441, 3-14=-651/2098, 4-14=-637/228, 6-13=-256/179, 6-12=-763/284, 7-12=-322/138, 9-12=-572/2219, 9-11=-3503/1115

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 4-1-12, Exterior (2) 4-1-12 to 25-11-13, Corner (3) 25-11-13 to 29-11-13 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 198 lb uplift at joint 11 and 238 lb uplift at joint 16.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	C9	Roof Special	1	1	Job Reference (optional)



Scale = 1:50.1

Plate Offsets (X, Y): [13:0-4-12,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.53	Vert(LL)	-0.52	12-13	>594	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.93	Vert(CT)	-0.87	12-13	>356	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.99	Horz(CT)	0.13	11	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 123 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2 *Except* B2:2x4 DF 2100F 1.8E
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 11=1254/ Mechanical, 15=1474/0-5-8, (min. 0-1-9)
Max Horiz 15=38 (LC 7)
Max Uplift 11=-184 (LC 7), 15=-227 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-3832/1262, 4-5=-3832/1265, 5-17=-5285/1760, 6-17=-5282/1761, 6-18=-5282/1761, 7-18=-5285/1760, 7-8=-4847/1635, 8-9=-4847/1632
BOT CHORD 14-15=-674/2183, 13-14=-1568/4791, 12-13=-1836/5483, 11-12=-1035/3011
WEBS 2-15=-282/130, 3-14=-597/1827, 3-15=-2473/889, 5-14=-1085/401, 5-13=-154/554, 7-12=-686/272, 8-12=-297/147, 9-12=-579/1942, 9-11=-3044/1091


NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 12-1-12, Exterior (2) 12-1-12 to 15-11-13, Corner (3) 15-11-13 to 27-11-13 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 184 lb uplift at joint 11 and 227 lb uplift at joint 15.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	C10	Roof Special	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:44 Page: 1
ID:GaGBv2cJPvVLLO9hUMwbvjzcXjH-iGKjcFlf2VQvr5_G3d_vkwefZcRev7hVNwPYyszcVf9





Scale = 1:47.1

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.40	Vert(LL)	-0.40	12-13	>718	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.96	Vert(CT)	-0.66	12-13	>429	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.77	Horz(CT)	0.11	11	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 115 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 11=1155/ Mechanical, 16=1377/0-5-8, (min. 0-1-8)
Max Horiz 16=38 (LC 7)
Max Uplift 11=-169 (LC 7), 16=-215 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-3266/1397, 4-5=-3266/1400, 5-6=-4539/2005, 6-18=-4537/2006, 7-18=-4540/2006, 7-8=-4147/1700, 8-9=-4147/1697
BOT CHORD 15-16=-733/1845, 14-15=-1809/4102, 13-14=-1809/4102, 12-13=-1968/4691, 11-12=-1039/2560
WEBS 2-16=-266/132, 3-15=-695/1599, 3-16=-2147/967, 5-15=-960/527, 5-13=-163/499, 7-12=-594/349, 8-12=-280/144, 9-12=-650/1692, 9-11=-2616/1106

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) 0-1-12 to 12-1-12, Exterior (2) 12-1-12 to 13-11-13, Corner (3) 13-11-13 to 25-11-13 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 169 lb uplift at joint 11 and 215 lb uplift at joint 16.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	C11	Roof Special	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:45 Page: 1
ID:ZaQU5?0R8oUBHa0qVgbSGKzcWeK-ATu5pamHppYmTEZSdLV8G7Bl90qIecBeba95VIzcVf8



Scale = 1:44.1

Plate Offsets (X, Y): [3:0-1-12,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.73	Vert(LL)	-0.34	9-10	>770	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.74	Vert(CT)	-0.56	9-10	>463	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.69	Horz(CT)	0.07	8	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 106 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud *Except* W11:2x4 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (2-11-8 max.): 4-5.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 8=1056/ Mechanical, 13=1280/0-5-8, (min. 0-1-8)
Max Horiz 13=39 (LC 9)
Max Uplift 8=-159 (LC 7), 13=-212 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-3784/1428, 4-15=-3996/1555, 5-15=-3996/1555, 5-6=-3997/1551, 6-7=-3456/1353, 7-8=-992/413
BOT CHORD 12-13=-819/2203, 11-12=-819/2203, 10-11=-1396/3813, 9-10=-1304/3450
WEBS 4-11=-344/205, 6-10=-200/558, 6-9=-642/320, 7-9=-1264/3296, 3-13=-2397/1043, 3-11=-575/1627


NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 159 lb uplift at joint 8 and 212 lb uplift at joint 13.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	C12	Roof Special	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:45 Page: 1
ID:VE3g5VFMfetV3VzU69QvXLzcWe1-ATu5pamHppYmTEZSdLV8G7Bpl0sfedveba95VIzcVf8





Scale = 1:41.2

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.50	Vert(LL)	-0.23	9-10	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.59	Vert(CT)	-0.37	8-9	>648	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.58	Horz(CT)	0.07	8	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 96 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

REACTIONS (lb/size) 8=957/ Mechanical, 12=1183/0-5-8, (min. 0-1-8)
Max Horiz 12=39 (LC 7)
Max Uplift 8=-151 (LC 7), 12=-213 (LC 6)

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (2-11-1 max.): 4-5.
BOT CHORD Rigid ceiling directly applied.
WEBS 1 Row at midpt 6-8

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-2955/1187, 4-14=-3387/1368, 5-14=-3387/1368, 5-6=-3357/1347
BOT CHORD 11-12=-715/1866, 10-11=-715/1866, 9-10=-1157/2993, 8-9=-1039/2479
WEBS 4-10=-396/209, 4-9=-165/412, 5-9=-314/182, 6-9=-269/919, 6-8=-2410/1071, 2-12=-305/165, 3-10=-456/1177, 3-12=-2043/914


NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 151 lb uplift at joint 8 and 213 lb uplift at joint 12.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	C13	Roof Special Girder	1	2	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:45 Page: 1
ID:Sujr4?UGBUGoqQw8keGNoLzcWdk-ATu5pamHppYmTEZSdLV8G7BoS0tzeb5eba95VIzcVf8





Scale = 1:40.5

0-2-12

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.52	Vert(LL)	-0.18	9-10	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.57	Vert(CT)	-0.28	9-10	>775	180		
TCDL	12.0	Rep Stress Incr	NO	WB	0.76	Horz(CT)	0.02	8	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	7.0										Weight: 206 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x6 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 5-4-10 oc purlins, except end verticals, and 2-0-0 oc purlins (5-5-5 max.): 4-6.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 13-14.

REACTIONS (lb/size) 8=1368/ Mechanical, 13=1731/0-5-8, (min. 0-1-8)
Max Horiz 13=39 (LC 7)
Max Uplift 8=-340 (LC 5), 13=-389 (LC 4)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-4374/932, 4-5=-5626/1179, 5-6=-5626/1179, 6-7=-4811/1059, 7-8=-1255/288
BOT CHORD 12-13=-556/2464, 11-12=-556/2464, 11-15=-962/4441, 15-16=-962/4441, 10-16=-962/4441, 10-17=-1089/4874, 9-17=-1089/4874, 9-18=-103/356, 18-19=-103/356, 8-19=-103/356
WEBS 4-11=-602/139, 4-10=-258/1256, 5-10=-289/86, 6-10=-114/797, 6-9=-588/128, 7-9=-991/4543, 2-13=-272/72, 3-11=-456/2192, 3-13=-2790/606

NOTES
1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
4) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
5) Provide adequate drainage to prevent water ponding.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Refer to girder(s) for truss to truss connections.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 340 lb uplift at joint 8 and 389 lb uplift at joint 13.
10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
11) Use Simpson Strong-Tie SUL24 (4-10d Girder, 4-10dx1 1/2 Truss) or equivalent at 6-10-1 from the left end to connect truss(es) CJ3 (1 ply 2x4 DF) to front face of bottom chord, skewed 45.0 deg.to the left, sloping 0.0 deg. down.
12) Fill all nail holes where hanger is in contact with lumber.
13) "NAILED" indicates Girder: 3-10d (0.148" x 3") toe-nails per NDS guidelines.
14) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 321 lb down and 86 lb up at 13-11-4 on bottom chord. The design/ selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard
1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)


Continued on page 2

Vert: 1-7=-84, 8-14=-14

Concentrated Loads (lb)

Vert: 11=-341, 9=-321, 15=-163, 16=-163, 17=-163, 18=-70, 19=66

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	C14	Diagonal Hip Girder	1	2	Job Reference (optional)



Scale = 1:33.6

0-4-15

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.16	Vert(LL)	-0.01	7-8	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.36	Vert(CT)	-0.02	6-7	>999	180		
TCDL	12.0	Rep Stress Incr	NO	WB	0.19	Horz(CT)	0.00	6	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	7.0										Weight: 116 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 8-9.

REACTIONS (lb/size) 6=792/ Mechanical, 9=1100/0-9-14, (min. 0-1-8)
Max Horiz 9=41 (LC 5)
Max Uplift 6=-127 (LC 8), 9=-349 (LC 4)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-142/427, 2-3=-633/177, 3-11=-1129/204, 4-11=-1127/205
BOT CHORD 9-13=-424/158, 8-13=-424/158, 8-14=-162/630, 7-14=-162/630, 7-15=-188/1127, 6-15=-188/1127
WEBS 1-9=-484/151, 2-9=-785/209, 4-6=-1136/200, 3-8=-447/81, 2-8=-296/1142, 3-7=-55/541

NOTES
1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
4) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
5) Provide adequate drainage to prevent water ponding.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Refer to girder(s) for truss to truss connections.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 127 lb uplift at joint 6 and 349 lb uplift at joint 9.
10) "NAILED" indicates Girder: 3-10d (0.148" x 3") toe-nails per NDS guidelines.

LOAD CASE(S) Standard
1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-5=-84, 6-10=-14
Concentrated Loads (lb)
Vert: 12=-130, 13=78, 14=-183, 15=-422

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ1	Diagonal Hip Girder	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:46 Page: 1
ID:mCaPEiUw8DuVp3xIVigi8BzcXgt-efRT1wmva6gd5O8eB20NpLk_MPKONBBoqEuf1kzcVf7



Scale = 1:42.2

Plate Offsets (X, Y): [2:0-2-12,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.51	Vert(LL)	-0.02	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.11	Vert(CT)	-0.02	4-5	>999	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	NO	WB	0.13	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 35 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud
OTHERS	2x6 DF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied or 7-4-3 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=172/ Mechanical, 8=473/0-4-6, (min. 0-1-8)
Max Horiz 8=44 (LC 7)
Max Uplift 4=-51 (LC 8), 8=-147 (LC 4)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES


1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Bearing at joint(s) 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 51 lb uplift at joint 4 and 147 lb uplift at joint 8.
10) Use Simpson Strong-Tie TJC37 (4 nail, 22-30) or equivalent at 4-11-3 from the left end to connect truss(es) CJ10 (1 ply 2x4 DF) to front face of bottom chord, skewed 67.5 deg.to the left, sloping 0.0 deg. down.
11) Use Simpson Strong-Tie TJC37 (4 nail, 150-157) or equivalent at 4-11-3 from the left end to connect truss(es) CJ9 (1 ply 2x4 DF) to back face of bottom chord, skewed 67.5 deg.to the right, sloping 0.0 deg. down.
12) Fill all nail holes where hanger is in contact with lumber.

LOAD CASE(S) Standard


1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-3=-84, 6-7=-14, 4-5=-14
Concentrated Loads (lb)
Vert: 13=36

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ2	Jack-Closed	4	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:46 Page: 1
ID:xKkZXTcpYcHxelGPfWNH5WzcXgi-efRT1wmva6gd5O8eB20NpLk0?PJvNBBoqEuf1kzcVf7



38-9-7 38-3-12



Scale = 1:39.2

0-5-8

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.34	Vert(LL)	-0.02	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.14	Vert(CT)	-0.03	4-5	>999	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.13	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 33 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud
OTHERS	2x6 DF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=177/ Mechanical, 8=454/0-4-1, (min. 0-1-8)
Max Horiz 8=44 (LC 7)
Max Uplift 4=-23 (LC 10), 8=-121 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


NOTES

1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Bearing at joint(s) 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 23 lb uplift at joint 4 and 121 lb uplift at joint 8.
10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ3	Diagonal Hip Girder	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:46 Page: 1
ID:lZ3t9_tcMM2pH8ydx7mS_9zcXgM-efRT1wmva6gd5O8eB20NpLkyGPHaNCVoqEuf1kzcVf7



Scale = 1:32.1

0-3-11

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.58	Vert(LL)	-0.05	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.29	Vert(CT)	-0.05	4-5	>999	180		
TCDL	12.0	Rep Stress Incr	NO	WB	0.11	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	7.0										Weight: 42 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=361/ Mechanical, 5=941/0-7-6, (min. 0-1-8)
Max Horiz 5=39 (LC 5)
Max Uplift 4=-93 (LC 8), 5=-333 (LC 4)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-5=-572/161, 2-4=-94/285

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 93 lb uplift at joint 4 and 333 lb uplift at joint 5.
8) "NAILED" indicates Girder: 3-10d (0.148" x 3") toe-nails per NDS guidelines.


LOAD CASE(S) Standard
1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-3=-84, 4-6=-14
Concentrated Loads (lb)
Vert: 8=-278, 9=82, 10=-201

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ4	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:46 Page: 1
ID:qMVVxet_b3wyf_NRNQFDRxzcXgN-efRT1wmva6gd5O8eB20NpLk2BPKsNB0oqEuf1kzcVf7



38-9-7 38-3-12



Scale = 1:39.2

0-5-8

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.20	Vert(LL)	-0.01	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.08	Vert(CT)	-0.01	4-5	>999	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.14	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 29 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud
OTHERS 2x6 DF No.2

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 4=120/ Mechanical, 8=420/0-4-1, (min. 0-1-8)
Max Horiz 8=44 (LC 7)
Max Uplift 4=-19 (LC 10), 8=-118 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Bearing at joint(s) 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 19 lb uplift at joint 4 and 118 lb uplift at joint 8.
10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ5	Jack-Closed	1	1	Job Reference (optional)



Scale = 1:39.2

0-5-8

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.08	Vert(LL)	n/a	-	n/a	999	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.02	Vert(CT)	n/a	-	n/a	999	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.14	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 21 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud
OTHERS	2x6 DF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied or 3-10-15 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=-47/ Mechanical, 8=392/0-4-1, (min. 0-1-8)
Max Horiz 8=42 (LC 7)
Max Uplift 4=-47 (LC 1), 8=-128 (LC 6)
Max Grav 4=35 (LC 6), 8=392 (LC 1)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES

1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Bearing at joint(s) 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 47 lb uplift at joint 4 and 128 lb uplift at joint 8.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ6	Jack-Closed	2	1	Job Reference (optional)



Scale = 1:23

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.07	Vert(LL)	n/a	-	n/a	999	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.02	Vert(CT)	n/a	-	n/a	999		
TCDL	12.0	Rep Stress Incr	YES	WB	0.04	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 10 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud

BRACING

TOP CHORD	Structural wood sheathing directly applied or 1-10-15 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 2=0/ Mechanical, 3=159/ Mechanical
Max Horiz 2=103 (LC 1), 3=-103 (LC 1)
Max Uplift 3=-54 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES

1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 54 lb uplift at joint 3.
9) Non Standard bearing condition. Review required.
10) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ7	Jack-Closed	1	1	Job Reference (optional)



38-3-12 38-3-12

2-2-12



Scale = 1:28.2

0-2-12

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.18	Vert(LL)	0.00	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.07	Vert(CT)	-0.01	4-5	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.10	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 27 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=113/ Mechanical, 5=438/0-5-8, (min. 0-1-8)
Max Horiz 5=44 (LC 7)
Max Uplift 4=-14 (LC 10), 5=-126 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-5=-341/347

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 126 lb uplift at joint 5 and 14 lb uplift at joint 4.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard


Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ8	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:47 Page: 1
ID:IZ3t9_tcMM2pH8ydx7mS_9zcXgM-6r?rEGnXLQoUiYjqkmXcLYGC4phj6elx3ueCZBzcVf6



38-3-12 38-3-12

2-2-12



Scale = 1:31.7

0-2-12

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.32	Vert(LL)	n/a	-	n/a	999	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.04	Vert(CT)	n/a	-	n/a	999		
TCDL	12.0	Rep Stress Incr	YES	WB	0.11	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 18 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 3-10-15 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 3=-63/ Mechanical, 4=418/0-5-8, (min. 0-1-8)
Max Horiz 4=42 (LC 7)
Max Uplift 3=-63 (LC 1), 4=-145 (LC 6)
Max Grav 3=49 (LC 6), 4=418 (LC 1)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-279/263
WEBS 1-4=-301/310, 2-4=-340/389

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 63 lb uplift at joint 3 and 145 lb uplift at joint 4.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ9	Jack-Closed	1	1	Job Reference (optional)



Scale = 1:39.2

Plate Offsets (X, Y): [2:0-2-12,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.08	Vert(LL)	n/a	-	n/a	999	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.02	Vert(CT)	0.00	4-5	>999	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.15	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 23 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud
OTHERS	2x6 DF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=6/ Mechanical, 8=386/0-4-1, (min. 0-1-8)
Max Horiz 8=43 (LC 7)
Max Uplift 4=-7 (LC 7), 8=-121 (LC 6)
Max Grav 4=21 (LC 8), 8=386 (LC 1)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


NOTES

1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Bearing at joint(s) 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 7 lb uplift at joint 4 and 121 lb uplift at joint 8.
10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ10	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:48 Page: 1
ID:7QqlA1dh3pD8Yp7fG1ZbcKzcXtc-6r?rEGnXLQoUiYjqkmXcLYGBHpfr6f9x3ueCZBzcVf6



Scale = 1:35

0-8-9

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.37	Vert(LL)	0.00	7	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.16	Vert(CT)	0.00	7	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.02	Horz(CT)	0.00	6	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 21 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2 *Except* B2,B3:2x4 DF Stud
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 3=403/0-6-9, (min. 0-1-8), 6=-14/ Mechanical
Max Horiz 3=43 (LC 7)
Max Uplift 3=-117 (LC 6), 6=-18 (LC 19)
Max Grav 3=403 (LC 1), 6=14 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 18 lb uplift at joint 6 and 117 lb uplift at joint 3.
8) Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 3.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ11	Jack-Closed	1	1	Job Reference (optional)



Scale = 1:35.1

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.37	Vert(LL)	0.00	7	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.15	Vert(CT)	0.00	7	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.02	Horz(CT)	0.00	6	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 25 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2 *Except* B2,B3:2x4 DF Stud
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 3=421/0-6-9, (min. 0-1-8), 6=90/ Mechanical
Max Horiz 3=43 (LC 7)
Max Uplift 3=-115 (LC 6), 6=-23 (LC 10)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 23 lb uplift at joint 6 and 115 lb uplift at joint 3.
8) Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 3.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ12	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:48 Page: 1
ID:u8k29K5jBcoEuCLOEVHVNGzcXuH-a2ZERcoA6kwLKiI1IT2rumpM0D?Yr6Y5IYNl6dzcVf5



39-6-12 38-3-12



Scale = 1:44.5

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.37	Vert(LL)	0.00	7	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.13	Vert(CT)	0.00	7	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.01	Horz(CT)	-0.01	6	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	7.0										Weight: 18 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2 *Except* B2,B3:2x4 DF Stud
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 3-7-13 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 3=435/0-6-9, (min. 0-1-8), 6=-119/ Mechanical
Max Horiz 3=42 (LC 7)
Max Uplift 3=-129 (LC 6), 6=-119 (LC 1)
Max Grav 3=435 (LC 1), 6=39 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 119 lb uplift at joint 6 and 129 lb uplift at joint 3.
8) Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 3.

LOAD CASE(S) Standard


Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ13	Jack-Closed Girder	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:48 Page: 1
ID:MrE_pkJWODQSx23_ol_ofRzcXmG-a2ZERcoA6kwLKiI1IT2rumpOgD0Tr5b5IYNl6dzcVf5



38-3-12 38-3-12

2-4-10



Scale = 1:31.3

0-3-0

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.20	Vert(LL)	0.00	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.07	Vert(CT)	0.00	4-5	>999	180		
TCDL	12.0	Rep Stress Incr	NO	WB	0.07	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 27 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 5-9-13 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 4=89/ Mechanical, 5=456/0-5-15, (min. 0-1-8)
Max Horiz 5=43 (LC 5)
Max Uplift 4=-22 (LC 5), 5=-138 (LC 4)
Max Grav 4=89 (LC 15), 5=456 (LC 1)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-5=-344/110

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 138 lb uplift at joint 5 and 22 lb uplift at joint 4.
8) Use Simpson Strong-Tie TJC37 (4 nail, 150-157) or equivalent at 5-0-10 from the left end to connect truss(es) CJ14 (1 ply 2x4 DF) to back face of bottom chord, skewed 67.5 deg.to the right, sloping 0.0 deg. down.
9) Fill all nail holes where hanger is in contact with lumber.

LOAD CASE(S) Standard
1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-3=-84, 4-6=-14
Concentrated Loads (lb)
Vert: 7=-3

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ14	Jack-Closed	1	1	Job Reference (optional)



Scale = 1:31.8

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.40	Vert(LL)	0.00	3-4	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.04	Vert(CT)	0.00	3-4	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.12	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 21 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 3=5/ Mechanical, 4=408/0-5-8, (min. 0-1-8)
Max Horiz 4=43 (LC 7)
Max Uplift 3=-13 (LC 7), 4=-132 (LC 6)
Max Grav 3=28 (LC 8), 4=408 (LC 1)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-321/304
WEBS 1-4=-348/360, 2-4=-352/397

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 13 lb uplift at joint 3 and 132 lb uplift at joint 4.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard


Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ15	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:48 Page: 1
ID:MrE_pkJWODQSx23_ol_ofRzcXmG-a2ZERcoA6kwLKiI1IT2rumpFdD09r4L5IYNl6dzcVf5



38-3-12 38-3-12

2-2-12



Scale = 1:31.9

0-2-12

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.78	Vert(LL)	-0.01	3-4	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.09	Vert(CT)	-0.01	3-4	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.15	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 28 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 3=137/ Mechanical, 4=450/0-5-8, (min. 0-1-8)
Max Horiz 4=44 (LC 7)
Max Uplift 3=-20 (LC 10), 4=-127 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-427/416
WEBS 1-4=-476/484, 2-4=-435/470

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 20 lb uplift at joint 3 and 127 lb uplift at joint 4.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard


Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ16	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:49 Page: 1
ID:MrE_pkJWODQSx23_ol_ofRzcXmG-2E7cfypot12CystDsAZ4RzMYAdJNaXbEWC7Je3zcVf4



38-3-12 38-3-12

2-2-12



Scale = 1:28.8

0-2-12

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.28	Vert(LL)	-0.04	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.22	Vert(CT)	-0.06	4-5	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.15	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 36 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=253/ Mechanical, 5=529/0-5-8, (min. 0-1-8)
Max Horiz 5=45 (LC 7)
Max Uplift 4=-34 (LC 6), 5=-136 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
BOT CHORD 4-5=-165/284
WEBS 1-5=-229/265, 2-5=-583/535, 2-4=-299/199

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 136 lb uplift at joint 5 and 34 lb uplift at joint 4.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ17	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:49 Page: 1
ID:MrE_pkJWODQSx23_ol_ofRzcXmG-2E7cfypot12CystDsAZ4RzMW9dK_aY4EWC7Je3zcVf4



Scale = 1:27.7

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.41	Vert(LL)	-0.03	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.18	Vert(CT)	-0.04	4-5	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.12	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 35 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=228/ Mechanical, 5=510/0-5-8, (min. 0-1-8)
Max Horiz 5=45 (LC 7)
Max Uplift 4=-29 (LC 6), 5=-133 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-5=-458/420

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 29 lb uplift at joint 4 and 133 lb uplift at joint 5.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard


Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ18	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:49 Page: 1
ID:MrE_pkJWODQSx23_ol_ofRzcXmG-2E7cfypot12CystDsAZ4RzMS4dLiaXwEWC7Je3zcVf4



38-3-12 38-3-12

2-2-12



Scale = 1:31.8

0-2-12

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.67	Vert(LL)	0.00	3-4	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.07	Vert(CT)	-0.01	3-4	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.13	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 26 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 3=107/ Mechanical, 4=435/0-5-8, (min. 0-1-8)
Max Horiz 4=44 (LC 7)
Max Uplift 3=-13 (LC 10), 4=-126 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-403/388
WEBS 1-4=-445/456, 2-4=-412/451

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 13 lb uplift at joint 3 and 126 lb uplift at joint 4.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ19	Jack-Closed	1	1	Job Reference (optional)



Scale = 1:31.7

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.31	Vert(LL)	n/a	-	n/a	999	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.04	Vert(CT)	n/a	-	n/a	999		
TCDL	12.0	Rep Stress Incr	YES	WB	0.11	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 18 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 3-9-14 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 3=-76/ Mechanical, 4=422/0-5-8, (min. 0-1-8)
Max Horiz 4=42 (LC 7)
Max Uplift 3=-76 (LC 1), 4=-148 (LC 6)
Max Grav 3=54 (LC 6), 4=422 (LC 1)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-273/257
WEBS 1-4=-294/303, 2-4=-340/390

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 76 lb uplift at joint 3 and 148 lb uplift at joint 4.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ20	Jack-Closed	1	1	Job Reference (optional)



Scale = 1:23

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.06	Vert(LL)	n/a	-	n/a	999	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.02	Vert(CT)	n/a	-	n/a	999		
TCDL	12.0	Rep Stress Incr	YES	WB	0.04	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 10 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 1-9-14 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 2=0/ Mechanical, 3=150/ Mechanical
Max Horiz 2=92 (LC 1), 3=-92 (LC 1)
Max Uplift 3=-51 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 51 lb uplift at joint 3.
9) Non Standard bearing condition. Review required.
10) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ21	Jack-Closed	1	1	Job Reference (optional)



Scale = 1:24.6

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.62	Vert(LL)	n/a	-	n/a	999	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.02	Vert(CT)	n/a	-	n/a	999		
TCDL	12.0	Rep Stress Incr	YES	WB	0.01	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 12 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 1-9-10 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 4=-57/ Mechanical, 5=387/0-11-4, (min. 0-1-8)
Max Horiz 5=43 (LC 7)
Max Uplift 4=-196 (LC 16), 5=-156 (LC 6)
Max Grav 4=56 (LC 6), 5=566 (LC 16)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-5=-555/376

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) This truss has been designed for greater of min roof live load of 20.0 psf or 2.00 times flat roof load of 30.0 psf on overhangs non-concurrent with other live loads.
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 156 lb uplift at joint 5 and 196 lb uplift at joint 4.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ22	Jack-Closed	1	1	Job Reference (optional)



Scale = 1:24.6

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.67	Vert(LL)	-0.01	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.10	Vert(CT)	-0.01	4-5	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.01	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 20 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 3-9-10 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=116/ Mechanical, 5=411/0-11-4, (min. 0-1-8)
Max Horiz 5=44 (LC 7)
Max Uplift 4=-30 (LC 16), 5=-134 (LC 6)
Max Grav 4=116 (LC 1), 5=476 (LC 16)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-5=-451/375

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) This truss has been designed for greater of min roof live load of 20.0 psf or 2.00 times flat roof load of 30.0 psf on overhangs non-concurrent with other live loads.
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 134 lb uplift at joint 5 and 30 lb uplift at joint 4.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ23	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:50 Page: 1
ID:MrE_pkJWODQSx23_ol_ofRzcXmG-XQh_sIqQeLA3Z0SPQu5JzBuem1epJ0uOlsssAWzcVf3



Scale = 1:24.7

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.61	Vert(LL)	-0.05	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.27	Vert(CT)	-0.08	4-5	>806	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.02	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 28 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 4=234/ Mechanical, 5=488/0-11-4, (min. 0-1-8)
Max Horiz 5=46 (LC 7)
Max Uplift 4=-36 (LC 10), 5=-140 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-5=-450/423

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) This truss has been designed for greater of min roof live load of 20.0 psf or 2.00 times flat roof load of 30.0 psf on overhangs non-concurrent with other live loads.
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 140 lb uplift at joint 5 and 36 lb uplift at joint 4.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ24	Jack-Closed	1	1	Job Reference (optional)



Scale = 1:24.7

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.61	Vert(LL)	-0.07	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.32	Vert(CT)	-0.11	4-5	>633	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.03	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 30 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=259/ Mechanical, 5=508/0-11-4, (min. 0-1-8)
Max Horiz 5=46 (LC 7)
Max Uplift 4=-41 (LC 10), 5=-142 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-5=-466/429

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) This truss has been designed for greater of min roof live load of 20.0 psf or 2.00 times flat roof load of 30.0 psf on overhangs non-concurrent with other live loads.
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 142 lb uplift at joint 5 and 41 lb uplift at joint 4.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ25	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:50 Page: 1
ID:MrE_pkJWODQSx23_ol_ofRzcXmG-XQh_slqQeLA3Z0SPQu5JzBueJ1g0J02OlsssAWzcVf3



Scale = 1:24.6

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.64	Vert(LL)	-0.01	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.13	Vert(CT)	-0.02	4-5	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.01	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 22 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=144/ Mechanical, 5=426/0-11-4, (min. 0-1-8)
Max Horiz 5=44 (LC 7)
Max Uplift 4=-18 (LC 10), 5=-134 (LC 6)
Max Grav 4=144 (LC 1), 5=473 (LC 16)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-5=-446/386

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) This truss has been designed for greater of min roof live load of 20.0 psf or 2.00 times flat roof load of 30.0 psf on overhangs non-concurrent with other live loads.
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 134 lb uplift at joint 5 and 18 lb uplift at joint 4.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ26	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:50 Page: 1
ID:MrE_pkJWODQSx23_ol_ofRzcXmG-XQh_sIqQeLA3Z0SPQu5JzBuec1iaJ02OlsssAWzcVf3



Scale = 1:24.6

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.62	Vert(LL)	0.00	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.03	Vert(CT)	0.00	4-5	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.01	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 14 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 2-3-1 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 4=-5/ Mechanical, 5=379/0-11-4, (min. 0-1-8)
Max Horiz 5=43 (LC 7)
Max Uplift 4=-135 (LC 16), 5=-144 (LC 6)
Max Grav 4=36 (LC 6), 5=522 (LC 16)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-5=-509/361

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) This truss has been designed for greater of min roof live load of 20.0 psf or 2.00 times flat roof load of 30.0 psf on overhangs non-concurrent with other live loads.
4) Provide adequate drainage to prevent water ponding.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 144 lb uplift at joint 5 and 135 lb uplift at joint 4.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	CJ27	Monopitch	10	1	Job Reference (optional)



Scale = 1:23.6

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.07	Vert(LL)	n/a	-	n/a	999	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.02	Vert(CT)	n/a	-	n/a	999		
TCDL	12.0	Rep Stress Incr	YES	WB	0.04	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 10 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 2-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 2=0/ Mechanical, 3=167/ Mechanical
Max Horiz 2=115 (LC 1), 3=-115 (LC 1)
Max Uplift 3=-57 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 57 lb uplift at joint 3.
9) Non Standard bearing condition. Review required.
10) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	D1	Common	1	1	Job Reference (optional)



Scale = 1:42

Plate Offsets (X, Y): [6:0-3-0,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.18	Vert(LL)	-0.06	10-11	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.36	Vert(CT)	-0.12	10-11	>999	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.41	Horz(CT)	0.02	15	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 82 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud
OTHERS	2x6 DF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 13=891/0-5-8, (min. 0-1-8), 15=873/0-4-1, (min. 0-1-8)
Max Horiz 13=37 (LC 9)
Max Uplift 13=-168 (LC 6), 15=-164 (LC 7)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-1632/687, 4-5=-1632/687
BOT CHORD 12-13=-498/1213, 11-12=-498/1213, 10-11=-520/1205
WEBS 2-13=-293/177, 3-11=-145/444, 3-13=-1349/684, 5-11=-122/452, 5-10=-1201/578, 10-15=-213/510, 6-15=-213/510


NOTES

1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Bearing at joint(s) 15 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 168 lb uplift at joint 13 and 164 lb uplift at joint 15.
9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	D2	Hip Girder	1	2	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:51 Page: 1
ID:t4ZY6vl8SkVvxYSJNCf?YUzcWc5-?cFM4eq2PflwBA1czbcYWORwEQwg2M6X_WcQiyzcVf2



Scale = 1:48

Plate Offsets (X, Y): [7:0-2-12,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.18	Vert(LL)	-0.09	13-14	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.55	Vert(CT)	-0.13	13-14	>999	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	NO	WB	0.47	Horz(CT)	0.01	18	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	7.0										Weight: 193 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x6 DF No.2
WEBS	2x4 DF Stud
OTHERS	2x6 DF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied or 5-11-14 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 4-5.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS (lb/size) 16=1642/0-5-8, (min. 0-1-8), 18=1616/0-4-1, (min. 0-1-8)
Max Horiz 16=34 (LC 5)
Max Uplift 16=-329 (LC 4), 18=-323 (LC 5)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-4895/849, 4-23=-4834/850, 5-23=-4834/850, 5-6=-4850/854, 6-7=-2850/486
BOT CHORD 15-16=-481/2819, 14-15=-481/2819, 14-24=-840/4882, 13-24=-840/4882, 12-13=-497/2847, 11-12=-65/326
WEBS 2-16=-283/74, 3-16=-2999/574, 7-12=-501/2782, 3-14=-398/2236, 6-13=-406/2152, 6-12=-1077/221, 7-18=-461/91

NOTES

1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
4) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
5) Provide adequate drainage to prevent water ponding.
6) All plates are MT20 plates unless otherwise indicated.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Bearing at joint(s) 18 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 329 lb uplift at joint 16 and 323 lb uplift at joint 18.
11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
12) Use Simpson Strong-Tie THJA26 (THJA26 on 2 ply, Left Hand Hip) or equivalent at 8-0-6 from the left end to connect truss(es) DJ1 (1 ply 2x4 DF), DJ7 (1 ply 2x4 DF) to front face of bottom chord.
13) Use Simpson Strong-Tie THJA26 (THJA26 on 2 ply, Right Hand Hip) or equivalent at 10-4-8 from the left end to connect truss(es) DJ1 (1 ply 2x4 DF), DJ8 (1 ply 2x4 DF) to front face of bottom chord.
14) Fill all nail holes where hanger is in contact with lumber.
15) "NAILED" indicates Girder: 3-10d (0.148" x 3") toe-nails per NDS guidelines.

LOAD CASE(S) Standard


Continued on page 2

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	D2	Hip Girder	1	**2**	Job Reference (optional)

1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-8=-84, 11-17=-14, 9-10=-14
Concentrated Loads (lb)
Vert: 14=-638, 13=-626, 24=-229

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	DJ1	Jack-Closed	3	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:51 Page: 1
ID:t4ZY6vl8SkVvxYSJNCf?YUzcWc5-?cFM4eq2PfIwBA1czbcYWORqIQ?M2SaX_WcQiyzcVf2



Scale = 1:34.5

0-5-8

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.56	Vert(LL)	-0.04	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.25	Vert(CT)	-0.07	4-5	>961	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.12	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 37 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud
OTHERS	2x6 DF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=243/ Mechanical, 8=502/0-4-1, (min. 0-1-8)
Max Horiz 8=45 (LC 7)
Max Uplift 4=-35 (LC 6), 8=-128 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES

1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Bearing at joint(s) 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 35 lb uplift at joint 4 and 128 lb uplift at joint 8.
10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	DJ2	Jack-Closed	3	1	Job Reference (optional)



Scale = 1:39.2

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.20	Vert(LL)	-0.01	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.08	Vert(CT)	-0.01	4-5	>999	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.14	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 29 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud
OTHERS	2x6 DF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=120/ Mechanical, 8=420/0-4-1, (min. 0-1-8)
Max Horiz 8=44 (LC 7)
Max Uplift 4=-19 (LC 10), 8=-118 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES

1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Bearing at joint(s) 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 19 lb uplift at joint 4 and 118 lb uplift at joint 8.
10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	DJ3	Jack-Closed	3	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:52 Page: 1
ID:t4ZY6vl8SkVvxYSJNCf?YUzcWc5-TppkH_rgAyRnpJcoXJ7n2c_6ZqOCnuVgCALzFOzcVf1


2-3-3

2-1-10

2-0-7 3-10-15
2-0-7 1-7-12

0-1-3

0-1-9



32-9-7 32-3-12

2-4-12

1-11-4 3-10-15
1-11-4 1-6-3

Scale = 1:39.2

0-5-8

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.08	Vert(LL)	n/a	-	n/a	999	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.02	Vert(CT)	n/a	-	n/a	999	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	YES	WB	0.14	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 21 lb	FT = 20%

LUMBER

TOP CHORD	2x4 DF No.2
BOT CHORD	2x4 DF No.2
WEBS	2x4 DF Stud
OTHERS	2x6 DF No.2

BRACING

TOP CHORD	Structural wood sheathing directly applied or 3-10-15 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=-47/ Mechanical, 8=392/0-4-1, (min. 0-1-8)
Max Horiz 8=42 (LC 7)
Max Uplift 4=-47 (LC 1), 8=-128 (LC 6)
Max Grav 4=35 (LC 6), 8=392 (LC 1)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES

1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Bearing at joint(s) 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 47 lb uplift at joint 4 and 128 lb uplift at joint 8.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	DJ4	Jack-Closed	4	1	Job Reference (optional)



Scale = 1:23

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.07	Vert(LL)	n/a	-	n/a	999	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.02	Vert(CT)	n/a	-	n/a	999		
TCDL	12.0	Rep Stress Incr	YES	WB	0.04	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 10 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 1-10-15 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 2=0/ Mechanical, 3=159/ Mechanical
Max Horiz 2=103 (LC 1), 3=-103 (LC 1)
Max Uplift 3=-54 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 54 lb uplift at joint 3.
9) Non Standard bearing condition. Review required.
10) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.

LOAD CASE(S) Standard


Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	DJ5	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:52 Page: 1
ID:t4ZY6vl8SkVvxYSJNCf?YUzcWc5-TppkH_rgAyRnpJcoXJ7n2c_5_qNPnv7gCALzFOzcVf1



32-3-12 32-3-12

2-2-12



Scale = 1:28.2

0-2-12

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.18	Vert(LL)	0.00	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.07	Vert(CT)	-0.01	4-5	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.10	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 27 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=113/ Mechanical, 5=438/0-5-8, (min. 0-1-8)
Max Horiz 5=44 (LC 7)
Max Uplift 4=-14 (LC 10), 5=-126 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-5=-341/347

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 126 lb uplift at joint 5 and 14 lb uplift at joint 4.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard


Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	DJ6	Jack-Closed	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:52 Page: 1
ID:t4ZY6vl8SkVvxYSJNCf?YUzcWc5-TppkH_rgAyRnpJcoXJ7n2c_3pqOunv_gCALzFOzcVf1



32-3-12 32-3-12

2-2-12



Scale = 1:31.7

0-2-12

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.32	Vert(LL)	n/a	-	n/a	999	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.04	Vert(CT)	n/a	-	n/a	999		
TCDL	12.0	Rep Stress Incr	YES	WB	0.11	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 18 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 3-10-15 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 3=-63/ Mechanical, 4=418/0-5-8, (min. 0-1-8)
Max Horiz 4=42 (LC 7)
Max Uplift 3=-63 (LC 1), 4=-145 (LC 6)
Max Grav 3=49 (LC 6), 4=418 (LC 1)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-279/263
WEBS 1-4=-301/310, 2-4=-340/389

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 63 lb uplift at joint 3 and 145 lb uplift at joint 4.


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	DJ7	Diagonal Hip Girder	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:52 Page: 1
ID:t4ZY6vl8SkVvxYSJNCf?YUzcWc5-TppkH_rgAyRnpJcoXJ7n2c_3HqHrnsigCALzFOzcVf1



32-9-7 32-3-12



Scale = 1:37.9

0-9-4

Plate Offsets (X, Y): [2:0-3-4,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.29	Vert(LL)	-0.03	5-6	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.49	Vert(CT)	-0.05	5-6	>999	180	M18AHS	169/162
TCDL	12.0	Rep Stress Incr	NO	WB	0.32	Horz(CT)	0.00	5	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	7.0										Weight: 52 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud
OTHERS 2x10 DF SS

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 5=428/ Mechanical, 10=1014/0-5-6, (min. 0-1-8)
Max Horiz 10=40 (LC 7)
Max Uplift 5=-85 (LC 8), 10=-357 (LC 4)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-595/198
BOT CHORD 6-17=-182/592, 5-17=-182/592
WEBS 2-6=-256/826, 3-5=-526/188, 8-10=-152/387, 2-10=-152/387

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Bearing at joint(s) 10 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 85 lb uplift at joint 5 and 357 lb uplift at joint 10.
10) "NAILED" indicates Girder: 3-10d (0.148" x 3") toe-nails per NDS guidelines.
11) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 139 lb down and 63 lb up at 2-5-15, and 139 lb down and 63 lb up at 2-5-15 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
12) Special hanger(s) or other connection device(s) shall be provided at 2-9-8 from the left end sufficient to connect trusses DJ4 (1 ply 2x4 DF) to front face of bottom chord, skewed 45.0 deg. to the left, sloping 0.0 deg down.. The design/selection of such special connection device(s) is the responsibility of others.
13) Special hanger(s) or other connection device(s) shall be provided at 2-9-8 from the left end sufficient to connect trusses DJ4 (1 ply 2x4 DF) to back face of bottom chord, skewed 45.0 deg. to the right, sloping 0.0 deg down.. The design/selection of such special connection device(s) is the responsibility of others.


LOAD CASE(S) Standard
1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-4=-84, 8-9=-14, 5-7=-14
Concentrated Loads (lb)
Vert: 8=-278, 16=82, 17=-194

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	DJ8	Diagonal Hip Girder	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:53 Page: 1
ID:t4ZY6vl8SkVvxYSJNCf?YUzcWc5-x?M7VKslwGZeRTB_50e0bpWFeEd4WIdqRq5WnqzcVf0



32-9-7 32-3-12



Scale = 1:37.9

0-11-14

Plate Offsets (X, Y): [2:0-2-8,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.25	Vert(LL)	-0.03	5-6	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.49	Vert(CT)	-0.05	5-6	>999	180	M18AHS	132/127
TCDL	12.0	Rep Stress Incr	NO	WB	0.34	Horz(CT)	0.00	5	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	7.0										Weight: 52 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud
OTHERS 2.0 RigidLam DF LVL 1-1/2 x 11-7/8

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 5=417/ Mechanical, 10=1036/0-5-12, (min. 0-1-8)
Max Horiz 10=40 (LC 7)
Max Uplift 5=-78 (LC 8), 10=-356 (LC 4)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-556/170
BOT CHORD 6-17=-154/554, 5-17=-154/554
WEBS 2-6=-243/834, 3-5=-486/157, 8-10=-154/394, 2-10=-154/394


NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) All plates are MT20 plates unless otherwise indicated.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Bearing at joint(s) 10 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 78 lb uplift at joint 5 and 356 lb uplift at joint 10.
10) "NAILED" indicates Girder: 3-10d (0.148" x 3") toe-nails per NDS guidelines.
11) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 139 lb down and 63 lb up at 2-6-7, and 139 lb down and 63 lb up at 2-6-7 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
12) Special hanger(s) or other connection device(s) shall be provided at 2-9-8 from the left end sufficient to connect trusses DJ4 (1 ply 2x4 DF) to front face of bottom chord, skewed 45.0 deg. to the left, sloping 0.0 deg down.. The design/selection of such special connection device(s) is the responsibility of others.
13) Special hanger(s) or other connection device(s) shall be provided at 2-9-8 from the left end sufficient to connect trusses DJ4 (1 ply 2x4 DF) to back face of bottom chord, skewed 45.0 deg. to the right, sloping 0.0 deg down.. The design/selection of such special connection device(s) is the responsibility of others.

LOAD CASE(S) Standard
1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-4=-84, 8-9=-14, 5-7=-14
Concentrated Loads (lb)
Vert: 8=-278, 16=76, 17=-201

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	E1	Monopitch	1	1	Job Reference (optional)



30-3-12 30-3-12



Scale = 1:32.4

0-2-12

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.38	Vert(LL)	-0.10	5-6	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.39	Vert(CT)	-0.17	5-6	>614	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.26	Horz(CT)	0.01	5	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 48 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 5=391/ Mechanical, 6=646/0-5-8, (min. 0-1-8)
Max Horiz 6=47 (LC 7)
Max Uplift 5=-66 (LC 10), 6=-153 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
BOT CHORD 5-6=-378/624
WEBS 2-6=-321/250, 3-5=-555/400, 3-6=-672/556


NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 153 lb uplift at joint 6 and 66 lb uplift at joint 5.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	E2	Half Hip	2	1	Job Reference (optional)



30-3-12 30-3-12



Scale = 1:37.5

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.21	Vert(LL)	-0.01	7	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.17	Vert(CT)	-0.03	7	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.27	Horz(CT)	0.00	6	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 50 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 4-5.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 6=391/ Mechanical, 8=646/0-5-8, (min. 0-1-8)
Max Horiz 8=47 (LC 7)
Max Uplift 6=-61 (LC 6), 8=-153 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-650/375
BOT CHORD 7-8=-326/646
WEBS 4-6=-427/278, 2-8=-334/255, 4-7=-236/462, 3-8=-723/463

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 61 lb uplift at joint 6 and 153 lb uplift at joint 8.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	E3	Half Hip Girder	2	**2**	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:53 Page: 1
ID:dymiiCP?1jtQ?Zp7trY27TzcWW5-x?M7VKsIwGZeRTB_50e0bpWHrEiFWLbqRq5WnqzcVf0



Scale = 1:32.3

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.11	Vert(LL)	-0.01	7-8	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.16	Vert(CT)	-0.02	7-8	>999	180		
TCDL	12.0	Rep Stress Incr	NO	WB	0.15	Horz(CT)	0.00	6	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	7.0										Weight: 113 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x6 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 4-5.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS (lb/size) 6=1023/ Mechanical, 8=880/0-5-8, (min. 0-1-8)
Max Horiz 8=42 (LC 7)
Max Uplift 6=-186 (LC 4), 8=-202 (LC 4)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-1494/281
BOT CHORD 7-8=-199/1064, 7-11=-251/1439, 6-11=-251/1439
WEBS 4-7=-73/469, 4-6=-1498/275, 2-8=-253/69, 3-7=-83/478, 3-8=-1192/269

NOTES
1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Web connected as follows: 2x4 - 1 row at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
4) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
5) Provide adequate drainage to prevent water ponding.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) Refer to girder(s) for truss to truss connections.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 186 lb uplift at joint 6 and 202 lb uplift at joint 8.
10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
11) Use Simpson Strong-Tie THJA26 (THJA26 on 2 ply, Left Hand Hip) or equivalent at 8-0-6 from the left end to connect truss(es) EJ1 (1 ply 2x4 DF), EJ5 (1 ply 2x4 DF) to front face of bottom chord.
12) Fill all nail holes where hanger is in contact with lumber.
13) "NAILED" indicates Girder: 3-10d (0.148" x 3") toe-nails per NDS guidelines.

LOAD CASE(S) Standard
1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-5=-84, 6-9=-14
Concentrated Loads (lb)
Vert: 7=-640, 11=-226

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	EJ1	Jack-Closed	4	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:54 Page: 1
ID:dymiiCP?1jtQ?Zp7trY27TzcWW5-PBwViftwhahV2dIBfk9F813Nae20FpJzgUq4JHzcVf?



Scale = 1:27.7

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.43	Vert(LL)	-0.03	4-5	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.19	Vert(CT)	-0.05	4-5	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.12	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 36 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 4=238/ Mechanical, 5=518/0-5-8, (min. 0-1-8)
Max Horiz 5=45 (LC 9)
Max Uplift 4=-31 (LC 6), 5=-134 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-5=-471/429

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 31 lb uplift at joint 4 and 134 lb uplift at joint 5.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	EJ2	Jack-Closed	4	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:54 Page: 1
ID:9mCKVsONGQlZNPEwJ80paFzcWW6-PBwViftwhahV2dlBfk9F813JXe3tFo9zgUq4JHzcVf?



Scale = 1:31.9

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.69	Vert(LL)	0.00	3-4	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.07	Vert(CT)	-0.01	3-4	>999	180		
TCDL	12.0	Rep Stress Incr	YES	WB	0.13	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-AS								
BCDL	7.0										Weight: 26 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 3=113/ Mechanical, 4=438/0-5-8, (min. 0-1-8)
Max Horiz 4=44 (LC 7)
Max Uplift 3=-14 (LC 10), 4=-126 (LC 6)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-408/394
WEBS 1-4=-451/462, 2-4=-416/455

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 14 lb uplift at joint 3 and 126 lb uplift at joint 4.
8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	EJ3	Jack-Closed	4	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Mon Mar 09 23:18:54 Page: 1
ID:dymiiCP?1jtQ?Zp7trY27TzcWW5-PBwViftwhahV2dlBfk9F813PJe4MFpTzgUq4JHzcVf?



Scale = 1:31.7

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.32	Vert(LL)	n/a	-	n/a	999	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.04	Vert(CT)	n/a	-	n/a	999		
TCDL	12.0	Rep Stress Incr	YES	WB	0.11	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 18 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 3-10-15 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 3=-63/ Mechanical, 4=418/0-5-8, (min. 0-1-8)
Max Horiz 4=42 (LC 7)
Max Uplift 3=-63 (LC 1), 4=-145 (LC 6)
Max Grav 3=49 (LC 6), 4=418 (LC 1)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-279/263
WEBS 1-4=-301/310, 2-4=-340/389

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 63 lb uplift at joint 3 and 145 lb uplift at joint 4.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	EJ4	Jack-Closed	4	1	Job Reference (optional)



Scale = 1:23

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.07	Vert(LL)	n/a	-	n/a	999	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.02	Vert(CT)	n/a	-	n/a	999		
TCDL	12.0	Rep Stress Incr	YES	WB	0.04	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MP								
BCDL	7.0										Weight: 10 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 1-10-15 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS (lb/size) 2=0/ Mechanical, 3=159/ Mechanical
Max Horiz 2=103 (LC 1), 3=-103 (LC 1)
Max Uplift 3=-54 (LC 6)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 54 lb uplift at joint 3.
9) Non Standard bearing condition. Review required.
10) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-R	EJ5	Diagonal Hip Girder	2	1	Job Reference (optional)



Scale = 1:33.3

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.15	TC	0.27	Vert(LL)	-0.03	5-6	>999	240	MT20	220/195
(Roof Snow = 30.0)		Lumber DOL	1.15	BC	0.50	Vert(CT)	-0.05	5-6	>999	180		
TCDL	12.0	Rep Stress Incr	NO	WB	0.30	Horz(CT)	0.00	5	n/a	n/a		
BCLL	0.0 *	Code	IRC2021/TPI2014	Matrix-MSH								
BCDL	7.0										Weight: 50 lb	FT = 20%

LUMBER
TOP CHORD 2x4 DF No.2
BOT CHORD 2x4 DF No.2
WEBS 2x4 DF Stud

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 5=436/ Mechanical, 7=1008/0-7-12, (min. 0-1-8)
Max Horiz 7=40 (LC 7)
Max Uplift 5=-93 (LC 8), 7=-354 (LC 4)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-110/256, 2-3=-623/227
BOT CHORD 7-10=-253/126, 6-10=-253/126, 6-11=-212/621, 5-11=-212/621
WEBS 1-7=-290/118, 2-7=-616/184, 2-6=-282/903, 3-5=-557/220

NOTES
1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=3.0psf; h=20ft; Ke=0.90; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
2) TCLL: ASCE 7-16; Pf=30.0 psf (Lum DOL = 1.15 Plate DOL = 1.15); Is=1.0; Rough Cat C; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.00
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
6) Refer to girder(s) for truss to truss connections.
7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 354 lb uplift at joint 7 and 93 lb uplift at joint 5.
8) "NAILED" indicates Girder: 3-10d (0.148" x 3") toe-nails per NDS guidelines.

LOAD CASE(S) Standard
1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-4=-84, 5-8=-14
Concentrated Loads (lb)
Vert: 7=-278, 10=89, 11=-187