
Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-MF	F1	Floor	10	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:35:28 Page: 1
ID:Ftoa6HPKGxr4aeYPHbn4HJzhY6w-u1gEmlp4YSwMQLMsAmjfByFBKvmvHePO?IaWjbzUliT



10-0-0 10-0-0

Scale = 1:37.4

Plate Offsets (X, Y): [12:Edge,0-1-8], [13:0-1-8,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.30	Vert(LL)	-0.17	15	>999	360	M18AHS	169/162
TCDL	11.0	Lumber DOL	1.00	BC	0.68	Vert(CT)	-0.26	14-15	>937	240	MT20	220/195
BCLL	0.0	Rep Stress Incr	YES	WB	0.48	Horz(CT)	0.06	12	n/a	n/a		
BCDL	7.0	Code	IRC2021/TPI2014	Matrix-AS							Weight: 106 lb	FT = 20%F, 11%E

LUMBER
TOP CHORD 2x4 DF No.2(flat)
BOT CHORD 2x4 DF No.2(flat)
WEBS 2x4 DF Stud(flat)

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

REACTIONS (lb/size) 12=1173/0-3-8, (min. 0-1-8), 18=1173/ Mechanical


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-2374/0, 3-4=-2374/0, 4-5=-3195/0, 5-6=-3195/0, 6-7=-2554/0, 7-8=-2554/0, 8-9=-2554/0, 9-10=-434/0
BOT CHORD 17-18=0/1391, 16-17=0/2949, 15-16=0/2949, 14-15=0/3038, 13-14=0/1660, 12-13=0/434
WEBS 2-18=-1738/0, 2-17=0/1241, 4-17=-725/0, 4-15=0/311, 6-14=-610/0, 9-14=0/1129, 9-13=-1546/0, 10-13=0/1011, 10-12=-1299/0

NOTES
1) All plates are MT20 plates unless otherwise indicated.
2) Refer to girder(s) for truss to truss connections.
3) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
4) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-MF	F1G	Floor Girder	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:35:28 Page: 1
ID:Ftoa6HPKGxr4aeYPHbn4HJzhY6w-u1gEmlp4YSwMQLMsAmjfByF49vmDHYIO?IaWjbzUliT



Scale = 1:37.4

10-0-0

10-0-0

Plate Offsets (X, Y): [5:0-1-8,Edge], [13:Edge,0-1-8], [14:0-1-8,Edge], [18:0-1-8,Edge], [20:Edge,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.76	Vert(LL)	-0.24	17	>999	360	M18AHS	169/162
TCDL	11.0	Lumber DOL	1.00	BC	0.66	Vert(CT)	-0.36	15-17	>671	240	MT20	220/195
BCLL	0.0	Rep Stress Incr	NO	WB	0.87	Horz(CT)	0.09	13	n/a	n/a		
BCDL	7.0	Code	IRC2021/TPI2014	Matrix-MS							Weight: 110 lb	FT = 20%F, 11%E

LUMBER
TOP CHORD 2x4 DF No.2(flat)
BOT CHORD 2x4 DF 2100F 1.8E(flat)
WEBS 2x4 DF Stud(flat)

BRACING
TOP CHORD Structural wood sheathing directly applied or 5-2-5 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 13=1464/0-3-8, (min. 0-1-8), 20=1810/ Mechanical


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-4039/0, 3-4=-4039/0, 4-5=-4934/0, 5-6=-4806/0, 6-7=-4806/0, 7-8=-3412/0, 8-9=-3412/0, 9-10=-3412/0, 10-11=-537/0
BOT CHORD 19-20=0/2239, 18-19=0/4866, 17-18=0/4934, 16-17=0/4270, 15-16=0/4270, 14-15=0/2140, 13-14=0/537
WEBS 2-20=-2799/0, 2-19=0/2271, 6-17=-257/0, 7-17=0/676, 7-15=-1083/0, 10-15=0/1605, 10-14=-2022/0, 11-14=0/1298, 11-13=-1606/0, 4-19=-1384/0

NOTES
1) All plates are MT20 plates unless otherwise indicated.
2) Refer to girder(s) for truss to truss connections.
3) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
4) Use Simpson Strong-Tie THA426 (Single Chord Girder) or equivalent at 6-5-8 from the left end to connect truss(es) FGIR (1 ply 2x4 DF) to back face of top chord, skewed 0.0 deg.to the left, sloping 0.0 deg. down.
5) Fill all nail holes where hanger is in contact with lumber.

LOAD CASE(S) Standard
1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (lb/ft)
Vert: 13-20=-14, 1-12=-102
Concentrated Loads (lb)
Vert: 4=-927

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-MF	F2	Floor	2	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:35:29 Page: 1
ID:41AsMLU5rnbEIZ?ZesuUWazhY6q-u1gEmlp4YSwMQLMsAmjfByFBzvq8Hh2O?IaWjbzUliT



10-0-0 10-0-0
Scale = 1:27.6

Plate Offsets (X, Y): [1:Edge,0-0-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.26	Vert(LL)	-0.04	9-10	>999	360	MT20	220/195
TCDL	11.0	Lumber DOL	1.00	BC	0.41	Vert(CT)	-0.09	10-11	>999	240		
BCLL	0.0	Rep Stress Incr	YES	WB	0.31	Horz(CT)	0.02	8	n/a	n/a		
BCDL	7.0	Code	IRC2021/TPI2014	Matrix-AS							Weight: 70 lb	FT = 20%F, 11%E

LUMBER
TOP CHORD 2x4 DF No.2(flat)
BOT CHORD 2x4 DF No.2(flat)
WEBS 2x4 DF Stud(flat)

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

REACTIONS (lb/size) 8=794/0-3-8, (min. 0-1-8), 11=794/ Mechanical


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1369/0, 3-4=-1369/0, 4-5=-1225/0, 5-6=-1225/0
BOT CHORD 10-11=0/868, 9-10=0/1460, 8-9=0/577
WEBS 2-11=-1095/0, 2-10=0/632, 4-9=-296/0, 5-9=-252/0, 6-9=0/817, 6-8=-925/0

NOTES
1) Refer to girder(s) for truss to truss connections.
2) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
3) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-MF	F3	Floor Supported Gable	1	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:35:29 Page: 1
ID:41AsMLU5rnbEIZ?ZesuUWazhY6q-MEEc_5qiJl2C1Vx2kTEukAoPgIGd0ChYEyK3F2zUliS



Scale = 1:30.5

10-0-0

Plate Offsets (X, Y): [1:Edge,0-0-12], [24:Edge,0-0-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.07	Vert(LL)	n/a	-	n/a	999	MT20	220/195
TCDL	11.0	Lumber DOL	1.00	BC	0.01	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0	Rep Stress Incr	YES	WB	0.03	Horiz(TL)	n/a	-	n/a	n/a		
BCDL	7.0	Code	IRC2021/TPI2014	Matrix-AS							Weight: 66 lb	FT = 20%F, 11%E

LUMBER

TOP CHORD	2x4 DF No.2(flat)
BOT CHORD	2x4 DF No.2(flat)
WEBS	2x4 DF Stud(flat)
OTHERS	2x4 DF Stud(flat)

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.

REACTIONS All bearings 13-9-11.
(lb) - Max Grav All reactions 250 (lb) or less at joint(s) 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES
1) All plates are 1.5x4 (||) MT20 unless otherwise indicated.
2) Gable requires continuous bottom chord bearing.
3) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
4) Gable studs spaced at 1-4-0 oc.
5) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
6) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-MF	F4	Floor	6	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:35:29 Page: 1
ID:41AsMLU5rnbEIZ?ZesuUWazhY6q-MEEc_5qiJl2C1Vx2kTEukAoMOI8004tYEyK3F2zUliS



10-0-0 10-0-0

Scale = 1:33.3

Plate Offsets (X, Y): [1:Edge,0-0-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.28	Vert(LL)	-0.10	13-14	>999	360	MT20	220/195
TCDL	11.0	Lumber DOL	1.00	BC	0.56	Vert(CT)	-0.16	12-13	>999	240		
BCLL	0.0	Rep Stress Incr	YES	WB	0.53	Horz(CT)	0.04	11	n/a	n/a		
BCDL	7.0	Code	IRC2021/TPI2014	Matrix-AS							Weight: 93 lb	FT = 20%F, 11%E

LUMBER
TOP CHORD 2x4 DF No.2(flat)
BOT CHORD 2x4 DF No.2(flat)
WEBS 2x4 DF Stud(flat)

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.

REACTIONS (lb/size) 11=1019/ Mechanical, 16=1019/0-3-8, (min. 0-1-8)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1953/0, 3-4=-1953/0, 4-5=-2393/0, 5-6=-2393/0, 6-7=-1366/0, 7-8=-1366/0, 8-9=-1366/0
BOT CHORD 15-16=0/1160, 14-15=0/1160, 13-14=0/2337, 12-13=0/2041, 11-12=0/282
WEBS 2-16=-1463/0, 2-14=0/1000, 4-14=-484/0, 6-13=0/444, 6-12=-851/0, 8-12=-254/0, 9-12=0/1368, 9-11=-1095/0

NOTES
1) Refer to girder(s) for truss to truss connections.
2) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
3) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-MF	F5	Floor	4	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:35:29 Page: 1
ID:41AsMLU5rnbEIZ?ZesuUWazhY6q-MEEc_5qiJl2C1Vx2kTEukAoMYIC409tYEyK3F2zUliS



Scale = 1:25.8

10-0-0 10-0-0

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.27	Vert(LL)	-0.01	7	>999	360	MT20	220/195
TCDL	11.0	Lumber DOL	1.00	BC	0.30	Vert(CT)	-0.06	6-7	>999	240		
BCLL	0.0	Rep Stress Incr	YES	WB	0.21	Horz(CT)	0.01	6	n/a	n/a		
BCDL	7.0	Code	IRC2021/TPI2014	Matrix-AS							Weight: 55 lb	FT = 20%F, 11%E

LUMBER
TOP CHORD 2x4 DF No.2(flat)
BOT CHORD 2x4 DF No.2(flat)
WEBS 2x4 DF Stud(flat)

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.


REACTIONS (lb/size) 6=574/ Mechanical, 8=574/ Mechanical

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-800/0, 3-4=-800/0
BOT CHORD 7-8=0/595, 6-7=0/598
WEBS 2-8=-744/0, 2-7=0/258, 4-7=0/254, 4-6=-746/0

NOTES
1) Refer to girder(s) for truss to truss connections.
2) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
3) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-MF	F6	Floor Supported Gable	1	1	Job Reference (optional)



Scale = 1:20.5

10-0-0

Plate Offsets (X, Y): [1:Edge,0-0-12], [14:Edge,0-0-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.07	Vert(LL)	n/a	-	n/a	999	MT20	220/195
TCDL	11.0	Lumber DOL	1.00	BC	0.01	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0	Rep Stress Incr	YES	WB	0.03	Horiz(TL)	n/a	-	n/a	n/a		
BCDL	7.0	Code	IRC2021/TPI2014	Matrix-AS							Weight: 36 lb	FT = 20%F, 11%E

LUMBER

TOP CHORD	2x4 DF No.2(flat)
BOT CHORD	2x4 DF No.2(flat)
WEBS	2x4 DF Stud(flat)
OTHERS	2x4 DF Stud(flat)

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.

REACTIONS All bearings 7-1-0.
(lb) - Max Grav All reactions 250 (lb) or less at joint(s) 8, 9, 10, 11, 12, 13, 14

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


NOTES

1) All plates are 1.5x4 (||) MT20 unless otherwise indicated.
2) Gable requires continuous bottom chord bearing.
3) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
4) Gable studs spaced at 1-4-0 oc.
5) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
6) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-MF	F7	Floor	4	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:35:29 Page: 1
ID:41AsMLU5rnbEIZ?ZesuUWazhY6q-MEEc_5qiJl2C1Vx2kTEukAoNsID10BHYEyK3F2zUliS



Scale = 1:22.4

10-0-0 10-0-0

Plate Offsets (X, Y): [1:Edge,0-0-12], [3:0-1-8,Edge], [6:0-1-8,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.25	Vert(LL)	0.00	6-7	>999	360	MT20	220/195
TCDL	11.0	Lumber DOL	1.00	BC	0.24	Vert(CT)	-0.07	6-7	>999	240		
BCLL	0.0	Rep Stress Incr	YES	WB	0.12	Horz(CT)	0.00	5	n/a	n/a		
BCDL	7.0	Code	IRC2021/TPI2014	Matrix-AS							Weight: 40 lb	FT = 20%F, 11%E

LUMBER
TOP CHORD 2x4 DF No.2(flat)
BOT CHORD 2x4 DF No.2(flat)
WEBS 2x4 DF Stud(flat)

BRACING
TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD Rigid ceiling directly applied.


REACTIONS (lb/size) 5=399/ Mechanical, 7=399/0-3-8, (min. 0-1-8)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-342/0
BOT CHORD 6-7=0/354, 5-6=0/342
WEBS 2-7=-446/0, 3-5=-469/0

NOTES
1) Refer to girder(s) for truss to truss connections.
2) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
3) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-MF	F8	Floor	2	1	Job Reference (optional)



Scale = 1:35.6

0-1-12

Plate Offsets (X, Y): [2:0-1-8,Edge], [3:0-1-8,Edge], [5:0-1-8,Edge], [7:0-1-8,0-0-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.23	Vert(LL)	n/a	-	n/a	999	MT20	220/195
TCDL	11.0	Lumber DOL	1.00	BC	0.03	Vert(CT)	0.00	5-6	>999	240		
BCLL	0.0	Rep Stress Incr	YES	WB	0.06	Horz(CT)	n/a	-	n/a	n/a		
BCDL	7.0	Code	IRC2021/TPI2014	Matrix-MP							Weight: 29 lb	FT = 20%F, 11%E

LUMBER

TOP CHORD	2x4 DF No.2(flat)
BOT CHORD	2x4 DF No.2(flat)
WEBS	2x4 DF Stud(flat)
OTHERS	2x4 DF Stud(flat)

BRACING

TOP CHORD	Structural wood sheathing directly applied or 3-11-12 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS (lb/size) 5=355/0-3-8, (min. 0-1-8), 6=71/ Mechanical
Max Uplift 6=-17 (LC 4)
Max Grav 5=355 (LC 1), 6=110 (LC 3)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-5=-273/0

NOTES

1) Unbalanced floor live loads have been considered for this design.
2) Refer to girder(s) for truss to truss connections.
3) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 17 lb uplift at joint 6.
4) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
5) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-MF	F9	Floor Supported Gable	1	1	Job Reference (optional)



Scale = 1:27.7

10-0-0

Plate Offsets (X, Y): [8:Edge,0-1-8], [9:0-1-8,0-0-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.06	Vert(LL)	n/a	-	n/a	999	MT20	220/195
TCDL	11.0	Lumber DOL	1.00	BC	0.01	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0	Rep Stress Incr	YES	WB	0.03	Horiz(TL)	n/a	-	n/a	n/a		
BCDL	7.0	Code	IRC2021/TPI2014	Matrix-MR							Weight: 25 lb	FT = 20%F, 11%E

LUMBER

TOP CHORD	2x4 DF No.2(flat)
BOT CHORD	2x4 DF No.2(flat)
WEBS	2x4 DF Stud(flat)
OTHERS	2x4 DF Stud(flat)

BRACING

TOP CHORD	Structural wood sheathing directly applied or 3-11-12 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS All bearings 3-11-12.
(lb) - Max Grav All reactions 250 (lb) or less at joint(s) 5, 6, 7, 8

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


NOTES

1) Gable requires continuous bottom chord bearing.
2) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
3) Gable studs spaced at 1-4-0 oc.
4) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
5) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-MF	F10	Floor	2	1	Job Reference (optional)

Run: 25.10 S May 12 2025 Print: 25.1.0 S May 12 2025 MiTek Industries, Inc. Thu Apr 02 11:35:30 Page: 1
ID:41AsMLU5rnbEIZ?ZesuUWazhY6q-rQo?BRrK43A3feWEIBI7GNLYciaBlfbhTc3doUzUliR



Scale = 1:25.4

10-0-0 10-0-0

Plate Offsets (X, Y): [1:Edge,0-0-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.25	Vert(LL)	n/a	-	n/a	999	MT20	220/195
TCDL	11.0	Lumber DOL	1.00	BC	0.18	Vert(CT)	-0.05	4-5	>999	240		
BCLL	0.0	Rep Stress Incr	YES	WB	0.05	Horz(CT)	0.00	4	n/a	n/a		
BCDL	7.0	Code	IRC2021/TPI2014	Matrix-AS							Weight: 25 lb	FT = 20%F, 11%E

LUMBER

TOP CHORD	2x4 DF No.2(flat)
BOT CHORD	2x4 DF No.2(flat)
WEBS	2x4 DF Stud(flat)

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.

REACTIONS (lb/size) 4=227/ Mechanical, 5=227/0-3-8, (min. 0-1-8)


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES

1) Refer to girder(s) for truss to truss connections.
2) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
3) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-MF	F11	Floor Supported Gable	1	1	Job Reference (optional)



Scale = 1:20.1

10-0-0

Plate Offsets (X, Y): [1:Edge,0-0-12], [8:Edge,0-0-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.07	Vert(LL)	n/a	-	n/a	999	MT20	220/195
TCDL	11.0	Lumber DOL	1.00	BC	0.01	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0	Rep Stress Incr	YES	WB	0.03	Horiz(TL)	n/a	-	n/a	n/a		
BCDL	7.0	Code	IRC2021/TPI2014	Matrix-AS							Weight: 21 lb	FT = 20%F, 11%E

LUMBER

TOP CHORD	2x4 DF No.2(flat)
BOT CHORD	2x4 DF No.2(flat)
WEBS	2x4 DF Stud(flat)
OTHERS	2x4 DF Stud(flat)

BRACING

TOP CHORD	Structural wood sheathing directly applied, except end verticals.
BOT CHORD	Rigid ceiling directly applied.

REACTIONS All bearings 4-1-4.
(lb) - Max Grav All reactions 250 (lb) or less at joint(s) 5, 6, 7, 8


FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES

1) Gable requires continuous bottom chord bearing.
2) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
3) Gable studs spaced at 1-4-0 oc.
4) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
5) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Rodriguez Residence
254084-MF	FGIR	Floor Girder	1	1	Job Reference (optional)



Scale = 1:25.2

10-0-0 10-0-0

Plate Offsets (X, Y): [5:Edge,0-1-8], [6:0-1-8,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.50	Vert(LL)	-0.01	6-7	>999	360	MT20	220/195
TCDL	11.0	Lumber DOL	1.00	BC	0.43	Vert(CT)	-0.07	6-7	>999	240		
BCLL	0.0	Rep Stress Incr	NO	WB	0.37	Horz(CT)	0.01	5	n/a	n/a		
BCDL	7.0	Code	IRC2021/TPI2014	Matrix-MP							Weight: 40 lb	FT = 20%F, 11%E

LUMBER

TOP CHORD	2x4 DF No.2(flat)
BOT CHORD	2x4 DF No.2(flat)
WEBS	2x4 DF Stud(flat)

BRACING

TOP CHORD	Structural wood sheathing directly applied or 5-9-7 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 5=1029/ Mechanical, 7=1011/0-3-8, (min. 0-1-8)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	2-9=-542/0, 3-9=-542/0
BOT CHORD	6-7=0/1090, 5-6=0/542
WEBS	2-7=-1358/0, 2-6=-683/0, 3-6=0/492, 3-5=-1364/0

NOTES

1) Refer to girder(s) for truss to truss connections.
2) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
3) Use Simpson Strong-Tie THA426 (8-16d Girder, 6-16d Truss) or equivalent spaced at 2-0-0 oc max. starting at 1-11-3 from the left end to 3-11-3 to connect truss(es) F2 (1 ply 2x4 DF) to back face of top chord.
4) Fill all nail holes where hanger is in contact with lumber.

LOAD CASE(S) Standard

1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
   Uniform Loads (lb/ft)
   Vert: 5-7=-14, 1-4=-102
   Concentrated Loads (lb)
   Vert: 8=-692, 9=-692