RAILING SUBCONTRACT AGREEMENT

DRAFT FOR REVIEW | November 12, 2026

Project: Rodriguez Residence - Oak Valley Estates Lot 5
746 S Liberty Lane, Kanarraville, Utah

General Contractor: RAC Inc. / RAC Development, Craig Engel
1267 N 1390 W, St. George, UT 84770 | 435-229-7360 | racinc19@gmail.com

Subcontractor: Ironhorse Welding and Design LLC, Attn: Kody
2611 W 200 S, Hurricane, UT 84737 | 435-559-3683 | kody@ironhorseweld.com

1. Contract documents and status

This proposed subcontract incorporates Estimate 1148 dated November 10, 2026 (Exhibit A, attached), together with Kody's November 12, 2026 written clarifications summarized below. These clarifications govern the corresponding estimate provisions. This draft is unsigned and does not authorize fabrication or payment. The parties must confirm the open items on page 2 and sign before proceeding.

2. Scope and contract price

Estimate item	Quantity	Rate	Amount
Custom railing	619 ft	$95.45	$59,083.55
Wall-mounted handrail	70 ft	$21.50	$1,505.00
Travel and installation	40 units	$220.00	$8,800.00
TOTAL ESTIMATE BASIS			**$69,388.55**

Furnish, fabricate and install the quoted railing and handrail system, including gates as confirmed by Kody. Custom railing: 3 x 1.5 inch or 3 x 2 inch top rail; galvanized and powder-coated Banker wire infill; 2.5 x 2.5 x .090 inch posts; 2 x 1.5 inch or 1.5 x 1.5 inch frames. Wall handrail: 1 x 2 inch material. Frames and top rail are mechanically fastened. Final dimensions, tube selections, gate details and connections are subject to approved shop drawings / 3D rendering before fabrication.

Standard powder-coat colors include common colors that do not require special ordering, including the penny vein finish discussed in the email. Final color remains subject to written selection. Kody proposes guardrails at least 36 inches high and handrails 34-38 inches high; final dimensions must satisfy the approved plans and applicable project requirements.

3. Payment and installation timing

Estimate terms: 50% deposit before fabrication, remaining 50% upon completion of fabrication. If installation cannot follow fabrication immediately, RAC retains the quoted $8,800 installation amount while completed fabrication is billed in full. The $8,800 is part of the $69,388.55 estimate, not an additional installation charge. Kody and RAC will confirm the deposit allocation, tax treatment and milestone invoice amounts before execution; no payment is represented as made by this document.

SUBCONTRACT TERMS AND CONFIRMATIONS

4. Coordination, exclusions and schedule

Posts are to be installed before sheathing per the estimate. Ironhorse will coordinate required blocking locations with the other trades. Blocking and its installation are excluded; Ironhorse may provide blocking only if separately requested and priced in an approved written change. Waterproofing post penetrations and connections, including roofing membrane and sealant, is by others. Alterations of subframing to support steel components and site coordination beyond the quoted scope are excluded. RAC will coordinate these prerequisites with Leonard and the responsible trades.

Ironhorse shall verify field conditions before fabrication and identify discrepancies for written resolution. No added-cost work, changed hardware, latches or design shall proceed without RAC's prior written approval of scope and price. Fabrication, post installation and final installation dates will be agreed in writing before work proceeds; lead time was not stated in the November 12 reply.

5. Warranty and required documentation

Per Kody's written clarification, Ironhorse warrants the finish and fabrication for one year from installation. The stated warranty excludes roofing leaks and issues not directly related to fabrication or installation of Ironhorse's product. Before mobilization, provide current contractor-license information, a completed W-9 and certificates of general liability and workers' compensation insurance, with RAC Inc. and the owner named as additional insureds where applicable. Provide appropriate lien waivers with payments. These documentation requirements follow RAC's project subcontract practice and are proposed for review.

6. Items to confirm before signing

Confirm that $69,388.55 is the full installed total, including the applicable tax treatment and quoted travel; identify any proposed additional mobilization before agreement. Confirm the deposit and fabrication-completion invoice amounts while preserving the $8,800 installation holdback when installation is deferred. Confirm fabrication lead time, site visit, blocking and post-installation sequence, final installation date, approved shop drawings and finish selection.

7. Agreement and signatures

The signed agreement, attached estimate and agreed written clarifications will define the subcontract. Amendments and changes require both parties' written agreement. Signature below confirms acceptance only after the open items above have been resolved in writing and attached. No signatures have been supplied or applied.

RAC Inc. / RAC Development
Craig Engel

Signature: _____

Date: _____

Ironhorse Welding and Design LLC
Authorized representative

Signature: _____

Name / title: _____

Date: _____

Source record: Estimate 1148, November 10, 2026; Kody's email, November 12, 2026, subject "Re: Oak Valley Lot 5 - questions on estimate 1148." Original estimate attached as Exhibit A.

Ironhorse Welding and Design LLC

2611 W 200 S

Hurricane, UT 84737 US

+14355593683

kody@ironhorseweld.com

Estimate

ADDRESS

Craig Engel

RAC Development

ESTIMATE 1148

DATE 11/10/2026

DATE	ACTIVITY	DESCRIPTION	QTY	RATE	AMOUNT
	Custom Railing	Quoted as 3"x1.5" or 3x2" Top Rail Banker wire galvanized infill Posts 2.5"x2.5"x.090" Frames as 2"x1.5" or 1.5"x1.5" Dimensions to be finalized for shop drawings. Posts to be installed prior to sheathing per plan. Frames and top rail to be mechanically fastened. Powder coated standard color.	619	95.45	59,083.55
	Handrail - Wall Mount	1"x2" material	70	21.50	1,505.00
	Travel & Installation	Field setting posts, attaching panels/top rail, and installing handrails.	40	220.00	8,800.00

50% Deposit due before proceeding with fabrication. Remaining 50% due upon completion of fabrication. Installation will be billed separately if components cannot be installed immediately following fabrication completion.
Job Name: Rodriguez - Oak Valley Estates #5

TOTAL **$69,388.55**

Exclusions:
2x blocking and installation

Waterproofing any post penetrations or other connections

Alterations of sub framing to support steel components

On site co-ordination beyond necessary for proposed scope

Accepted By

Accepted Date